

Transmittal

245 Main Street Suite 110, Chester, NJ 07930

PROJECT:	North Castle NY - JG Petrucci 2179-99-009	DATE:	7/12/2021
SUBJECT:	94 Business Park Drive	TRANSMITTAL ID:	00006
PURPOSE:	For your use	VIA:	Info Exchange

FROM

NAME	COMPANY	EMAIL	PHONE
Danielle Lescrinier 245 Main Street Suite 110 Chester, NJ 07930	Dynamic Engineering Consultants PC	dlescrinier@dynamicec.com	908-879-9229

ТО

NAME	COMPANY	EMAIL	PHONE
planning@northcastleny. com		planning@northcastleny.com	

REMARKS: Jul

Julie,

Please use the link to download our resubmission documents for 94 Business Park Drive:

- Site Plans
- Banked Option Plan
- SWPPP Report
- Engineering Response Letter

Let us know if you need anything else.

Thank you, Danielle

DESCRIPTION OF CONTENTS

QTY	DATED	TITLE	NOTES
1	7/12/2021	SWPPP - July 2021 FULL.pdf	
1	7/12/2021	Dynamic-94BusinessParkDr-ArmonkNY- SitePlansRev2.pdf	
1	7/12/2021	01 BANKED OPTION PLAN.pdf	
1	7/12/2021	2021-07-12 - Town of North Castle - Response Letter.pdf	

COPIES:

Transmittal

DATE: 7/12/2021 TRANSMITTAL ID: 00006

(Dynamic Engineering Consultants	PC)	
(Dynamic Engineering Consultants	PC)	

Dan Sehnal John DeMartinis afv@venezianox.com akaufman@northcastleNY.com Ko Hung Chan

(Dynamic Engineering Consultants PC)



Dynamic Engineering Consultants, PC 245 Main Street, Suite 110 Chester NJ 07930 T. 908-879-9229

July 12, 2021 Via Email

Town of North Castle Conservation Board 17 Bedford Road Armonk, NY 10504

Attn: Julie Mucker Board Secretary

RE: Armonk Fairview, LLC & Aggro and Brassi, LLC Proposed Warehouse Section 108.03; Block 1; Lot 50 94 Business Park Drive Town of North Castle (Armonk) Westchester County, NY DEC #2179-99-009

Dear Ms. Mucker,

Enclosed please find the following information constituting our resubmission to the Planning Board:

- Signed and Sealed Preliminary and Final Site Plans prepared by our office dated February 19, 2021, revised July 12, 2021;
- Signed and Sealed Banked Option Plan prepared by our office dated February 19, 2021, revised July 12, 2021; and
- Signed and Sealed Stormwater Pollution Prevention Plan Report prepared by our office dated July 2021.

The following are responses to an engineering review letter prepared by Kellard Sessions dated March 5, 2021:

 As illustrated on the plan, the project site is located partially within the FEMA regulated floodplain of the Byram River, a FEMA regulated floodway. As per effective FEMA FIRM Maps, the floodplain is designated as a Zone AE, with a base flood elevation (BFE) of ±Elevation 370.5. While no development is proposed to occur within the floodplain, the applicant will be required to obtain a Floodplain Development Permit, as required by Chapter 177 – Flood Damage Prevention of the Town Code. The Existing Condition Site Plan shall clearly illustrate the boundaries of the floodplain and floodway and include references to the FEMA Effective FIRM Maps and floodplain elevation.

A Floodplain Development permit will be obtained. None of the proposed improvements will be located within the floodplain, as shown on the accompanying engineering drawings.

2. The Byram River flows generally north to south along the eastern property boundary. This watercourse is a locally-regulated wetland/watercourse, as well as a New York State Department of Environmental Conservation (NYSDEC) Class C(T) stream. The plan illustrates a 50 foot buffer; however, Chapter 340, Wetlands and Watercourse Protection of the Town Code requires a 100-foot regulated buffer. Please revise the plan to illustrate this. The regulated buffer area will extend onto the property and, as such, require a local Wetland Permit. In addition, improvements specific to the stormwater management system appear to extend to within 50 feet of the bed and banks of the Byram River. As such, the applicant shall provide confirmation from NYSDEC as to whether an Article 15, Protection of Water Permit will be required.

www.dynamicec.com

Lake Como, NJ • Chester, NJ • Toms River, NJ • Newark, NJ • Newtown, PA • Philadelphia, PA Bethlehem, PA • Allen, TX • Houston, TX • Austin, TX • Delray Beach, FL The 100-foot regulated buffer has been indicated on the plan. There is an approval pending from the Conservation Board for the Wetland Permit. All proposed improvements are located outside of the buffer, so a Protection of Water Permit will not be required.

3. The project site is located within the check zone of NYSDEC Freshwater Wetland, G-2. As such, the applicant shall provide confirmation from the NYSDEC as to whether an Article 24, Freshwater Wetland Permit, will be required for the project. If required, the applicant shall provide a validation map signed by the NYSDEC, establishing the boundaries of the State regulated wetland.

Per correspondence with the NYSDEC, these are not state-regulated wetlands. Therefore, a Freshwater Wetland Permit will not be required.

4. The applicant shall confirm whether the wetland boundary illustrated on the plan has been established in the field with fluorescent, sequentially numbered ribbons. Once confirmed, please notify this office for field verification of the boundary by the Town Wetland Consultant.

The wetland boundary has been identified and verified by the Town Wetland Consultant.

5. We note that the Byram River is a Westchester County controlled stream. Development is proposed within 100 feet of its banks and will require a Westchester County Department of Public Works (WC DPW) Stream Control Permit.

Application for a Stream Control Permit will be submitted following Planning Board Approval.

6. As previously indicated, the plan proposes disturbances within the locally regulated 100-foot buffer of the Byram River and associated fringe wetland area. The applicant will be required to prepare a Wetland Mitigation Plan, providing a minimum mitigation ratio of 2:1, for unavoidable disturbances within the wetland/wetland buffer, as required by Chapter 340, Wetlands and Watercourse Protection of the Town Code. The Wetland Mitigation Plan shall include, at a minimum, a summary table illustrating and quantifying the total area of disturbance for the project, the disturbance area within the wetland and wetland buffer, existing and proposed pervious and impervious surface areas within the wetland and wetland buffer, as well as the total area of wetland mitigation proposed. We recommend that once the plan is developed that the Planning Board refer the plan to the Conservation Board for review and consideration.

The proposed mitigation includes removing invasive species from the wetland area. There is a pending application submitted to the Conservation Board for review.

7. We note that, as required by Town Code, the applicant will be required to provide a long-term monitoring and maintenance plan for the proposed wetland mitigation for a period of at least5 five (5) years. This office will provide standard conditions for this plan for inclusion on the Wetland Mitigation Plan.

A long-term monitoring and maintenance plan for the proposed wetland mitigation will be provided.

8. The site plan indicates available sight line distances for vehicles exiting both proposed driveway locations. The plan, however, should be expanded to illustrate the entirety of the available sight distance, as well as include sight line profiles for these locations. The profile shall be taken from a vehicle 14 feet from the edge of the traveled way, with the driver's eye at 3.5 feet above finish grade, to an object in the road 2 feet above grade. The plan should identify whether any additional existing vegetation along the right-of-way of Business Park Drive will require removal to maintain adequate sight lines.

The plan has been revised to show the sight line profiles. The sight line is complete in the roadway, as there are no obstructions.

9. The applicant should illustrate turning movements, around the proposed building and exiting the site, for fire apparatus vehicles and tractor trailers of a size anticipated to utilize the site. The plan should be referred to the Armonk Fire Department for review of adequate emergency access and location(s) of proposed fire hydrant(s).

The plans have been updated to illustrate turning movements.

10. The plan proposes a total of 150 parking spaces, including six (6) accessible parking spaces, as required by Section 355-56N (1) of the Town Code. For clarity, Site Plan Note No. 8C should be corrected to indicate this as well.

Site Plan Note No. 8C has been revised as required.

11. The plan shall include proposed driveway profiles to demonstrate compliance with Section 355-59, Driveways of the Town Code.

The plan has been revised to show proposed driveway profiles.

12. The applicant has provided a Lighting Plan for consideration by the Planning Board. We note that the proposed fixture height is 25 feet above grade, which appears to be higher than normally accepted by the Board.

Acknowledged.

13. The applicant has provided a Landscape Plan for consideration by the Planning Board. We note that the proposed fixture height is 25 feet above grade, which appears to be higher than normally accepted by the Board.

Our office has received a landscape approval from the ARV. A tree removal summary is shown on the plan.

- 14. The plan proposes approximately 5.2 acres of disturbance, which will require the owner to prepare a Stormwater Pollution Prevention Plan (SWPPP) in accordance with Chapter 267, Stormwater Management of the Town Code, as well as to obtain coverage under the NYSDEC SPDES General Permit (GP-0-20-001) FOR Stormwater Discharge from Construction Activities. The applicant has prepared a Stormwater Management Report and Erosion and Sediment Control Plan for review. We will defer a detailed review of the plan and report until it is developed further to address the following preliminary comments for consideration (our office is available for a technical review meeting if desired).
 - a. The SWPPP shall be revised to acknowledge the requirement for compliance under the General Permit, as well as include discussions related to required inspections and frequency by a Qualified Professional, the need for a Trained Contractor, sequence of construction etc.

The operations & maintenance information is included with the submission of the SWPPP.

b. The SWPPP shall include a draft copy of the Notice of Intent (NOI) and MS4 Acceptance Form for review.

A draft copy of the Notice of Intent (NOI) and MS4 Acceptance Form will be included with the final submission.

c. The proposed water quality treatment does not appear to meet the requirements of the New York State Stormwater Management Design Manual (NYS SMDM) for redevelopment projects (Chapter 9). The plan proposes a closed-pipe detention system to collect roof runoff (Drainage Area, DA-2) with no water quality treatment provided. In addition, water quality treatment is only provided for the rear portion of the parking lot (Drainage Area, DA-3) and provides for direct discharge of stormwater runoff from the front parking area (Drainage Area, DA-3) to the Byram River without the benefit of water quality treatment. The plan must be revised to provide stormwater quality treatment for all areas. Volume and/or peak treatment rate calculations shall be provided for each system.

The plan has been revised to provide stormwater quality treatment for all areas.

d. The water quality sizing calculations appear to only provide for 25% of the required treatment. Unless the plan is revised to include the use of standard stormwater mitigation practices, the plan shall provide 75% of the required water quality treatment for all redeveloped areas and 100% of the required water quality treatment for all newly developed or expanded areas. The water quality volume calculations provided in the SWPPP shall be updated accordingly and include the entire tributary drainage area.

The stormwater management design has been revised to provide water quality treatment for all redeveloped areas.

e. It appears that the proposed detention system, as designed, does not meet the requirements for alternative stormwater treatment practices, as described in the NYS SMDM, specifically as it relates to treatment via permanent pools, baffles or other proprietary method.

The proposed detention system has been revised to comply with NYS SMDM.

f. The SWPPP includes curve number (CN) calculations for existing and proposed drainage areas; however, they appear to be incomplete and do not provide the final resulting CN value. Please revise as necessary.

The CN values have been revised.

g. The hydrologic and hydraulic calculations provided in the SWPPP should include the routing calculations through the detention system and control structure, as well as the water quality treatment units. Include the outlet control structure model data.

These calculations have been included in the Appendix of the Stormwater report.

h. The SWPPP should include pipe capacity calculations demonstrating adequate capacity for the peak discharge flow rates.

Pipe capacity calculations are included within the Appendix of the Stormwater Management report.

i. The proposed stormwater practices do not currently rely on infiltration or underlying soils. As such, deep and percolation soil testing is not required. Should the design of the practices change and require soil testing, please coordinate with this office so that the testing can be witnessed by our office as required.

Acknowledged.

j. The SWPPP shall clearly demonstrate the overflow bypass rate provided by the water quality unit to ensure safe passage of the 100-year design flow.

The Stormwater Management report will be revised to include 100-year design flow following approval of the proposed water quality design.

k. The SWPPP and Erosion and Sediment Control Plan shall include a construction sequence and phasing plan, limiting disturbance for a particular phase of construction to no more than five (5) acres. The phases shall be clearly identified on the stormwater plan.

The Stormwater Management report will be revised to include 100-year design flow following approval of the proposed water quality design.

1. The construction phasing and sequence described on the Stormwater Pollution Prevention Plan (Sheet 8 of 13) shall be expanded based on the phasing described above, as well to include provisions for temporary sediment basins, protection of drainage facilities throughout construction, conversion to allow stormwater mitigation systems to go on-line, wetland mitigation, etc.

The Stormwater Management report will be revised to include 100-year design flow following approval of the proposed water quality design.

m. The plan requires the import of approximately 2,000 cubic yards of material. The erosion and sediment control plan shall clearly illustrate the ability to adequately stage and stockpile this material on site and not require the queuing of trucks within Business Park Drive.

The stockpile location is indicated on the Erosion and Sediment Control plan.

n. The Erosion and Sediment Control Plan should incorporate a temporary construction access road, in lieu of proposing to utilize the existing paved drive, in order to eliminate the potential for off-site sediment transport to Business Park Drive.

The Erosion and Sediment Control plan proposes the use of the existing paved access drive for construction vehicles.

o. The plan should consider the use of temporary sediment basins throughout construction to not only collect sediment from stormwater runoff but to also be used for dewatering activities that may be required. Provide details.

Acknowledged. Details of any sediment basin will be provided if required.

p. According to available New York State Office of Parks, Recreation and Historic Preservation (NYS OPRHP), the project site is located within an archeological sensitive area. As such, the SWPPP shall include confirmation from NYSOPRHP, indicating no adverse impact.

A letter has been received from the New York State Office of Parks, Recreation and Historic Preservation indicating that NYS OPHRP has no concerns regarding the proposed project under SEQRA.

q. The SWPPP shall include a discussion related to long-term operation and maintenance and designate the responsible parties both during and after construction. A Long-Term Maintenance Agreement will be required to be put in place by the owner. A draft agreement should be provided for review by the Town Attorney.

The operation & maintenance information is included with this submission. A maintenance agreement will be drafted and provided when/if final Planning Board approval is obtained.

15. The plan should include profiles for all drainage conveyances to demonstrate adequate cover and slope and that there are no conflicts with other utilities.

The plan has been revised to include profiles.

16. The site plan illustrates a wet tap for the proposed water service. This should be reviewed with the Town Water and Sewer Department as well as any potential requirement for remote metering and backflow protection. The applicant should clarify whether individual services for domestic water and fire protection are required for the building.

The plans have been reviewed by the Town Water and Sewer Departments. A hot box is being proposed per the direction of the Water Department.

17. The applicant proposed reconnection and expansion of the existing gas service for the building. We note that in March 2019, ConEdison imposed a moratorium on new services or expansions to existing gas services. The applicant should provide confirmation from ConEd that the proposed modifications are acceptable. Otherwise, alternative fuel sources should be noted on the plan.

Our office will work with ConEdison to confirm that the proposed modifications are acceptable.

18. The plan shall include a trench restoration detail for all work within the right-of-way of Business Park Drive in accordance with Town Highway Department Standards.

The plan has been updated to include a trench restoration detail in accordance with Town Highway Department standards.

Please process this submission and if you have any questions or require any additional information, do not hesitate to contact our office.

Sincerely,

Dynamic Engineering Consultants, PC

Daniel T. Sehnal, PE

Enclosures

Cc: Henry Szwed Jeff Mandelbaum George Reeves

Jesoninia

Danielle R. Lescrinier

July 12, 2021 Via Email

Town of North Castle Conservation Board 17 Bedford Road Armonk, NY 10504

Attn: Julie Mucker Board Secretary

> RE: Armonk Fairview, LLC & Aggro and Brassi, LLC Proposed Warehouse Section 108.03; Block 1; Lot 50 94 Business Park Drive Town of North Castle (Armonk) Westchester County, NY DEC #2179-99-009

Dear Ms. Mucker,

Enclosed please find the following information constituting our resubmission to the Planning Board:

- Signed and Sealed Preliminary and Final Site Plans prepared by this office dated February 19, 2021, revised July 12, 2021;
- Signed and Sealed Banked Option Plan prepared by this office dated February 19, 2021, revised July 12, 2021;
- Signed and Sealed Stormwater Pollution Prevention Plan Report prepared by this office dated July 2021.
- As illustrated on the plan, the project site is located partially within the FEMA regulated floodplain of the Byram River, a FEMA regulated floodway. As per effective FEMA FIRM Maps, the floodplain is designated as a Zone AE, with a base flood elevation (BFE) of ±Elevation 370.5. While no development is proposed to occur within the floodplain, the applicant will be required to obtain a Floodplain Development Permit, as required by Chapter 177 – Flood Damage Prevention of the Town Code. The Existing Condition Site Plan shall clearly illustrate the boundaries of the floodplain and floodway and include references to the FEMA Effective FIRM Maps and floodplain elevation.

A Floodplain Development permit will be obtained. None of the proposed improvements will be located within the floodplain, as shown on the accompanying engineering drawings.

2. The Byram River flows generally north to south along the eastern property boundary. This watercourse is a locally-regulated wetland/watercourse, as well as a New York State Department of Environmental Conservation (NYSDEC) Class C(T) stream. The plan illustrates a 50 foot buffer; however, Chapter 340, Wetlands and Watercourse Protection of the Town Code requires a 100-foot regulated buffer. Please revise the plan to illustrate this. The regulated buffer area will extend onto the property and, as such, require a local Wetland Permit. In addition, improvements specific to the stormwater management system appear to extend to within 50 feet of the bed and banks of the Byram River. As such, the applicant shall provide confirmation from NYSDEC as to whether an Article 15, Protection of Water Permit will be required.

The 100-foot regulated buffer has been indicated on the plan. There is an approval pending from the Conservation Board for the Wetland Permit. All proposed improvements are located outside of the buffer, so a Protection of Water Permit will not be required.

3. The project site is located within the check zone of NYSDEC Freshwater Wetland, G-2. As such, the applicant shall provide confirmation from the NYSDEC as to whether an Article 24, Freshwater Wetland Permit, will be required for the project. If required, the applicant shall provide a validation map signed by the NYSDEC, establishing the boundaries of the State regulated wetland.

Per correspondence with the NYSDEC, these are not state-regulated wetlands. Therefore, a Freshwater Wetland Permit will not be required.

4. The applicant shall confirm whether the wetland boundary illustrated on the plan has been established in the field with fluorescent, sequentially numbered ribbons. Once confirmed, please notify this office for field verification of the boundary by the Town Wetland Consultant.

The wetland boundary has been identified and verified by the Town Wetland Consultant.

5. We note that the Byram River is a Westchester County controlled stream. Development is proposed within 100 feet of its banks and will require a Westchester County Department of Public Works (WC DPW) Stream Control Permit.

Application for a Stream Control Permit will be submitted following Planning Board Approval.

6. As previously indicated, the plan proposes disturbances within the locally regulated 100-foot buffer of the Byram River and associated fringe wetland area. The applicant will be required to prepare a Wetland Mitigation Plan, providing a minimum mitigation ratio of 2:1, for unavoidable disturbances within the wetland/wetland buffer, as required by Chapter 340, Wetlands and Watercourse Protection of the Town Code. The Wetland Mitigation Plan shall include, at a minimum, a summary table illustrating and quantifying the total area of disturbance for the project, the disturbance area within the wetland and wetland buffer, existing and proposed pervious and impervious surface areas within the wetland and wetland buffer, as well as the total area of wetland mitigation proposed. We recommend that once the plan is developed that the Planning Board refer the plan to the Conservation Board for review and consideration.

The proposed mitigation includes removing invasive species from the wetland area. There is a pending application submitted to the Conservation Board for review.

7. We note that, as required by Town Code, the applicant will be required to provide a long-term monitoring and maintenance plan for the proposed wetland mitigation for a period of at least5 five (5) years. This office will provide standard conditions for this plan for inclusion on the Wetland Mitigation Plan.

A long-term monitoring and maintenance plan for the proposed wetland mitigation will be provided.

8. The site plan indicates available sight line distances for vehicles exiting both proposed driveway locations. The plan, however, should be expanded to illustrate the entirety of the available sight distance, as well as include sight line profiles for these locations. The profile shall be taken from a vehicle 14 feet from the edge of the traveled way, with the driver's eye at 3.5 feet above finish grade, to an object

in the road 2 feet above grade. The plan should identify whether any additional existing vegetation along the right-of-way of Business Park Drive will require removal to maintain adequate sight lines.

The plan has been revised to show the sight line profiles. The sight line is complete in the roadway, as there are no obstructions.

9. The applicant should illustrate turning movements, around the proposed building and exiting the site, for fire apparatus vehicles and tractor trailers of a size anticipated to utilize the site. The plan should be referred to the Armonk Fire Department for review of adequate emergency access and location(s) of proposed fire hydrant(s).

The plans have been updated to illustrate turning movements.

10. The plan proposes a total of 150 parking spaces, including six (6) accessible parking spaces, as required by Section 355-56N (1) of the Town Code. For clarity, Site Plan Note No. 8C should be corrected to indicate this as well.

Site Plan Note No. 8C has been revised as required.

11. The plan shall include proposed driveway profiles to demonstrate compliance with Section 355-59, Driveways of the Town Code.

The plan has been revised to show proposed driveway profiles.

12. The applicant has provided a Lighting Plan for consideration by the Planning Board. We note that the proposed fixture height is 25 feet above grade, which appears to be higher than normally accepted by the Board.

Acknowledged.

13. The applicant has provided a Landscape Plan for consideration by the Planning Board. We note that the proposed fixture height is 25 feet above grade, which appears to be higher than normally accepted by the Board.

Our office has received a landscape approval from the ARV. A tree removal summary is shown on the plan.

- 14. The plan proposes approximately 5.2 acres of disturbance, which will require the owner to prepare a Stormwater Pollution Prevention Plan (SWPPP) in accordance with Chapter 267, Stormwater Management of the Town Code, as well as to obtain coverage under the NYSDEC SPDES General Permit (GP-0-20-001) FOR Stormwater Discharge from Construction Activities. The applicant has prepared a Stormwater Management Report and Erosion and Sediment Control Plan for review. We will defer a detailed review of the plan and report until it is developed further to address the following preliminary comments for consideration (our office is available for a technical review meeting if desired)
 - a. The SWPPP shall be revised to acknowledge the requirement for compliance under the General Permit, as well as include discussions related to required inspections and frequency by a Qualified Professional, the need for a Trained Contractor, sequence of construction etc.

The operations & maintenance information is included with the submission of the SWPPP.

b. The SWPPP shall include a draft copy of the Notice of Intent (NOI) and MS4 Acceptance Form for review.

A draft copy of the Notice of Intent (NOI) and MS4 Acceptance Form will be included with the final submission.

c. The proposed water quality treatment does not appear to meet the requirements of the New York State Stormwater Management Design Manual (NYS SMDM) for redevelopment projects (Chapter 9). The plan proposes a closed-pipe detention system to collect roof runoff (Drainage Area, DA-2) with no water quality treatment provided. In addition, water quality treatment is only provided for the rear portion of the parking lot (Drainage Area, DA-3) and provides for direct discharge of stormwater runoff from the front parking area (Drainage Area, DA-3) to the Byram River without the benefit of water quality treatment. The plan must be revised to provide stormwater quality treatment for all areas. Volume and/or peak treatment rate calculations shall be provided for each system.

The plan has been revised to provide stormwater quality treatment for all areas.

d. The water quality sizing calculations appear to only provide for 25% of the required treatment. Unless the plan is revised to include the use of standard stormwater mitigation practices, the plan shall provide 75% of the required water quality treatment for all redeveloped areas and 100% of the required water quality treatment for all newly developed or expanded areas. The water quality volume calculations provided in the SWPPP shall be updated accordingly and include the entire tributary drainage area.

The stormwater management design has been revised to provide water quality treatment for all redeveloped areas.

e. It appears that the proposed detention system, as designed, does not meet the requirements for alternative stormwater treatment practices, as described in the NYS SMDM, specifically as it relates to treatment via permanent pools, baffles or other proprietary method.

The proposed detention system has been revised to comply with NYS SMDM.

f. The SWPPP includes curve number (CN) calculations for existing and proposed drainage areas; however, they appear to be incomplete and do not provide the final resulting CN value. Please revise as necessary.

The CN values have been revised.

g. The hydrologic and hydraulic calculations provided in the SWPPP should include the routing calculations through the detention system and control structure, as well as the water quality treatment units. Include the outlet control structure model data.

These calculations have been included in the Appendix of the Stormwater report.

h. The SWPPP should include pipe capacity calculations demonstrating adequate capacity for the peak discharge flow rates.

Pipe capacity calculations are included within the Appendix of the Stormwater Management report.

i. The proposed stormwater practices do not currently rely on infiltration or underlying soils. As such, deep and percolation soil testing is not required. Should the design of the practices change and require soil testing, please coordinate with this office so that the testing can be witnessed by our office as required.

Acknowledged.

j. The SWPPP shall clearly demonstrate the overflow bypass rate provided by the water quality unit to ensure safe passage of the 100-year design flow.

The Stormwater Management report will be revised to include 100-year design flow following approval of the proposed water quality design.

k. The SWPPP and Erosion and Sediment Control Plan shall include a construction sequence and phasing plan, limiting disturbance for a particular phase of construction to no more than five (5) acres. The phases shall be clearly identified on the stormwater plan.

The Stormwater Management report will be revised to include 100-year design flow following approval of the proposed water quality design.

1. The construction phasing and sequence described on the Stormwater Pollution Prevention Plan (Sheet 8 of 13) shall be expanded based on the phasing described above, as well to include provisions for temporary sediment basins, protection of drainage facilities throughout construction, conversion to allow stormwater mitigation systems to go on-line, wetland mitigation, etc.

The Stormwater Management report will be revised to include 100-year design flow following approval of the proposed water quality design.

m. The plan requires the import of approximately 2,000 cubic yards of material. The erosion and sediment control plan shall clearly illustrate the ability to adequately stage and stockpile this material on site and not require the queuing of trucks within Business Park Drive.

The stockpile location is indicated on the Erosion and Sediment Control plan.

n. The Erosion and Sediment Control Plan should incorporate a temporary construction access road, in lieu of proposing to utilize the existing paved drive, in order to eliminate the potential for off-site sediment transport to Business Park Drive.

The Erosion and Sediment Control plan proposes the use of the existing paved access drive for construction vehicles.

o. The plan should consider the use of temporary sediment basins throughout construction to not only collect sediment from stormwater runoff but to also be used for dewatering activities that may be required. Provide details.

Acknowledged. Details of any sediment basin will be provided if required.

p. According to available New York State Office of Parks, Recreation and Historic Preservation (NYS OPRHP), the project site is located within an archeological sensitive area. As such, the SWPPP shall include confirmation from NYSOPRHP, indicating no adverse impact.

A letter has been received from the New York State Office of Parks, Recreation and Historic Preservation indicating that NYS OPHRP has no concerns regarding the proposed project under SEQRA.

q. The SWPPP shall include a discussion related to long-term operation and maintenance and designate the responsible parties both during and after construction. A Long-Term Maintenance Agreement will be required to be put in place by the owner. A draft agreement should be provided for review by the Town Attorney.

The operation & maintenance information is included with this submission. A maintenance agreement will be drafted and provided when/if final Planning Board approval is obtained.

15. The plan should include profiles for all drainage conveyances to demonstrate adequate cover and slope and that there are no conflicts with other utilities.

The plan has been revised to include profiles.

16. The site plan illustrates a wet tap for the proposed water service. This should be reviewed with the Town Water and Sewer Department as well as any potential requirement for remote metering and backflow protection. The applicant should clarify whether individual services for domestic water and fire protection are required for the building.

The plans have been reviewed by the Town Water and Sewer Departments. A hot box is being proposed per the direction of the Water Department.

17. The applicant proposed reconnection and expansion of the existing gas service for the building. We note that in March 2019, ConEdison imposed a moratorium on new services or expansions to existing gas services. The applicant should provide confirmation from ConEd that the proposed modifications are acceptable. Otherwise, alternative fuel sources should be noted on the plan.

Our office will work with ConEdison to confirm that the proposed modifications are acceptable.

18. The plan shall include a trench restoration detail for all work within the right-of-way of Business Park Drive in accordance with Town Highway Department Standards.

The plan has been updated to include a trench restoration detail in accordance with Town Highway Department standards.

Please process this submission and if you have any questions or require any additional information, do not hesitate to contact our office.

Sincerely,


Dynamic Engineering Consultants, PC

Daniel T. Sehnal, PE


Danielle R. Lescrinier

Enclosures

Cc: Henry Szwed Jeff Mandelbaum George Reeves



PRELIMINARY AND FINAL SITE PLAN FOR ARMONK FAIRVIEW, LLC & AGGRO AND BRASSI, LLC PROPÓSED WAREHOUSE SECTION 108.03; BLOCK 1, LOT 50; - TAX MAP DATED 6-1-2019 94 BUSINESS PARK DRIVE TOWN OF NORTH CASTLE (ARMONK) WESTCHESTER COUNTY, NEW YORK




VICINITY MAP 1" = 200'

ADJOINING PROPERTY OWNERS LIST

<u>PROPERTY OWNER</u> WESTCHESTER COUNTY IDA ENGEL BURMAN GROUP NEW YORK STATE DEPARTMENT OF TRANSPORTATION (NYSDOT) 165 E BROADWAY MONTICELLO, NY 12701

<u>SECTION</u> <u>BLOCK</u> 108.03 1 108.03 1 108.03 1 INTERSTATE ROUTE 684

PREPARED BY DYNAMIC ENGINEERING CONSULTANTS, P.C. 245 MAIN STREET - SUITE 110 CHESTER, NJ 07930 WWW.DYNAMICEC.COM





AERIAL MAP 1" = 200'


	CHOOL DISTRICT AND Special districts
SCHOOL:	BYRAM HILLS CENTRAL SCHOOL DIST. 553801
FIRE:	FIRE DISTRICT #2
WATER:	WATER DISTRICT NO. 4
SEWER:	SEWER DISTRIC #2

DRAWING IN	IDEX
COVER SHEET	1 of 16
DEMOLITION PLAN	2 of 16
SITE PLAN	3 of 16
GRADING PLAN	4 of 16
DRAINAGE AND UTILITY PLAN	5 of 16
STORM AND SANITARY PROFILE	6 of 16
DRIVEWAY PROFILES	7 of 16
LANDSCAPE PLAN	8 of 16
LIGHTING PLAN	9 of 16
STORMWATER POLLUTION PREVENTION PLAN	10 of 16
CONSTRUCTION DETAILS	11 of 16
CONSTRUCTION DETAILS	12 of 16
CONSTRUCTION DETAILS	13 of 16
CONSTRUCTION DETAILS	14 of 16
CONSTRUCTION DETAILS	15 of 16
VEHICLE CIRCULATION PLAN	16 of 16

		ENGINEERING EARTH SURVEY - TRAFFIC				
		KHC KHC BY				
		2 07/12/21 REVISED REV CONSERVATION BOARD COMMENTS 1 04/08/21 REVISED PER TOWN COMMENTS REV. DATE COMMENTS				
THIS PLAN SET IS FOR PERMITTING PURPOSES ONLY AND MAY NOT BE USED FOR CONSTRUCTION	JED DESIGNED BY: CHECKED BY: CHECKED BY: CHECKED BY: JED DTS BWS	PROJECT: AKMUNN FAIKVIEW, LLV & AUGNU BNADOI, LLV PROPOSED WAREHOUSE SECTION 108.03, BLOCK 1, LOT 50 94 BUSINESS PARK DRIVE Town of North Castle (Armonk) Westchester County, New York				
Know what's Dele Call before y	PROTECT ALL STATES REQU EXCAVATORS, DESIGN PREPARING TO D	NE NUMBERS VISIT:				
LAND DEVE GEO TRAFFIC 24 T: 90	DYNAMIC CONSULTING PERMITTING GEOTECHNICAL PENVIRONMENTAL TRAFFIC SURVEY PLANNING & ZONING GEOTECHNICAL PLANNING & ZONING CASS Main Street, Suite 110 Chester, NJ 07930 T. 908.879.9229 F. 908.879.0222 Offices conveniently located at Chester, New Jersey P. 1732.974.0198 Chester, New Jersey P. 1732.974.0198 Newar, New Jersey P. 1732.974.0198 New Jersey P. 1732.974.0198 New Jersey P. 1722.974.0198 New Jersey P. 1722					
DAN	NIEL T. SE	HNAL				
	ROFESSIONAL ENG EW YORK LICENSE No.					
BRETT W. SKAPINETZ PROFESSIONAL ENGINEER NEW YORK LICENSE No. 087962						
Pf	EW YORK LICENSE No.					
TITLE:	EW YORK LICENSE NO.	HEET				
Pf NE	VER S	HEET 2/19/2021				







GRADING NOTES

- . SITE GRADING SHALL BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE RECOMMENDATIONS SET FORTH IN THE SOILS REPORT REFERENCED IN THIS PLAN SET. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING AND REPLACING ALL SOFT, YIELDING OR UNSUITABLE MATERIALS AND REPLACING WITH SUITABLE MATERIALS AS SPECIFIED IN THE SOILS REPORT. ALL EXCAVATED OR FILLED AREAS SHALL BE COMPACTED TO 95% OF MODIFIED PROCTOR MAXIMUM DENSITY PER <u>A.S.T.M. TEST D-1557</u>. MOISTURE CONTENT AT TIME OF PLACEMENT SHALL NOT EXCEED 2% ABOVE NOR 3% BELOW OPTIMUM. CONTRACTOR SHALL SUBMIT A COMPACTION REPORT PREPARED BY A QUALIFIED SOILS ENGINEER, REGISTERED WITHIN THE STATE WHERE THE WORK IS PERFORMED, VERIFYING THAT ALL FILLED AREAS AND SUBGRADE AREAS WITHIN THE BUILDING PAD AREA AND AREAS TO BE PAVED HAVE BEEN COMPACTED IN ACCORDANCE WITH THESE PLANS AND SPECS AND THE RECOMMENDATIONS SET FORTH IN THE SOILS REPORT.
- . CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF EXISTING TOPOGRAPHIC INFORMATION AND UTILITY INVERT ELEVATIONS PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION. CONTRACTOR TO ENSURE 0.75% MIN. SLOPE AGAINST ALL ISLAND GUTTERS, CURBS AND 1.0% ON ALL CONCRETE SURFACES, AND 1-1/2% MIN. ON ASPHALT, TO PREVENT PONDING. ANY DESCREPANCIES THAT MAY EFFECT THE PUBLIC SAFETY OR PROJECT COST, MUST BE IDENTIFIED TO THE ENGINEER IN WRITING IMMEDIATELY. PROCEEDING WITH CONSTRUCTION WITH DESIGN DISCREPANCIES IS DONE SO AT THE CONTRACTOR'S OWN RISK.
- . PROPOSED TOP OF CURB ELEVATIONS ARE GENERALLY 6" ABOVE EXISTING LOCAL ASPHALT GRADE UNLESS OTHERWISE NOTED. FIELD ADJUST TO CREATE A MIN. OF 0.75% GUTTER GRADE ALONG CURB FACE. ENGINEER TO APPROVE FINAL CURBING CUT SHEETS PRIOR TO INSTALLATION. ✓ 4. SUBBASE MATERIAL FOR SIDEWALKS, CURB, OR ASPHALT SHALL BE FREE OF ORGANICS AND OTHER UNSUITABLE MATERIALS. SHOULD SUBBASE BE DEEMED UNSUITABLE, SUBBASE IS TO BE REMOVED AND FILLED WITH APPROVED FILL MATERIAL COMPACTED TO 95% OPTIMUM DENSITY (AS DETERMINED BY MODIFIED PROCTOR METHOD).
- 5. REFER TO SITE PLAN FOR ADDITIONAL NOTES.

2

E

 \geq


 $|\mathbf{X}|$

V

 \mathcal{A}

B

- 6. IN CASE OF DISCREPANCIES BETWEEN PLANS, THE SITE PLAN WILL SUPERCEDE IN ALL CASES. CONTRACTOR MUST NOTIFY ENGINEER OF RECORD OF ANY CONFLICT IMMEDIATELY. 7. MAXIMUM CROSS SLOPE OF 2% ON ALL SIDEWALKS.
- 8. CONTRACTOR TO ENSURE A MAXIMUM OF 2% SLOPE IN ALL DIRECTIONS IN ADA PARKING SPACES AND ADA ACCESS AISLES. CONTRACTOR TO ENSURE A MAXIMUM OF 5% RUNNING SLOPE AND 2% CROSS SLOPE ALONG ALL OTHER PORTIONS OF ACCESSIBLE ROUTE, WITH THE EXCEPTION OF RAMPS AND CURB RAMPS. CONTRACTOR SHALL CLARIFY ANY QUESTIONS CONCERNING CONSTRUCTION IN ADA AREAS WITH THE ENGINEER PRIOR TO THE START OF CONSTRUCTION.
- . THE OWNER SHALL RETAIN DYNAMIC EARTH, LLC (908–879–7095) OR ALTERNATE QUALIFIED GEOTECHNICAL ENGINEER TO TEST SOIL PERMEABILITY AND PROVIDE CONSTRUCTION PHASE INSPECTIONS OF THE BASIN BOTTOM SOILS AND ANY FILL MATERIALS WITHIN ANY PROPOSED INFILTRATION OR RETENTION BASIN TO COMPARE RESULTS TO DESIGN CRITERIA. 10. CONTRACTOR IS TO REMOVE EXISTING UNSUITABLE OR OVERLY COMPACT SOIL OR ROCK AS NEEDED TO ACHIEVE REQUIRED PERMEABILITY AS DIRECTED BY THE OWNERS GEOTECHNICAL ENGINEER, AND NEW FILL, IF NEEDED, SHALL HAVE AN IN PLACE PERMEABILITY GREATER THAN OR EQUAL TO THE DESIGN CRITERIA.
- 11. CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE OWNER'S GEOTECHNICAL ENGINEER PRIOR TO ONSET OF CONSTRUCTION TO SUBMIT AND CONFIRM THE CONTRACTOR'S PROPOSED MEANS AND MATERIALS AND TO SCHEDULE INSPECTIONS FOR BOTTOM OF BASIN, REMOVAL OF UNSUITABLE SOIL, FILL PLACEMENT, AND FINAL BASIN PERMEABILITY TESTING. € 12. THE CONTRACTOR IS RESPONSIBLE FOR AS-BUILT PLANS AND GRADE CONTROL UNLESS DEFINED OTHERWISE ELSEWHERE IN THE CONTRACT DOCUMENTS.



CALE: (H) 1"=30'

2179-99-009


PROJECT No:

HEFT No:

02/19/2021

OF 16

<u>GRAPHIC SCALE</u>



EXISTING UTILITY NOTES

EXISTING WATER SERVICE NOTE: CONTRACTOR TO LOCATE AND UTILIZE EXISTING WATER SERVICE CONNECTION IF FEASIBLE. OTHERWISE REMOVE EXISTING WATER SERVICE LINE AND CAP AT MAIN IN R.O.W. IN ACCORDANCE WITH THE LOCAL WATER COMPANY REQUIREMENTS. TERMINATION AT THE MAIN MUST BE APPROVED BY THE LOCAL WATER COMPANY PRIOR TO COMPLETION. IF THE EXISTING WATER SERVICE CAN NOT BE UTILIZED, THE NEW SERVICE IS TO BE COORDINATED AND VERIFIED FOR LOCATION WITH THE LOCAL WATER COMPANY. CONTRACTOR SHALL OBTAIN ALL REQUIRED STREET OPENING PERMITS FOR REMOVAL OF EXISTING SERVICE AND INSTALLATION OF NEW SERVICE

EXISTING GAS SERVICE NOTE: CONTRACTOR TO LOCATE AND UTILIZE EXISTING GAS SERVICE CONNECTION IF FEASIBLE. OTHERWISE REMOVE EXISTING GAS SERVICE LINE AND CAP AT MAIN IN R.O.W. IN ACCORDANCE WITH THE LOCAL GAS COMPANY REQUIREMENTS. TERMINATION AT THE MAIN MUST BE APPROVED BY THE LOCAL GAS COMPANY PRIOR TO COMPLETION. ANY NEW SERVICE IS TO BE COORDINATED AND VERIFIED FOR LOCATION WITH THE LOCAL GAS COMPANY. THE CONTRACTOR SHALL OBTAIN ALL REQUIRED STREET OPENING PERMITS FOR REMOVAL OF EXISTING SERVICE AND INSTALLATION OF NEW SERVICE.

/ SANITARY SEWER SERVICE NOTE: CONTRACTOR TO LOCATE AND UTILIZE EXISTING SEWER SERVICE CONNECTION IF OF ADEQUATE SIZE AND INTEGRITY AND ACCEPTABLE TO LOCAL SEWER AUTHORITY. OTHERWISE CONTRACTOR TO REMOVE EXISTING SEWER SERVICE LINE AND CAP / AT MAIN IN R.O.W. IN ACCORDANCE WITH THE LOCAL SEWER AUTHORITY REQUIREMENTS. TERMINATION AT THE MAIN MUST BE APPROVED BY THE LOCAL SEWER AUTHORITY PRIOR TO COMPLETION. IF EXISTING SEWER SERVICE CAN NOT BE UTILIZED THEN THE NEW SERVICE IS TO BE COORDINATED AND VERIFIED FOR LOCATION WITH THE LOCAL SEWER AUTHORITY. CONTRACTOR SHALL OBTAIN ALL REQUIRED & STREET OPENING PERMITS FOR REMOVAL OF EXISTING SERVICE AND INSTALLATION OF NEW SERVICE.

UTILITY NOTES

R

 \geq


-

- LOCATION OF ALL EXISTING AND PROPOSED SERVICES ARE APPROXIMATE AND MUST BE CONFIRMED INDEPENDENTLY WITH LOCAL UTILITY COMPANIES PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION OR EXCAVATION. SANITARY SEWER AND ALL OTHER UTILITY SERVICE CONNECTION POINTS SHALL BE CONFIRMED INDEPENDENTLY BY THE CONTRACTOR IN FIELD PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. ALL DISCREPANCIES SHALL BE REPORTED IMMEDIATELY IN WRITING TO THE ENGINEER. CONSTRUCTION SHALL COMMENCE BEGINNING AT THE LOWEST INVERT (POINT OF CONNECTION) AND PROGRESS UP GRADIENT. INTERFACE POINTS (CROSSINGS) WITH EXISTING UNDERGROUND UTILITIES SHALL BE FIELD VERIFIED BY TEST PIT PRIOR TO COMMENCEMENT OF CONSTRUCTION
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY UTILITY "ONE-CALL" NUMBER 72 HOURS PRIOR TO ANY EXCAVATION ON THIS SITE. CONTRACTOR SHALL ALSO NOTIFY LOCAL WATER & SEWER DEPARTMENTS TO MARK OUT THEIR UTILITIES.
- . REFER TO ARCHITECTURAL DRAWINGS FOR EXACT BUILDING UTILITY CONNECTION LOCATIONS. WHERE CONFLICTS EXIST WITH THESE SITE PLANS, ENGINEER IS TO BE NOTIFIED PRIOR TO CONSTRUCTION TO RESOLVE SAME. SERVICE SIZES TO BE DETERMINED BY ARCHITECT
- . WATER SERVICE MATERIALS SHALL BE SPECIFIED BY THE LOCAL UTILITY COMPANY. CONTRACTORS PRICE FOR WATER SERVICE SHALL INCLUDE ALL FEES AND APPURTENANCES REQUIRED BY THE LEGITLE OF PROVIDE A COMPLETE WORKING SERVICE. 5. ALL WATER MAIN SHALL BE CEMENT-LINED, CLASS 52 DUCTILE IRON PIPE, UNLESS OTHERWISE DESIGNATED.
- 5. THE MINIMUM DIAMETER FOR DOMESTIC WATER SERVICES SHALL BE 1 INCH.
- 2. SEWER MAINS SHALL BE SEPARATED FROM WATER MAINS BY A DISTANCE OF AT LEAST 10 FEET HORIZONTALLY. WHERE THIS IS NOT POSSIBLE, THE PIPES SHALL BE IN SEPARATE TRENCHES WITH THE SEWER MAIN AT LEAST 18 INCHES BELOW THE WATER MAIN. ALL SEWER MAINS SHALL BE SDR-35 PVC PIPE UNLESS OTHERWISE DESIGNATED.
- 8. ALL SEWER PIPE INSTALLED WITH LESS THAN 3 FEET OF COVER, GREATER THAN 20 FEET OF COVER OR WITHIN 18 INCHES OF A WATER MAIN SHALL BE CONSTRUCTED OF DUCTILE IRON PIPE. ALL DUCTILE IRON SEWER PIPE SHALL BE CEMENT-LINED, CLASS 52 PIPE, FURNISHED WITH SEWER COAT, OR APPROVED EQUAL. 9. WHERE SANITARY SEWER LATERALS ARE GREATER THAN 10' DEEP AT CONNECTION TO THE SEWER MAIN, CONCRETE DEEP LATERAL
- CONNECTIONS ARE TO BE UTILIZED. 10. THE CONTRACTOR IS RESPONSIBLE FOR THE STABILIZATION OF THE EXISTING SEWER MAIN, STRUCTURES AND APPURTENANCES DURING CONNECTION.
- 11. LOCATION & LAYOUT OF GAS, ELECTRIC & TELECOMMUNICATION UTILITY LINES AND SERVICES SHOWN ON THESE PLANS ARE SCHEMATIC IN NATURE. ACTUAL LOCATION & LAYOUT OF THESE UTILITIES & SERVICES ARE TO BE PER THE APPROPRIATE UTILITY PROVIDER.
- 12. ROOF LEADER COLLECTION PIPING ARE CONCEPTUAL IN NATURE AND ARE NOT FOR CONSTRUCTION. ACTUAL ROOF LEADER COLLECTION PIPING IS TO BE COORDINATED W/ ARCHITECTURAL PLANS FOR EACH INDIVIDUAL BUILDING. ALL ROOF LEADER COLLECTION PIPING SHALL BE SCHEDULE 40 PVC UNLESS OTHERWISE DESIGNATED.
- 13. ALL SEWER AND WATER FACILITIES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE REGULATORY AUTHORITY'S RULES AND REGULATIONS. 14. ALL PROPOSED UTILITIES TO BE INSTALLED UNDERGROUND UNLESS OTHERWISE NOTED.
- 15. MANUFACTURED REINFORCED CONCRETE STORM PIPE TO CONFORM TO ASTM C-76, CLASS III, UNLESS OTHERWISE DESIGNATED. MANUFACTURED REINFORCED CONCRETE ELLIPTICAL STORM PIPE TO CONFORM TO ASTM C-507, CLASS HE-III, UNLESS OTHERWISE DESIGNATED. REINFORCED CONCRETE STORMWATER PIPE TO BE INSTALLED IN ACCORDANCE WITH AMERICAN CONCRETE PIPE ASSOCIATION INSTALLATION GUIDELINES AND MORTAR OR PREFORMED FLEXIBLE JOINT SEALANTS IN ACCORDANCE WITH ASTM C 990 TO BE UTILIZED TO PROVIDE A SILT-TIGHT JOINT. WHERE SPECIFICALLY INDICATED, REINFORCED CONCRETE STORM PIPE JOINTS SHALL BE WATERTIGHT AND CONFORM TO ASTM C-443.
- 16. HDPE DRAINAGE PIPE SHALL HAVE A SMOOTH WALL INTERIOR WITH ANNULAR EXTERIOR CORRUGATIONS AND CONFORM TO ASTM F2306. SOLID PIPE SHALL HAVE GASKETED WATER-TIGHT JOINTS MEETING THE REQUIREMENTS OF ASTM F2306 AND ASTM D3212. PERFORATED PIPE SHALL HAVE GASKETED SILT-TIGHT JOINTS MEETING THE REQUIREMENTS OF ASTM F2306 AND ASTM F477. HDPE PIPE SHALL BE FROM A MANUFACTURER WHO IS AN EASTERN STATES CONSORTIUM (ESC) QUALIFIED MANUFACTURER OF HDPE PIPE AND INSTALLED IN ACCORDANCE WITH PIPE MANUFACTURE RECOMMENDATIONS.
- 17. HP DRAINAGE PIPE SHALL HAVE A SMOOTH WALL INTERIOR WITH ANNULAR EXTERIOR CORRUGATIONS AND CONFORM TO ASTM F2736 (12"-30" PIPE) AND ASTM F2881 (36"-60" PIPE). PIPE SHALL HAVE GASKETED WATER-TIGHT JOINTS MEETING THE REQUIREMENTS OF ASTM D3212 AND ASTM F477. FIELD WATERTIGHTNESS PERFORMANCE VERIFICATION MAY BE ACCOMPLISHED IN ACCORDANCE WITH ASTM F2487. HP PIPE SHALL BE FROM A MANUFACTURER WHO IS AN EASTERN STATES CONSORTIUM (ESC) QUALIFIED MANUFACTURER OF HP STORM PIPE AND INSTALLED IN ACCORDANCE WITH PIPE MANUFACTURER RECOMMENDATIONS.
- 8. PIPE LENGTHS ON THIS PLAN HAVE BEEN MEASURED AS THE DISTANCE BETWEEN THE CENTER POINT OF THE 2 STRUCTURES. ACTUAL PHYSICAL PIPE LENGTH FOR INSTALLATION IS EXPECTED TO BE LESS AND SHOULD BE ACCOUNTED FOR BY THE CONTRACTOR ACCORDINGLY.


<u>GRAPHIC SCALE</u>

(IN FEET)


1 INCH = 30 FT.




OF 16




− 11:53 AM, By: decfolders\data\l 07/12/21 decpc.local ΰŹ





OF 16



ക്

11:54

0.1	0.1	<u>U.1</u>	0.1	0.1	0.1	0.1	0.1	0.1														1			-
+ 0.1		ECTION 10 BLOCK + LOT 49 MONK BUSIN	1	0.1 R ^{+0.1}	⁺ 0.1		+ 0.1	+ 0.1	+ 0.1	+ 0.1	+ 0.1	+ 0.1	+ 0.1							-	- REE	WETLINDS FL FIELD BAR FOUND POINT	ng placed by Located on	0THERS 12/8/20 (TYP.)	
+ <u>0.2</u>		_ 			<u>575</u> 54 + _{0.2} 41	4' <u>30"E</u> 5 ₊ 47'		<u>+</u> 2	+0.2	+ 0.2	+ 0.1	+ 0.1	+ 0.1	+ 0.1	+ 0.1						100 0'			A13	
+ <u>0.4</u>	⁺ 0.4	<u>+</u>	±	+04	+ 0.4	⁺ 0.4	+	+ 0.4	+0.4	+0.3	+0.3	+ 0.3	 0.3	+0.2		<u>+</u> 0.1	⁺ 0.1			55"W	00.08		50.0'		
+ <u>0.7</u>	+ 0.7	+ <u>0.9</u>	+1.1	+09	⁺ 0.7	+ 0.7		1.0	<u>+</u> .8	+0.6	+ 0.6	+0.7	⁺ 0.6	+	1.7 4 •		±22	+ 0.1		S18° 58'	80.0	<u> </u>	REAM BUFFER		1
+ 1.5	†.5	†.7	⁺ 1.6	⁺ 1.6	⁺ 1.5	[†] .5	⁺ 1.6	†.6	†.6	+ 1.4	†.6	†. <i>8</i>	⁺ 1.4	†.6	†.9	+2.6	†1.9		+ 0 :1	ی 					ļ
+ 1.5	†.7	+2.1	+ 1.7	+ 2.2	⁺ 1.5	⁺ 1.6	+ 2.0	†.6	+ 2.1	⁺ 1.5	+ 2.7	+ 3.4	+ <u>2</u> .6	+ 2.7	+2.5	+ <u>3</u> .0	+ _{3.7}			· · · · · · · · · · · · · · · · · · ·	/ /- MONUMEN	IT	A12 		,
+3.2	+ 2.4	†.6	<i>1.5</i>	1.5		4# 25	†.6	1.5	1.5	+ 2.8	4.0	+ 3.4	+ 2.9	+2.9	2.6	+ 2.7	**************************************	*_2.2			FOUND	//	;		
E	•				E							+30	+	+2.5	+2.5	+ 2.1	+ 1.8	<i>†</i> .4	+ 3	- A3-			A11	, ,	
											• D		+ <u>2.7</u>	+ <u>2.5</u>	2.2	+ 1.8	f	†. <u>3</u> .	+; }				4		1
											-2.6	+3.4	⁴ [†] 3.9 [△] 2.9 [△]	2.8	+2.1	+ 1.6	17 <u>.8</u>	7.6	+ 1.7		+0.1		A10		
											2.9	+ <u>3</u> .5		. +2.9	+2.2	<i>†.6</i>	8	⁺ 2.0	+ 2:3	7.5	1⁺ <i>0.</i> r				
											2.3	+ 3.3		z +2.5	⁺ 1.9	† .6	†.8 1.8	+2.6.	+ <u>3</u> .4		ф. <u>2</u>	00			
											D	+ <u>3</u> .6	+∆ 4. 2.7 ∢ ∆	2.4	†. <i>7</i>	+ 1.4	[†] .6	⁺ 2.1	+ 2:7	1.6				,	\setminus
											<i>2.3</i>	+ <u>3</u> .2	+ 2.5 • 24 •	. +2.4	†.7	⁺ 1.3	†.5 \	7.6 •	+ 1.9	*/ //2 ······			Z		
											, <i>3.0</i>	+ <u>3</u> .4	±42.9		⁺ 1.9	† <i>1.3</i>	† <i>1.2</i>	1.2	† <i>1.8</i>	. , ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		\	UTE (١
											2.9	+3.3	* + ^A 2.8		†. <i>8</i>	⁺ 1.3	⁺ 1.3	+ <u>+</u> +	+ 1.8				ROUTE BLC R.O.W.)		
											<i>3.2</i>	+ <u>-</u> 3.4	+ 4 2.4 4 4	2.2	†.7	†.4	⁺ 1.6	†.8 \	+2.1			`\	TE ROU WIDTH PUBLIC R.O.W.)	AB	4
	P	ROPOSED 150 16	71,574 PARKING LOADING	SF WAREH SPACES SPACES	IOUSE						D 3.0	+ 3.3	△	△ ≰	†. <i>8</i>	†.5	⁺ 1.8	+2.4 V.	+ <u>3.2</u>	֠:9.	22				
											<i>3.0</i>	+ 3.3		2.7	+2.0	<i>†.6</i>	†. <i>8</i>	+ 2.3	+ 3.1.	+ B 1.8			INTERST		
												∎ ₄, ⁺ <i>3.3</i>	±4.2.9 ⊿ ⊲. ⊿	2.8	+ 2.0	†.4	⁺ 1.6	†. <i>8</i>	+2.9		0.1		LN		
											2.4	+ 3.2	≠ <u>+</u> 2.54	* <u>*</u> + <u>2.3</u>	⁺ 1.6	†.2	⁺ 1.3	†. <i>3</i>	† _{1.8}		1. 1 . 1				
											Đ	+ <u>3.5</u>	* * 2.5 _ 4 _ 4	+ 2.3	⁺ 1.5	†.2	⁺ 1.1	+ 1.2	†.9	+ <u>0.9</u>	+ 0.1		N.Y.S		
											2.7	+ <u>3.2</u>	2.6	+2.5	<i>†.8</i>	† 1.4	⁺ 1.6	⁺ 1.6	+2.0 I	1 1 1 2 3 1	0.1				
											3.4	+ 3.3	±2.9 ₫	2.8	+ 2.1	†. <i>6</i>	†. <i>7</i>	+ 2.3	⁺ 2.8	+	1+				
											I∐ 	* <u></u>	±2.7	2.6	1.9	⁺ 1.6	†. <i>9</i>	⁺ 2.6	+3.5	B	1. ta2				
											, + <u>3</u> 5 •	+ 3.4	<u>+</u> 2.4		=- +.7	+ 1.5	+ 1.8	+ 2.1	+ 2.4; 		1.0	, fo			
- 74 -			Î a 71		÷	i /ı						+2.8	+ 2.1	+2.0	7.6	+ 1.5	+ 1.8	[†] .8	+2.1						
+ <u>+</u>	+ - 2.3 1 4		⁴ ∕ +¶4 1.5	+	+ 2.94	a 2.4 △ a	<u> </u>	+ 1.5	<u></u>	+ <u>2.7</u>	E + 3	+ <i>3.2</i>	+2.4	+2.2	+2.0	+ 1.8	†.9	1.7. 1.7.	7.8	- - 0.8		.5 fc			
D ⁺ _{1.5}	†.7	+2.1	+ 1.7	+ 2.3	+ 1.5	+ 1.7	+ 2.1	+ 1.6	+2.2	+ 1.5	• + 2.9 •	+ 3.2	+2.1	+ 1.9	+2.0	+2.0	+	<i>1:8</i>	† 1.5		+ 1,0,2	25 f¢		/	/
+ 1.4	+ 1.4	⁺ 1.5	†. <i>6</i>	†.5	⁺ 1.4	+ 1.4	†.5	+ 1.6	⁺ 1.5	⁺ 1.4	⁺ 1.5	⁺ 1.6	⁺ 1.2	+ 1.3	†.7	+2.4	+3.0.	- <u>+</u> 2-6 	. 1.7.		1. 				
+0.6	+0.6	+0.8	т. <i>0</i>	+ 0.8	+0.6	+0.6	+0.8	+ 1.0	+0.8	+ <u>0.6</u>	- <u>0</u> 5 0	<u>+</u> 0.6	+0.6	* <u>*</u> ,*	+2/0	+ 2.5	+ 37 5		÷2.1	REBAR			~~~~ ^{A4}	, ,	/
+ 		4' + <u>30</u> "W 97.18'	+ 0.4	- ⁺ 0.4	+ 0.3	<u>+</u>	+0.4	+0.4	+ <u>0.4</u>	<u> </u>	3		* 0.2	- 0.2	0.2	0.2		0.3	т D.1	<u></u> <u>0</u> 1		60 21			
<u><u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u></u></u>	. <u>-+</u>	+ 	+ <u>0.2</u>		0.2	• <u>+</u> <u>0.2</u>	+ <u>0.2</u>	+ 	<u>+</u> 0.2	<u>+</u> 0.2	⁺ 0.1	<u>+</u> 0.1	<u>+</u> 1	<u>+</u> 0.1	<u>+</u>	<u> </u>	<u>+</u> 0.1	- <u>+</u> 0.1		©		A3			
ION 108.03 LOCK+1 LOT 51	+ 0.1	+ 0.1	+ 0.1	+ 0.1	+ 0.1	+0.1	+ 0.1	+ 0.1	+ 0 .1	+ 0.1	+0.1	+ 0.1	+ 0.1	+ 0.1			_				¹²	· · · ·			
K BUSINESS (⁺ 0.1	+0.1	+ 0.1	+ 0.1	+ 0.1	+ 0.1	+ 0.1	⁺ 0.1													A1			/		
																/	/								
																/ /									

Lum. Watts	Arr. Watts	Lum. Lumens	LLF
133.427	133.427	10544	0.950
133.603	133.603	11665	0.950
135.639	135.639	15467	0.950
135.583	135.583	15086	0.950
84	84	10544	0.950
	133.427 133.603 135.639 135.583	133.427 133.427 133.603 133.603 135.639 135.639 135.583 135.583	133.427 133.427 10544 133.603 133.603 11665 135.639 135.639 15467 135.583 135.583 15086

GENERAL NOTES

- 1. THIS LIGHTING PLAN ILLUSTRATES ILLUMINATION LEVELS CALCULATED FROM LABORATORY DATA TAKEN UNDER CONTROLLED CONDITIONS IN ACCORDANCE WITH ILLUMINATING ENGINEERING SOCIETY OF NORTH AMERICA (IESNA) APPROVED METHODS. ACTUAL SITE ILLUMINATION LEVELS AND PERFORMANCE OF LUMINARIES MAY VARY DUE TO VARIATIONS IN WEATHER, ELECTRICAL VOLTAGE, TOLERANCE IN LAMPS, AND OTHER RELATED VARIABLE FIELD CONDITIONS.
- 2. ALL EXISTING CONDITIONS LIGHTING LEVELS ARE REPRESENTATIVE OF AN APPROXIMATION UTILIZING LABORATORY DATA FOR SIMILAR FIXTURES AND/OR ACTUAL FIELD MEASUREMENTS TAKEN WITH A LIGHT METER. DUE TO FACTORS SUCH AS FIXTURE MAINTENANCE, EQUIPMENT TOLERANCES, WEATHER CONDITIONS, ETC., ACTUAL LIGHTING LEVELS MAY DIFFER AND THE LIGHTING LEVELS DEPICTED ON THIS PLAN SHOULD BE CONSIDERED AS APPROXIMATE.

<u>GRAPHIC SCALE</u>

(IN FEET)

1 INCH = 30 FT.

- 3. CONDUITS SHALL BE INSTALLED A MINIMUM OF 2 FEET BEHIND GUIDERAIL POSTS.
- 4. ALL WIRING METHODS AND EQUIPMENT CONSTRUCTION SHALL CONFORM TO THE CURRENT NATIONAL ELECTRICAL CODE.
- 5. REFER TO ARCHITECTURAL PLANS FOR SITE LIGHTING DIAGRAM.
- 6. TIME OF USE, DUSK TO DAWN, 7 DAYS.

2


E


 \mathbf{Z}

V

R


B








COPYRIGHT © 2021 – DYNAMIC ENGINEERING CONSULTANTS, PC – ALL RIGHTS RESERVED


COULEBORION & GEDIMENT CONTROL NOTES	UEu
 SOIL EROSION & SEDIMENT CONTROL NOTES 1. ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE INSTALLED IN ACCORDANCE WITH THE STATE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL, AND WILL BE INSTALLED IN PROPER SEQUENCE AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED. 2. ANY DISTURBED AREA THAT WILL BE LEFT EXPOSED FOR MORE THAN SEVEN (7) DAYS AND NOT SUBJECT TO CONSTRUCTION TRAFFIC SHALL IMMEDIATELY RECEIVE A TEMPORARY SEEDING. IF THE SEASON PROHIBITS TEMPORARY SEEDING, THE DISTURBED AREA WILL BE MULCHED WITH SALT HAY OR EQUIVALENT AND BE BOUND IN ACCORDANCE WITH THE STATE STANDARDS (I.E. PEG AND TWINE, MULCH NETTING, OR LIQUID MULCH BINDER). 	YNAMI GINEERING - EAR
3. IMMEDIATELY FOLLOWING INITIAL DISTURBANCE OR ROUGH GRADING, ALL CRITICAL AREAS SUBJECT TO EROSION WILL RECEIVE A TEMPORARY SEEDING IN COMBINATION WITH STRAW MULCH OR A SUITABLE EQUIVALENT, AT A RATE OF 2 TONS PER ACRE. ACCORDING TO STATE STANDARDS.	
4. TEMPORARY BERMS ARE TO BE INSTALLED ON ALL CLEARED ROADWAYS AND EASEMENT AREAS IN ACCORDANCE WITH THE STATE STANDARDS. 5. A SUB-BASE COURSE WILL BE APPLIED IMMEDIATELY FOLLOWING ROUGH GRADING AND INSTALLATION OF IMPROVEMENTS IN ORDER TO STABILIZE DRIVEWAYS AND PARKING AREAS. IN AREAS WHERE NO UTILITIES ARE PRESENT, SUB-BASE WILL BE INSTALLED WITHIN 15 DAYS OF PRELIMINARY	
GRADING. 6. THE SITE SHALL AT ALL TIMES BE GRADED AND MAINTAINED SUCH THAT ALL STORM WATER RUN–OFF IS DIVERTED TO SOIL EROSION MID SEDIMENT CONTROL FACILITIES.	COMMENTS
7. ANY STEEP SLOPES RECEIVING PIPELINE INSTALLATION WILL BE BACK FILLED AND STABILIZED DAILY, AS THE INSTALLATION PROCEEDS (I.E. SLOPES GREATER 3:1).	BOARD
8. ALL SEDIMENTATION STRUCTURES WILL BE INSPECTED AND MAINTAINED ON A REGULAR BASIS. 9. STOCKPILES ARE NOT TO BE LOCATED WITHIN 50' OF A FLOOD PLAIN, SLOPE, ROADWAY, OR DRAINAGE FACILITY. THE BASE OF ALL STOCKPILES	CONSERVATION
MUST BE PROTECTED BY A HAY BALE BARRIER OR SEDIMENT FENCE. 10. A CRUSHED STONE VEHICLE WHEEL CLEANING BLANKET WILL BE INSTALLED IMMEDIATELY AFTER INITIAL SITE DISTURBANCE AND WILL BE INSTALLED WHEREVER A CONSTRUCTION ACCESS ROAD INTERSECTS ANY PAVED ROADWAY. BLANKET SHALL BE 1–1/2" TO 2" CRUSHED STONE AND AT LEAST 30' X 100', AND MUST BE UNDERLAIN WITH A SUITABLE SYNTHETIC SEDIMENT FILTER FABRIC AND MAINTAINED.	ER TOWN & PER TOWN Z
 MAXIMUM SLIDE SLOPES OF ALL EXPOSED SURFACES SHALL NOT EXCEED 3:1 UNLESS OTHERWISE APPROVED. ANY INDIVIDUAL ACCESS ROADS OR DRIVES MUST BE STABILIZED WITH 2-1/2" CRUSHED STONE PRIOR TO COMMENCEMENT OF CONSTRUCTION IN THAT AREA. 	I REVISED PER COMMENTS
13. PAVED ROADWAYS MUST BE KEPT CLEAN AT ALL TIMES. 14. ALL CATCH BASIN INLETS MUST BE PROTECTED WITH A CRUSHED STONE OR HAY BALE FILTER (SEE DETAIL).	07/12/21 04/08/21
15. CONDUIT OUTLET PROTECTION MUST BE INSTALLED AT ALL REQUIRED OUT FALLS PRIOR TO THE DRAINAGE SYSTEM BECOMING OPERATIONAL.	RE<. 1 2
 ALL DE-WATERING OPERATIONS MUST DISCHARGE DIRECTLY INTO A SEDIMENT FILTER AREA. THE SEDIMENT FILTER SHALL BE COMPOSED OF A SUITABLE SEDIMENT FILTER FABRIC (SEE DETAIL). PERMANENT VEGETATION TO BE SEEDED OR SODDED ON ALL EXPOSED AREAS WITHIN TEN (10) DAYS AFTER FINAL GRADING. MULCH TO BE 	
USED AS NECESSARY FOR PROTECTION UNTIL SEEDING IS ESTABLISHED. 18. ALL UNSTABILIZED AREAS TO BE SPRINKLED WITH WATER UNTIL WET AT THE BEGINNING OF EACH DAY TO CONTROL DUST. 19. ANY SOIL HAVING A PH OF 4 OR LESS OR CONTAINING IRON SULFIDES SHALL BE COVERED WITH A MINIMUM OF 12" OF SOIL HAVING A PH OF 5 OR MORE PRIOR TO SEEDBED PREPARATION.	IG PURPOSIES GONSTRUGTION CHECKED BY: AND BRASSI, LLC
20. AT THE TIME OF SITE PREPARATION FOR PERMANENT VEGETATIVE STABILIZATION, ANY SOIL NOT SUITABLE TO SUPPORT ADEQUATE VEGETATIVE GROUND COVER WILL BE REMOVED OR TREATED IN SUCH A WAY TO PERMANENTLY ADJUST THE SOIL CONDITIONS AND RENDER IT SUITABLE FOR VEGETATIVE GROUND COVER. (IF REMOVAL OR TREATMENT OF THE SOIL WILL NOT PROVIDE SUITABLE CONDITIONS, NON-VEGETATIVE MEANS OF DEPLATIVE GROUND STABILIZATION WILL HAVE TO BE DROVIDED.)	MTTIR SOR OT 50
PERMANENT GROUND STABILIZATION WILL HAVE TO BE PROVIDED.) 21. ALL SITE WORK FOR SITE PLANS WILL HAVE TO BE COMPLETED PRIOR TO THE SOIL CONSERVATION DISTRICT ISSUING A REPORT OF COMPLIANCE FOR THE ISSUANCE OF A CERTIFICATE OF OCCUPANCY BY THE MUNICIPALITY.	CHECKED BY: USE AG CHECKED BY: DRIVE STLE (ARN Y, NEW)
22. THE APPROVING AUTHORITY MAY REQUEST ADDITIONAL MEASURES TO MINIMIZE ON OR OFF SITE EROSION PROBLEMS DURING CONSTRUCTION AND SHALL BE NOTIFIED IN WRITING 72 HOURS PRIOR TO THE COMMENCEMENT OF ANY LAND DISTURBANCE.	FOR BER CAST ARK DI ARK DI ARK DI ARK DI ARK DI
23. ANY CHANGES TO THE CERTIFIED SOIL EROSION MID SEDIMENT CONTROL PLANS WILL REQUIRE THE SUBMISSION OF REVISED SOIL EROSION AND SEDIMENT CONTROL PLANS TO THE DISTRICT FOR RECERTIFICATION. THE REVISED PLANS MUST MEET ALL CURRENT STATE SOIL EROSION AND SEDIMENT CONTROL STANDARDS.	SET IS SET IS DESIMED BY: DTS DTS DTS DTS DTS DTS DTS DTS DTS DTS
1. INSTALL STABILIZED CONSTRUCTION ENTRANCE AND SILT FENCE.	AND MAY AND MAY C Reposed Section 1 94 BUSINE Town of Westches
 DEMOLITION OF SITE FEATURES AS DETAILED ON SHEET #4. EXCAVATED MATERIALS SHALL NOT BE STORED ONSITE. ALL THE LEFT OVER MATERIALS NEED TO BE TRUCKED OUT FROM THE SITE. INSTALL UNDERGROUND PIPING, UTILITIES AND DRAINAGE STRUCTURES. INSTALL INLET PROTECTION. 	「記記® W: KH JECT
 INSTALL INCL. INCL. INCL. INCL. INCL. CLEAR AND ROUGH GRADE FOR NEW BUILDING & SITE IMPROVEMENTS. EXCAVATE AND INSTALL SITE IMPROVEMENTS INCLUDING CURBING, SIDEWALKS, AND LIGHT POLE FOUNDATIONS. GRADE PARKING LOT AND INSTALL SUB BASE AND PAVEMENT BASE COURSE. REMOVE SILT FENCE AND SEDIMENT CONTROL FEATURES. 	DRAWN BY:
9. INSTALL FINAL PAVEMENT AND FINAL VEGETATION INCLUDING SEEDING AND LANDSCAPING.	PROTECT YOURSELF All states require notification of
<u>STABILIZATION SPECIFICATIONS -</u> Temporary seeding and mulching	Know what's bolow Call boforo you do. FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT:
– LIME – 90 LBS/1,000 SF GROUND LIMESTONE; FERTILIZER – 11 LBS/1,000 SF; 10–20–10 OR EQUIVALENT WORKED INTO SOIL A MINIMUM OF 4". – SEEDS:	WWW.CALL811.COM
COOL SEASON: PERENNIAL RYE GRASS 100LBS/ACRE OR OTHER APPROVED SEEDS; PLANT BETWEEN MARCH 1 AND MAY 15 OR BETWEEN AUGUST 15 AND OCTOBER 1. WARM SEASON: PEARL MILLET AT 20 LBS/AC. OR OTHER APPROVED SEEDS; PLANT BETWEEN MAY 15 AND AUGUST 15.	ENGINEERING
- MULCH - SALT HAY OR SMALL GRAIN STRAW AT A RATE OF 70 TO 90 LBS/1,000 SF TO BE APPLIED ACCORDING TO THE STATE STANDARDS. MULCH SHALL BE SECURED BY APPROVED METHODS (I.E. PEG AND TWINE, MULCH NETTING. OR LIQUID MULCH BINDER.	LAND DEVELOPMENT CONSULTING • PERMITTING GEOTECHNICAL • ENVIRONMENTAL TRAFFIC • SURVEY • PLANNING & ZONING 245 Main Street Suite 110
STABILIZATION SPECIFICATIONS - Permanent Seeding	245 Main Street, Suite 110 Chester, NJ 07930 T: 908.879,9229 F: 908.879.0222
 PERMANENT STABILIZATION SPECIFICATIONS: SEEDING 1 . PRIOR TO SEEDING, AREA IS TO BE TOPSOILED, FINE GRADED, AND RAKED OF ALL DEBRIS LARGER THAN 2" DIAMETER. 	Offices conveniently located at: Lake Como, New Jersey • T: 732.974.0198 Chester, New Jersey • T: 908.879.9229 Newark, New Jersey • T: 973.755.7200
 PRIOR TO SEEDING, CONSULT MANUFACTURER'S RECOMMENDATIONS AND INSTRUCTIONS. 3. SEEDING RATES: 	Toms River, New Jersey • T: 732.974.0198 Newtown, Pennsylvania • T: 267.685.0276 Philadelphia, Pennsylvania • T: 215.253.4888 Allen, Texas • T: 972.534.2100 Ularthea Turna • (199.799.4100)
PERENNIAL RYEGRASS 1/2 LB/1,000 SQ FT KENTUCKY BLUEGRASS 1 LB/1,000 SQ FT RED FESCUE 1 1/2 LEIS/1,000 SQ FT SPREADING FESCUE 1/2 LBS/1,000 SQ FT FERTILIZER (20:10:10)14 LBS/1,000 SQ FT MULCH LBS/1,000 SQ FT	Houston, Texas • T: 281.789.6400 Austin, Texas • T: 512.646.2646 Deiray Beach, Florida • T: 561.921.8570
4. GERMINATION RATES WILL VARY AS TO TIME OF YEAR FOR SOWING. CONTRACTOR TO IRRIGATE SEEDED AREA UNTIL AN ACCEPTABLE STAND OF COVER IS ESTABLISHED BY OWNER.	www.dynamicec.com
 PERMANENT STABILIZATION SPECIFICATIONS: MULCHING A. MULCH MATERIALS TO BE UNROTTED SALT HAY, HAY, OR SMALL GRAIN STRAW AT THE RATE OF 1.5 TO 2 TONS PER ACRE OR 70 TO 90 POUNDS PER 1,000 SQ. FT. B. SPREAD UNICODMLY, BY HAND, OR MECHANICALLY SO THAT APPROXIMATELY 75% TO 95% OF SOIL 	DANIEL T. SEHNAL
 B. SPREAD UNIFORMLY BY HAND OR MECHANICALLY SO THAT APPROXIMATELY 75% TO 95% OF SOIL SURFACE WILL BE COVERED. C. MULCH ANCHORING TO BE DONE IMMEDIATELY AFTER PLACEMENT BY ONE OF THE FOLLOWING METHODS: (1) PEG AND TWINE (2) MULCH NETTING (3) LIDIUM MULCH DINDERS 	PROFESSIONAL ENGINEER NEW YORK LICENSE No. 099106
(3) LIQUID MULCH-BINDERS MULCH STABILIZATION A. UNROTTED SMALL-GRAIN STRAW, OR SALT HAY AT 2.0 TO 2.5 TONS PER ACRE IS SPREAD UNIFORMLY AT 90 TO 115 POUNDS PER 1,000 SQUARE FEET AND ANCHORED WITH A MULCH ANCHORING TOOL, LIQUID MULCH BINDERS, OR NETTING TIE DOWN. OTHER SUITABLE MATERIALS MAY BE USED IF APPROVED E	BRETT W. SKAPINETZ
AND ANCHORED WITH A MOLCH ANCHORING TOOL, LIQUID MULCH BINDERS, OR NETTING THE DOWN. OTHER SUITABLE MATERIALS MAY BE USED IF APPROVED E THE SOIL CONSERVATION DISTRICT. B. ASPHALT EMULSION IS RECOMMENDED AT THE RATE OF 600 TO 1,200 GALLONS PER ACRE. THIS IS SUITABLE FOR A LIMITED PERIOD OF TIME WHERE TRAVEL BY PEOPLE, ANIMALS, OR MACHINES IS NOT A PROBLEM. C. SYNTHETIC OR ORGANIC SOIL STABILIZERS MAYBE USED UNDER SUITABLE CONDITIONS AND IN QUANTITIES AS RECOMMENDED BY THE MANUFACTURER.	PROFESSIONAL ENGINEER NEW YORK LICENSE No. 087962
D. WOOD-FIBER OR PAPER-FIBER MULCH AT THE RATE OF 1,500 POUNDS PER ACRE (OR ACCORDING TO THE MANUFACTURER'S REQUIREMENTS) MAY BE APPLIED BY A HYDROSEEDER.	
E. MULCH NETTING, SUCH AS PAPER JUTE, EXCELSIOR, COTTON, OR PLASTIC,. MAYBE USED. F. MULCH ANCHORING TO BE DONE IMMEDIATELY AFTER PLACEMENT BY ONE OF THE FOLLOWING METHODS:	POLLUTION PREVENTION PLAN
 (1) PEG MID TWINE (2) MULCH NETTING (3) LIQUID MULCH-BINDERS 	SCALE: (H) 1"=30' DATE: (V) 02/19/2021 PROJECT No: 2179-99-009
<u>GRAPHIC SCALE</u> -30 0 15 30 60 120	SHEET No: Rev. #:
	¶/ \


















07/12/21 decpc.local



AM, By: s\Data\C – 11:56 decfolders 07/12/21 decpc.local ΰŹ



BANKED GRADING



(IN FEET) 1 INCH = 30 FT.

STORMWATER POLUTION PREVENTION PLAN REPORT

Prepared for:

ARMONK FAIRVIEW, LLC & AGGRO AND BRASSI, LLC

Proposed Warehouse Tax Lot 108.03-1-50 94 Business Park Drive Town of North Castle (Armonk) Westchester County, NY

Prepared by:



245 Main Street, Suite 110 Chester, NJ 07930 (908) 879-9229

Daniel T. Sehnal, PE NY Professional Engineer License #99106

> July 2021 DEC# 2179-99-009

TABLE OF CONTENTS

I.	Introduction
II.	Site Description
III.	Controls
IV.	Maintenance & Inspection Procedure 10
V.	Non-Stormwater Discharges
VI.	Inventory for Pollution Prevention Plan
VII.	Spill Control & Prevention
VIII.	Supplemental Plans & Reports

APPENDIX

- USGS Map
- Soil Survey
- Runoff Curve Number (CN) Calculations
- Pipe Sizing Calculations
- NOAA Atlas 14 Precipitation Data
- Hydrograph Summary Reports Existing and Proposed Conditions 1-yr., 10-yr. & 100-yr.
- Water Quality Volume Calculations
- ADS Water Quality Unit (WQU 4220B) Product Specification
- Pollution Prevention Plan Certification
- Certification by Contractors
- Stormwater Construction Site Inspection Report
- Corrective Action Log
- Amendment Log
- Grading Activities Log
- Training Log
- Post Construction Stormwater Management Facilities Maintenance Checklists
- Drainage Area Maps

I. <u>INTRODUCTION</u>

Notice of Intent:

Section 402 of the Clean Water Act requires a permit for stormwater discharge from construction activities, which disturb one or more acres of land. To implement this law, the New York State Department of Environmental Conservation (NYSDEC) issued the General Permit for Storm water Discharges from Construction Activities (GP-0-10-001). The Notice of Intent (NOI) is the means to obtain coverage under this permit.

SWPPP Goals and Objective:

The goal of the Stormwater Pollution Prevention Plan (SWPPP) is to control runoff of pollutants from the project site during and after construction activities by complying with the NY State Pollutant Discharge Elimination System (SPDES) Stormwater Permit for construction activities and local rules and regulations. The SWPPP will implement the following practices:

- Reduction or elimination of erosion and sediment loading to water bodies during construction.
- Control of the impact of stormwater runoff on the water quality of the receiving waters in accordance with green infrastructure and coordinates with 100% runoff reduction volume (RRv) source control practices.
- Control of the increased volume and peak rate of runoff during and after construction.
- Maintenance of stormwater controls during and after completion of construction.

The SWPPP will incorporate the proper selection, sizing and institution of the Stormwater Management Practices (SMPs) to protect water resources from stormwater impacts. The design of the proposed SMPs were determined using current engineering methodologies to provide appropriate sizing criteria to avoid overburdening stormwater conveyance structures. Erosion and Sediment Control (ESC), Water Quantity Control, and Water Quality Controls are inter-related components of the SWPPP.

The SWPPP is intended to be a "living" document. The document should be revised and updated by a qualified professional whenever site conditions dictate. Any proposed revisions shall undergo review by the owner or his designated representative prior to incorporation in the SWPPP and implementation at the site. Any proposed modifications shall be in accordance with the New York State Department of Environmental Conservation's technical standards.

II. <u>SITE DESCRIPTION</u>

Project Name & Location:

Proposed Warehouse Town of North Castle (Armonk) Westchester County, New York Section 108.03; Block 1, Lot 50

Owner/Operator Name & Address:

Armonk Fairview, LLC & Aggro and Brassi, LLC C/O Mandelbaum & Mandelbaum 80 Main Street, Suite 510 West Orange, New Jersey 07052 (267) 716-6880 greeves@jgpetrucci.com

General Contractor*:

(Company Name)

(Street Address)

(City, State, Zip Code)

(Phone Number)

*General Contractor shall be identified prior to commencement of work.

Description:

The intent of this study is to analyze the stormwater runoff conditions that will occur as a result of the proposed warehouse redevelopment for the site located at 94 Business Park Drive in Armonk (Town of North Castle), Westchester County, New York and specifically identified as tax lot 108.03-1-50 on the Town of North Castle Tax Maps. The site is presently developed, consisting of a 140-bedroom hotel, paved parking areas, and associated site improvements.

Under proposed conditions, the existing hotel will be removed and the site will be redeveloped with a proposed warehouse facility of approximately 71,500 SF, loading areas, paved parking areas, and associated site improvements as shown on the accompanying engineering drawings. The primary stormwater management design constraints for this project are based on requirements established within the New York State Stormwater Management Design Manual (NYSSMDM).

The soil types within the project site watershed area are classified as "Pompton silt loam, loamy substratum" and a hydrological soil group of "B/D," and "Urban land," also belonging to hydrological group "D." The Pompton silt loam, loam substratum, which accounts for about 43% of the site, is located in the northern and eastern sections of the lot. The Urban land soil exists in about 57% of the site, accounting for all of the area not covered by Pompton silt loam. The details of the soil characteristics can be found in the Soil Survey of Westchester County, New York, United States Department of Agriculture, Soil Conservation Service.

Impervious Cover:

The site currently consists of approximately 153,600 SF (63.9%) of impervious surface area. The proposed redevelopment project will result in an increase in overall impervious coverage by approximately 32,940 SF (13.7%). As result of the increase in impervious cover, the discharge rate from the site will be greater than the current discharge rates; therefore, the water quantity controls for the tenyear and hundred-year criteria apply.

Site Area:

The overall subject site consists of approximately 240,438 SF (5.52 Ac.) and is presently developed containing the hotel with associated site improvements. The majority of the subject parcel as well as portions of Business Park Drive right-of-way will be disturbed as a result of the proposed construction activities and improvements for a total disturbance area of approximately 225,601 SF (5.179 Ac.).

This site is to be considered areas of "redevelopment" as per the NYSSMDM for the purpose of this study. The stormwater runoff generated from this area flows towards existing onsite inlets and is conveyed to an existing storm sewer located within the drainage easement immediately south of the site. Runoff within this existing storm sewer ultimately discharges to the wetlands associated with the Byram River to the east of the site, identified as "Point of Analysis 1" (POA #1) for the purposes of this study. The Runoff Curve Numbers, included within the Appendix of this Report, were chosen to conservatively reflect the existing site conditions as outlined in the USDA's "Urban Hydrology for

Small Watersheds: TR-55," including hydrologic group B for the existing open space areas. A minimum time of concentration of 10 minutes has been utilized for this drainage area.

Sequence of Major Activities:

The sequence of construction activities is as follows:

- 1. Install stabilized construction entrance and silt fence.
- 2. Demolition of site features as detailed on sheet #2 of the accompanying engineering drawings.
- 3. Install underground piping, utilities and drainage structures.
- 4. Install inlet protection.
- 5. Clear and rough grade for new building and site improvements.
- 6. Excavate and install site improvements including curbing, sidewalks, and light pole foundations.
- 7. Grade parking lot and install sub base and pavement base course.
- 8. Remove silt fence and sediment control features.
- 9. Install final pavement and final vegetation including seeding and landscaping.

III. <u>CONTROLS</u>

Erosion and Sediment Controls Stabilization Practices:

a. Temporary Stabilization:

Topsoil, stockpiles, and soils that are exposed and left bare for a period of 14 days which are not being graded, not under active construction for 14 days or more, or not scheduled for permanent seeding within 14 days shall be stabilized with temporary seed and mulch. All grass seed mixtures and application rates shall comply with Soil Erosion and Sediment Control Plan.

Site areas which are to be paved; shall be temporarily stabilized by applying the stone sub-base until bituminous pavement is applied.

b. Permanent Stabilization

Disturbed portions of the site where construction activities permanently cease shall be stabilized with permanent seed no later than 14 days after the last construction activity.

Structural Practices:

Proposed measures will include silt fences, storm inlet protection, curb inlet protection, and stabilized construction entrances.

Stormwater Management Water Quality:

In order to meet the intent of the water quality standards set forth in Chapter 4 of the New York State Stormwater Management Design Manual, the development proposes ADS Water Quality Unit treatment devices to treat the required area. The proposed Detention basin has been designed with a pretreatment sump for water quality treatment. The minimum required water quality treatment area was determined using the NYSMDM Chapter 9 for Redevelopment Projects. As such, at least 75% of the existing paved surface area and the additional paved surface area must be treated under post-development conditions. In order to meet this requirement, ADS Water Quality Units are being proposed to treat at least the minimum required area and is sized to accommodate the proposed peak flows as calculated per TR-55. Associated calculations are included within the Appendix.

Peak Flow Attenuation:

Under proposed conditions, the site will be redeveloped into the aforementioned warehouse and site improvements, including stormwater management facilities to mitigate the increased stormwater runoff resulting from the additional impervious area. The proposed site improvements will result in an overall increase in impervious coverage of approximately 32,900 square feet (0.75 acres). The proposed design serves to match existing drainage patterns to the maximum extent practical. The site has been evaluated using the TR-55 'Urban Hydrology for Small Watersheds' standards and with the following proposed drainage sub-watershed areas as depicted on the Proposed Drainage Area Map:

<u>DA-1</u>: This area consists of the western portion of the site, including paved parking and landscaped areas. Stormwater runoff generated from this area is collected by various on-site inlets and conveyed directly to an ADS Water Quality Unit for treatment before discharging into the existing stormwater conveyance system (POA #1). The Runoff Curve Numbers, included within the Appendix of this Report, were chosen to best reflect the proposed site conditions as outlined in the USDA's "Urban Hydrology for Small Watersheds: TR-55." The minimum time of concentration of 10 minutes has been utilized for this drainage area.

<u>DA-2</u>: This drainage area consists of the proposed building roof area. The stormwater runoff generated from this area is collected by various roof leaders and conveyed to the proposed underground detention basin and is released at a controlled rate ultimately to the existing stormwater conveyance system located within the existing drainage easement, identified as POA #1. The runoff is treated by the proposed pretreatment sump tank prior to entering the detention system. Runoff Curve Numbers, included within the Appendix of this Report, were chosen to best reflect these proposed site conditions as outlined in the USDA's "Urban Hydrology for Small Watersheds: TR-55." The minimum time of concentration of 10 minutes has been utilized for this drainage area.

<u>DA-3</u>: This study area consists of the proposed trailer loading spaces and parking areas to the north and east of the proposed building. The stormwater runoff generated from this area is collected by onsite inlets and conveyed through a proposed ADS Water Quality Unit for treatment before discharging to the existing stormwater conveyance system (POA #1). Runoff Curve Numbers, included within the Appendix of this Report, were chosen to best reflect these proposed site conditions as outlined in the USDA's "Urban Hydrology for Small Watersheds: TR-55." A time of concentration of 10 minutes has been calculated for this area.

As previously mentioned the proposed site redevelopment will result in a 13.7% net increase in impervious cover. In order to mitigate this increase in stormwater runoff generation, the proposed development includes an underground detention basin in order to provide stormwater quantity reduction for the stormwater runoff generated by a DA-2. The proposed underground basin is located to the south of the proposed building within the parking area and is designed to detain runoff from the building roof area. Stormwater runoff generated by roof areas is considered clean and is conveyed directly to the basin. The basin consists of five (5) rows of 60" ADS HDPE pipe for a total storage volume of approximately 17,000 cubic feet. Runoff is released at a controlled rate through the use of an outlet control structure to the existing stormwater conveyance system located south of the subject site (POA #1) and ultimately discharged to the wetlands area associated with the Byram River. Channel protection criteria is met by the reduction of the discharge rate as outlined in Section 9.3.2 of the New York State Stormwater Management Design Manual.

Runoff Conveyance Systems:

The stormwater pipes and hydraulic control structure system at the site are designed to convey the 25year peak discharge flow. Associated calculations are included within the Appendix of this report.

Other Controls:

a. Waste Materials:

All waste materials will be collected and stored in securely lidded metal dumpsters rented from_______, a solid waste management company located in Westchester County (name of carting company to be identified 30 days prior to commencement of work). The dumpsters will meet Town of North Castle, Westchester County, and New York State solid waste management regulations. All trash and construction

b. Hazardous waste:

All hazardous waste materials will be disposed of in the manner specified by local or state regulation or by the manufacturer. Site personnel will be instructed in these practices and ______, Job Supervisor, individual who is responsible for managing the day to day site operations, will be responsible for seeing that these procedures are followed (Job Supervisor shall be identified 30 days prior to commencement of work).

c. Sanitary Waste:

A licensed sanitary waste management contractor (sanitary waste management contractor to be identified 30 days prior to commencement of work) will collect all sanitary waste from the portable units.

d. Offsite Vehicle Tracking:

A stabilized construction entrance and gravel pad will be provided to wash or spray-clean trucks over before leaving the site in order to prevent track-out of dirt, mud, debris and dust. Also, trucks will be covered with a tarp and at least 6 inches of freeboard clearance will be maintained to keep excessive dust from escaping the truck during hauling operations.

Timing of Control Measures:

As indicated in the Sequence of Construction, the stabilized construction entrance and other sediment and erosion control activities will be constructed prior to earthwork activities on any part of the site. Any soil areas that are exposed and left bare for a period of 14 days which are not being graded, not under active construction for 14 days or more, or not scheduled for permanent seeding within 14 days will be treated with temporary seed and mulch. Once construction activity ceases permanently in an area, that area will be stabilized with permanent seed and mulch. After the entire site is stabilized, accumulated sediments will be removed from the sediment and erosion control structures and the controls will be removed.

Certification of Compliance with Federal, State and Local Regulations:

The Stormwater Pollution Prevention Plan reflects New York State Department of Environmental Conservation requirements for storm water management and erosion and sediment control, as established in Article 17, Titles 7, 8 and Article 70 of the Environmental Conservation Law. To ensure compliance, this plan was prepared in accordance with guidelines issued with the SPDES General Permit for Storm Water Discharges from Construction Activities that are Classified as "Associated with Construction Activity", published by the New York State Department of Environmental Conservation.

IV. MAINTENANCE & INSPECTION PROCEDURES

Sediment & Erosion Control Inspection and Maintenance Practices:

The following are inspection and maintenance practices that will be used in coordination with the SWPPP Construction Site Inspection Report prepared for this project, the template which is included in Appendix, to maintain sediment and erosion controls:

- The Operator shall have a qualified professional conduct an assessment of the site prior to the commencement of construction and certify in this inspection report that the appropriate erosion and sediment controls described in the SWPPP, and required by the SPDES General Permit for Stormwater Discharges, have been adequately installed or implemented to ensure overall preparedness of the site for commencement of construction. Qualified professional means a person knowledgeable in the principles and practice of erosion and sediment Control, such as a licensed professional engineer, Certified Professional in Erosion and Sediment Control (CPESC), soil scientist, or someone working under the direction and supervision of a licensed professional engineer, Certified Professional in Erosion and Sediment Control (CPESC), or soil scientist (person must have experience in the principles and practices of erosion and sediment control).
- All control measures will be inspected by a qualified professional at least once each week (7 days) and immediately following any storm event of 0.5 inches or greater.
- All measures will be maintained in good working order. If a repair is necessary, it will be initiated within 24 hours of discovery.

- Provide sprinkle water on dirt roads during hot summer or when appropriate to prevent particles to be air born.
- Built up sediment to be removed from the silt fence when it has reached 1/3 the height of the fence.
- Silt fence will be inspected for depth of sediment, tears, to see if the fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground.
- Temporary and permanent seeding and planting will be inspected for bare spots, washouts, and healthy growth.
- A Construction Site Inspection Report shall be filled out after each inspection and will become part of the SWPPP.
- _____, Job Supervisor- Trained Individual, will select individuals who will be responsible for coordinating efforts with the qualified professional for regular inspections, maintenance and repair activities, and filling out the Construction Site Inspection Report forms. Inspection reports should summarize:
 - 1. Name of Inspector
 - 2. Qualifications of Inspector
 - 3. Date of Inspection
 - 4. Weather Conditions
 - 5. Areas inspected, including measurements
 - 6. Areas that have undergone temporary and permanent stabilization
 - 7. Indicate all disturbed areas that have not undergone active site work during the previous 14-day period
 - 8. Observed condition of all erosion and sediment control practices
 - 9. Inspect all sediment control practices and record approximate degree of sediment accumulation as a percentage of the sediment storage volume
 - 10. Actions Taken to Correct Problems
 - 11. Incorporate changes necessary to the SWPPP
- Personnel selected for inspection and maintenance responsibilities will receive training from the Job Supervisor and/or the qualified professional. They will be trained in all the inspection and maintenance practices necessary for keeping the erosion and sediment controls used on site in good working order.
- The operator shall ensure that a record of all Construction Site Inspection Reports is maintained in a SWPPP Site Construction Log Book. The site log book shall be maintained on site and be made available to the permitting authorities upon request. Prior to the commencement of construction, the Operator shall certify in the site log book that the SWPPP was prepared in accordance with the State's standards and meets all Federal, State and local erosion and sediment control requirements.

The Operator shall retain copies of SWPPPs and any reports submitted in conjunction with this permit, and records of all data used to complete the NOI to be covered by this permit, for a period of at least three years from the date that the site is finally stabilized. The Operator shall post at the site, in a publicly-accessible location, a summary of the site inspection activities on a monthly basis.

- Prior to filing of the Notice of Termination (NOT) or the end of permit term, the Operator shall have the qualified professional perform a final site inspection. The qualified professional shall certify that the site has undergone final stabilization using either vegetative or structural stabilization methods and that all temporary erosion and sediment controls (such as silt fencing) not needed for long-term erosion control have been removed. Final stabilization means that all soil-disturbing activities at the site have been completed and a uniform, perennial vegetative cover with a density of 80% has been established, or equivalent stabilization measures (such as the use of mulches or geotextiles) have been employed on all unpaved areas and areas not covered by permanent structure.
- Clean out all temporary structures and pipes upon completion of the project.
- When the site has been finally stabilized, the operator must submit a Notice of Termination (NOT) form to terminate coverage under the SPDES General Permit. The permittee must identify all of the permanent stormwater management structures that have been constructed. In addition, a manual describing the operation and maintenance practices that will be necessary for the structures to function as designed after the site is stabilized must be finalized and in-place. The permittee must also certify that the permanent structure has been constructed as described in the SWPPP.

Summary of SWPPP Required Document Filings:

The following table provides a summary of the required forms and inspections that need to be completed as part of the SWPPP requirements and which checklist or report document forms need to be used for each:

Name of Document	Form to be used	When to complete				
Pre-construction Meeting	SWPPP	Prior to beginning of construction				
Owner/Operator Certification	Pollution Prevention Plan Certification	Prior to beginning of construction				
Prime Contractor Certification	Certification by Contractors	Prior to beginning of construction				
Sub-Contractor Certification	Certification by Contractors	Prior to beginning of construction				
Pre-Construction Site Assessment	Pre-construction Site Assessment Checklist	Prior to beginning of construction				
Construction Duration Inspection	Construction Duration Inspection	One each 7 days or after any storm event of 0.5 inch or greater				

Three-month Status Reports	Summary of Site Inspection Activities	Every three months
Stormwater Management Facilities Construction Inspection	Stormwater Construction Site Inspection Report	Monthly
Corrective Action Log	Corrective Action Log	Whenever a BMP is modified
Amendment Log	SWPPP Amendment Log	Whenever SWPPP is modified
Grading Activities Log	Grading Activities Log	Whenever a major grading event takes place
SWPPP Training Log	Training Log	Whenever a new inspector is trained
Stormwater Maintenance Checklist	Post const. Stormwater Management Checklists	After completion of project

V. NON-STORM WATER DISCHARGES

Non-Stormwater Discharges:

It is expected that the following non-storm water discharges will occur from the site during the construction period:

- Water from water line flushing.
- Pavement wash waters (where no spills or leaks of toxic or hazardous materials have occurred).
- Uncontaminated groundwater (from natural springs)

VI. INVENTORY FOR POLLUTION PREVENTION PLAN

Material substances:

The materials or substances listed below are expected to be present on the site during construction:

- Concrete
- Detergents
- Paints (enamels and latex)
- Metal Studs
- Roofing Materials
- Tar and Paving Materials
- Fertilizers

- Petroleum Based Products
- Cleaning Solvents
- Wood
- Masonry Block

VII. <u>SPILL CONTROL & PREVENTION</u>

Material Management Practices:

The following are the material management practices that will be used to reduce the risk of spills or other accidental exposure of materials and substances to storm water runoff:

a. Good Housekeeping:

The following good housekeeping practices will be followed on site during the construction project:

- An effort will be made to store only enough products required to complete construction activities.
- All materials stored on site will be stored in a neat, orderly manner in their appropriate containers and, if possible, under a roof or other enclosure.
- Product will be kept in their original containers with the original manufacturer's label.
- Substances will not be mixed with one another unless recommended by the manufacturer.
- Whenever possible, all of a product will be used up before disposing of the container.
- Manufacturer's recommendations for proper use and disposal will be followed.
- The Job Supervisor will inspect daily to ensure proper use and disposal of materials on site.
- b. Hazardous Products:

The following practices will be used to reduce the risks associated with hazardous materials:

- Products will be kept in original containers unless they are not re-sealable.
- Original labels and material safety data will be retained; they contain important product information.
- If surplus product must be disposed of, manufacturer's or local and State recommended methods for proper disposal will be followed.

Product Specific Practices:

The following product specific practices will be followed on site:

a. Petroleum Products:

All onsite vehicles will be monitored for leaks and receive regular preventative maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers, which are clearly labeled. Any asphalt substances used on site will be applied according to the manufacturer's recommendations.

b. Fertilizers:

Fertilizers will be applied only in the minimum amounts recommended by the manufacturer. Once applied, fertilizer will be worked into the soil to limit exposure to stormwater. Storage will be in a covered shed. The content of any partially used bags of fertilizer will be transferred to a sealable plastic bin to avoid spills.

c. Paints:

All containers will be tightly sealed and stored when not required for use. Excess paint will not be discharged to the storm drainage system, but will be properly disposed of according to manufacturer's instructions or State and local regulations.

d. Concrete Trucks:

Concrete trucks will not be allowed to wash out or discharge surplus concrete or drum wash water on the site.

Spill Control Practices:

In addition to the good housekeeping and material management practices discussed in the previous sections of this plan, the following practices will be followed for spill prevention and cleanups:

- Manufacturer's recommended methods for spill cleanup will be clearly posted and site personnel will be made aware of the procedures and the location of the information and cleanup supplies.
- Materials and equipment necessary for spill cleanup will be kept in the material storage areas on site. Equipment and materials will include, but not be limited to, brooms, dust pans, mops, rags, gloves, goggles, kitty litter, sand, sawdust, and plastic and metal trash containers specifically for this purpose.
- All spills will be cleaned up immediately after discovery.

- The spill area will be kept well ventilated, and personnel will wear appropriate protective clothing to prevent injury from contact with hazardous substances.
- Spills of toxic or hazardous material will be reported to the appropriate State or local government agency, regardless of the size of the spill.
- The Job Supervisor responsible for daily site operations will be designated as the spill prevention and cleanup coordinator. He will designate at least three other site personnel who will receive spill prevention and cleanup training. These individuals will each become responsible for a particular phase of prevention and cleanup. The names of the responsible spill personnel will be posted in the material storage area.

VIII. SUPPORTING PLANS & REPORTS


1. Site Plan Drawings prepared by Dynamic Engineering Consultants P.C.

APPENDIX

USGS MAP




USGS Map Glenville Quad



1904 Main Street, Lake Como, NJ 07719 T. 732-974-0198

100 NE 5th Avenue, Suite B2, Delray Beach, FL 33483 T. 561-291-8570 14521 Old Katy Road, Suite 270, Houston, TX 77079 T. 281-789-6400 714 S. Greenville Avenue, Suite 100, Allen, TX 75002 T. 972-534-2100


SOIL SURVEY



USDA Natural Resources

Conservation Service

Web Soil Survey National Cooperative Soil Survey



Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
Ff	Fluvaquents-Udifluvents complex, frequently flooded	A/D	1.6	16.9%
Pw	Pompton silt loam, loamy substratum	B/D	2.4	25.6%
Uf	Urban land		5.3	57.6%
Totals for Area of Intere	st		9.2	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition Component Percent Cutoff: None Specified Tie-break Rule: Higher



RUNOFF CURVE NUMBER (CN) CALCULATIONS



EXISTING DRAINAGE AREA SUMMARY AND AVERAGE CURVE NUMBER(CN) CALCULATIONS

Project: Job #: Location:	2179-99-009	North Castle (Armonk), NY					DRL DTS 7/12/2021						
Drainage A		Curve	HSG B -	HSG B -	Curve	Avg. Perv.	Total Demriana Ar	Total Area	Resulting	TC (Min.)			

		Area (acre)	Area (sf)	Number (CN) Used	Open Space Area	Open Space Area	Number (CN) Used		PerviousAr ea (acres)	(acres)	CN	
				``	(acre)	(sf)	. ,		· /			
	EX-DA1	3.53	153,647	98	2.02	87,781	61	61	2.02	5.54	74	10
	Total	3.53	153647		2.02	87781			2.02	5.54		
Per	Westchester County S	oil Survey -	Pw	HSG	В	Soil	Pompton sily	[,] loam, loamy	substratum			
Per	Westchester County S	oil Survey -	Uf	HSG	D	Soil	Urban Land					

Description	Runoff Curve Number (CN) (HSG B)	Runoff Curve Number (CN) (HSG D)
Impervious Surface	98	98
Open Space (lawn) (good)	61	80
Woods (good)	55	77



PROPOSED DRAINAGE AREA SUMMARY AND AVERAGE CURVE NUMBER(CN) CALCULATIONS

Project:	Armonk - Proposed Warehouse	Computed By:	DRL
Job #:	2179-99-009	Checked By:	DTS
Location:	North Castle (Armonk), NY	Date:	7/12/2021


Drainage Area	Impervious	Impervious	Curve	HSG D -	HSG D -	Curve	Avg. Perv.	Total	Total Area	Resulting	TC (Min.)
	Area (acre)	Area (sf)	Number	Open	Open	Number	Curve	PerviousAr	(acres)	CN	
			(CN) Used	Space Area	Space Area	(CN) Used	Number	ea (acres)			
				(acre)	(sf)						
PR-DA1	2.63	114,610	98	1.27	55,245	80	80	1.27	3.90	92	10
RA	1.64	71,574	98	0.00	-	80	N/A	0.00	1.64	98	10
 Total	4.27	186184		1.27	55245		-	1.27	5.54		•

Per Westchester County Soil Survey -	Pw	HSG	В	Soil	Pompton sily loam, loamy substratum
Per Westchester County Soil Survey -	Uf	HSG	D	Soil	Urban Land

Description	Runoff Curve Number (CN) (HSG B)	Runoff Curve Number (CN) (HSG D)
Impervious Surface	98	98
Open Space (lawn) (good)		80
Woods (good)	55	77

PIPE SIZING CALCULATIONS

Hydraflow Storm Sewers Extension for Autodesk® Civil 3D® Plan



Line No.	Line ID	Inlet ID	Drng Area	Runoff Coeff	lncr CxA	Total CxA	Inlet Time	Тс	i Sys	Line Size	Line Length	Line Slope	Line Type	Capac Full	Flow Rate	Vel Ave	
			(ac)	(C)			(min)	(min)	(in/hr)	(in)	(ft)	(%)		(cfs)	(cfs)	(ft/s)	
1	33 to UDET-1	33	0.00	0.00	0.00	0.81	0.0	9.1	7.15	18	10	1.00	Cir	11.49	5.80	5.04	
2	32 to 33	32	0.00	0.00	0.00	0.81	0.0	8.6	7.25	18	91	1.00	Cir	11.49	5.89	5.09	
3	RDW-5-1 to 32	RDW-5-1	0.00	0.00	0.00	0.72	0.0	8.4	7.31	15	60	1.01	Cir	7.02	5.28	5.73	
4	RDW-4-1 to RDW-5-1	RDW-4-1	0.00	0.00	0.00	0.57	0.0	8.2	7.36	15	48	1.00	Cir	6.97	4.23	4.60	
5	31 to RDW-4-1	31	0.00	0.00	0.00	0.41	0.0	7.9	7.42	15	39	0.99	Cir	6.93	3.01	3.88	
6	RWD-3-1 to 31	RWD-3-1	0.00	0.00	0.00	0.41	0.0	7.8	7.47	12	40	1.00	Cir	3.99	3.03	5.12	
7	RDW-2-1 to RWD-3-1	RDW-2-1	0.00	0.00	0.00	0.24	0.0	7.4	7.55	12	48	1.00	Cir	3.99	1.80	3.35	
8	30 to RDW-2-1	30	0.00	0.00	0.00	0.09	0.0	6.3	7.87	12	61	1.00	Cir	3.98	0.70	2.19	
9	RDW-1 to 30	RDW-1	0.09	0.99	0.09	0.09	6.0	6.0	7.94	10	20	1.00	Cir	2.37	0.71	3.15	
10	RDW-4 to RDW-4-1	RDW-4	0.17	0.99	0.17	0.17	6.0	6.0	7.94	10	20	1.00	Cir	2.37	1.34	4.12	
11	RDW-3 to RWD-3-1	RDW-3	0.17	0.99	0.17	0.17	6.0	6.0	7.94	10	20	1.00	Cir	2.37	1.34	4.12	
12	RDW-2 to RDW-2-1	RDW-2	0.15	0.99	0.15	0.15	6.0	6.0	7.94	10	20	1.00	Cir	2.37	1.18	3.97	
13	RDW-5 to RDW-5-1	RDW-5	0.15	0.99	0.15	0.15	6.0	6.0	7.94	10	20	1.00	Cir	2.37	1.18	3.97	
14	RDW-6 to 32	RDW-6	0.09	0.99	0.09	0.09	6.0	6.0	7.94	10	20	1.00	Cir	2.37	0.71	3.41	
15	43 to UDET-3	43	0.00	0.00	0.00	0.81	0.0	8.6	7.26	18	10	0.50	Cir	8.13	5.89	5.00	
16	42 to 43	42	0.00	0.00	0.00	0.81	0.0	8.4	7.32	18	51	0.51	Cir	8.22	5.94	4.86	
17	RDE-5 to 42	RDE-5	0.17	0.99	0.17	0.17	6.0	6.0	7.94	10	20	6.80	Cir	6.19	1.34	6.41	
18	RDE-4-1 to 42	RDE-4-1	0.00	0.00	0.00	0.64	0.0	8.0	7.41	18	60	0.50	Cir	8.13	4.77	3.86	
19	41 to RDE-4-1	41	0.00	0.00	0.00	0.49	0.0	7.5	7.53	18	60	0.50	Cir	8.13	3.65	3.93	
20	RDE-2-1 to 41	RDE-2-1	0.00	0.00	0.00	0.33	0.0	7.1	7.65	15	60	0.50	Cir	4.93	2.50	4.03	
21	40 to RDE-2-1	40	0.00	0.00	0.00	0.17	0.0	6.1	7.91	15	60	0.50	Cir	4.93	1.33	2.72	
22	RDE-1 to 40	RDE-1	0.17	0.99	0.17	0.17	6.0	6.0	7.94	10	20	5.00	Cir	5.30	1.34	5.93	
23	RDE-3 to 41	RDE-3	0.16	0.99	0.16	0.16	6.0	6.0	7.94	10	20	1.00	Cir	2.37	1.26	4.05	
Projec	t File: 2021-07 Armonk, NY Pipe.stm								Numl	per of lin	es: 34			Date: 7	7/9/2021		
	S: Intensity = 102.61 / (Inlet time + 16.50) ^ /	0.82 Return perior	d = 25 Y	rs · ** Cr	itical de	oth								1			

NOTES: Intensity = 102.61 / (Inlet time + 16.50) ^ 0.82 -- Return period = 25 Yrs.; ** Critical depth

Line No.	Line ID	Inlet ID	Drng Area	Runoff Coeff	lncr CxA	Total CxA	Inlet Time	Тс	i Sys	Line Size	Line Length	Line Slope	Line Type	Capac Full	Flow Rate	Vel Ave	
	(ac) (C) (min) (m									(in)	(ft)	(%)		(cfs)	(cfs)	(ft/s)	
24	RDE-2 to RDE-2-1	RDE-2	0.16	0.99	0.16	0.16	6.0	6.0	7.94	10	20	1.00	Cir	2.37	1.26	3.45	
25	RDE-4 to RDE-4-1	RDE-4	0.16	0.99	0.16	0.16	6.0	6.0	7.94	10	20	1.00	Cir	2.37	1.26	4.05	
26	14 to 15	14	0.00	0.00	0.00	1.65	0.0	10.1	6.92	24	21	1.02	Cir	24.94	20.05	7.39	
27	13 to 14	13	0.16	0.97	0.16	1.65	6.0	9.9	6.96	24	47	0.34	Cir	14.47	11.45	5.07	
28	12 to 13	12	1.07	0.94	1.01	1.49	6.0	9.1	7.15	24	177	0.35	Cir	14.63	10.66	4.35	
29	11 to 12	11	0.12	0.95	0.11	0.48	6.0	7.7	7.48	18	169	0.60	Cir	8.93	3.62	3.35	
30	10 to 11	10	0.39	0.95	0.37	0.37	6.0	6.0	7.94	15	246	1.00	Cir	6.97	2.94	4.52	
31	UDET-OUT to 14	UDET-OUT	0.00	0.00	0.00	0.00	0.0	0.0	0.00	18	116	0.70	Cir	9.61	8.67	5.18	
32	22 to 23	22	0.38	0.95	0.36	1.19	6.0	7.2	7.61	18	17	1.03	Cir	11.69	9.07	6.14	
33	3 21 to 22 21 0.12 0.95 0.11 0.83 6.0 6							6.6	7.79	18	142	1.00	Cir	11.50	6.47	5.04	
34	20 to 21	20	0.78	0.92	0.72	0.72	6.0	6.0	7.94	15	157	1.00	Cir	6.96	5.70	5.89	
Project	Project File: 2021-07 Armonk, NY Pipe.stm Number of lines: 34 Date: 7/9/2021																
NOTES	S: Intensity = 102.61 / (Inlet time + 16.50) ^	0.82 Return perio	d = 25 Y	rs.; ** Cr	itical dep	oth											

Line No.	Line ID	Inlet ID	Drng Area	Runoff Coeff	lncr CxA	Total CxA	Inlet Time	Tc	i Sys	Line Size	Line Length	Line Slope	Line Type	Capac Full	Flow Rate	Vel Ave	
			(ac)	(C)			(min)	(min)	(in/hr)	(in)	(ft)	(%)		(cfs)	(cfs)	(ft/s)	
1	33 to UDET-1	33	0.00	0.00	0.00	0.81	0.0	8.6	8.73	18	10	1.00	Cir	11.49	7.08	5.80	
2	32 to 33	32	0.00	0.00	0.00	0.81	0.0	8.2	8.83	18	91	1.00	Cir	11.49	7.17	5.51	
3	RDW-5-1 to 32	RDW-5-1	0.00	0.00	0.00	0.72	0.0	8.0	8.88	15	60	1.01	Cir	7.02	6.42	6.25	
4	RDW-4-1 to RDW-5-1	RDW-4-1	0.00	0.00	0.00	0.57	0.0	7.8	8.93	15	48	1.00	Cir	6.97	5.13	5.05	
5	31 to RDW-4-1	31	0.00	0.00	0.00	0.41	0.0	7.6	8.99	15	39	0.99	Cir	6.93	3.65	4.19	
6	RWD-3-1 to 31	RWD-3-1	0.00	0.00	0.00	0.41	0.0	7.5	9.04	12	40	1.00	Cir	3.99	3.67	5.45	
7	RDW-2-1 to RWD-3-1	RDW-2-1	0.00	0.00	0.00	0.24	0.0	7.2	9.12	12	48	1.00	Cir	3.99	2.17	3.63	
8	30 to RDW-2-1	30	0.00	0.00	0.00	0.09	0.0	6.2	9.42	12	61	1.00	Cir	3.98	0.84	2.31	
9	RDW-1 to 30	RDW-1	0.09	0.99	0.09	0.09	6.0	6.0	9.49	10	20	1.00	Cir	2.37	0.85	3.34	
10	RDW-4 to RDW-4-1	RDW-4	0.17	0.99	0.17	0.17	6.0	6.0	9.49	10	20	1.00	Cir	2.37	1.60	4.36	
11	RDW-3 to RWD-3-1	RDW-3	0.17	0.99	0.17	0.17	6.0	6.0	9.49	10	20	1.00	Cir	2.37	1.60	4.36	
12	RDW-2 to RDW-2-1	RDW-2	0.15	0.99	0.15	0.15	6.0	6.0	9.49	10	20	1.00	Cir	2.37	1.41	4.19	
13	RDW-5 to RDW-5-1	RDW-5	0.15	0.99	0.15	0.15	6.0	6.0	9.49	10	20	1.00	Cir	2.37	1.41	4.19	
14	RDW-6 to 32	RDW-6	0.09	0.99	0.09	0.09	6.0	6.0	9.49	10	20	1.00	Cir	2.37	0.85	3.59	
15	43 to UDET-3	43	0.00	0.00	0.00	0.81	0.0	8.2	8.83	18	10	0.50	Cir	8.13	7.17	5.35	
16	42 to 43	42	0.00	0.00	0.00	0.81	0.0	8.0	8.89	18	51	0.51	Cir	8.22	7.22	5.07	
17	RDE-5 to 42	RDE-5	0.17	0.99	0.17	0.17	6.0	6.0	9.49	10	20	6.80	Cir	6.19	1.60	6.78	
18	RDE-4-1 to 42	RDE-4-1	0.00	0.00	0.00	0.64	0.0	7.7	8.98	18	60	0.50	Cir	8.13	5.78	3.54	
19	41 to RDE-4-1	41	0.00	0.00	0.00	0.49	0.0	7.3	9.09	18	60	0.50	Cir	8.13	4.41	3.54	
20	RDE-2-1 to 41	RDE-2-1	0.00	0.00	0.00	0.33	0.0	6.9	9.21	15	60	0.50	Cir	4.93	3.01	4.23	
21	40 to RDE-2-1	40	0.00	0.00	0.00	0.17	0.0	6.1	9.46	15	60	0.50	Cir	4.93	1.59	2.51	
22	RDE-1 to 40	RDE-1	0.17	0.99	0.17	0.17	6.0	6.0	9.49	10	20	5.00	Cir	5.30	1.60	6.28	
23	RDE-3 to 41	RDE-3	0.16	0.99	0.16	0.16	6.0	6.0	9.49	10	20	1.00	Cir	2.37	1.50	4.27	
Project File: 2021-07 Armonk, NY Pipe.stm Number of lines: 34 Date: 7/9/2021																	
NOTES: Intensity = 127.16 / (Inlet time + 17.80) ^ 0.82 Return period = 100 Yrs. ; ** Critical depth																	

NOTES: Intensity = 127.16 / (Inlet time + 17.80) ^ 0.82 -- Return period = 100 Yrs.; ** Critical depth

Line No.	Line ID	Inlet ID	Drng Area	Runoff Coeff	lncr CxA	Total CxA	Inlet Time	Тс	i Sys	Line Size	Line Length	Line Slope	Line Type	Capac Full	Flow Rate	Vel Ave	
			(ac)	(C)			(min)	(min)	(in/hr)	(in)	(ft)	(%)		(cfs)	(cfs)	(ft/s)	
24	RDE-2 to RDE-2-1	RDE-2	0.16	0.99	0.16	0.16	6.0	6.0	9.49	10	20	1.00	Cir	2.37	1.50	2.79	
25	RDE-4 to RDE-4-1	RDE-4	0.16	0.99	0.16	0.16	6.0	6.0	9.49	10	20	1.00	Cir	2.37	1.50	3.59	
26	14 to 15	14	0.00	0.00	0.00	1.65	0.0	9.5	8.50	24	21	1.02	Cir	24.94	22.65	8.14	
27	13 to 14	13	0.16	0.97	0.16	1.65	6.0	9.3	8.54	24	47	0.34	Cir	14.47	14.05	5.21	
28	12 to 13	12	1.07	0.94	1.01	1.49	6.0	8.6	8.73	24	177	0.35	Cir	14.63	13.01	4.42	
29	11 to 12	11	0.12	0.95	0.11	0.48	6.0	7.4	9.05	18	169	0.60	Cir	8.93	4.39	3.51	
30	10 to 11	10	0.39	0.95	0.37	0.37	6.0	6.0	9.49	15	246	1.00	Cir	6.97	3.52	4.75	
31	UDET-OUT to 14	UDET-OUT	0.00	0.00	0.00	0.00	0.0	0.0	0.00	18	116	0.70	Cir	9.61	8.67	4.99	
32	22 to 23	22	0.38	0.95	0.36	1.19	6.0	7.0	9.17	18	17	1.03	Cir	11.69	10.94	7.14	
33	21 to 22	21	0.12	0.95	0.11	0.83	6.0	6.5	9.34	18	142	1.00	Cir	11.50	7.77	5.47	
34	20 to 21	20	0.78	0.92	0.72	0.72	6.0	6.0	9.49	15	157	1.00	Cir	6.96	6.81	6.35	
Project	t File: 2021-07 Armonk, NY Pipe.stm	l		1		I			Numt	ber of lin	es: 34			Date: 7	7/9/2021		
NOTE	S: Intensity = 127.16 / (Inlet time + 17.80) ^	0.82 Return perio	d = 100 `	Yrs.; ** 0	Critical de	əpth											

NOAA ATLAS 14 PRECIPITATION DATA



NOAA Atlas 14, Volume 10, Version 3 Location name: Armonk, New York, USA* Latitude: 41.1212°, Longitude: -73.7063° Elevation: 369.72 ft** * source: ESRI Maps ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

PF_tabular | PF_graphical | Maps_&_aerials

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches/hour) ¹											
Duration				Avera	ge recurren	ce interval (y	/ears)				
Duration	1	2	5	10	25	50	100	200	500	1000	
5-min	4.38 (3.40-5.54)	5.09 (3.94-6.44)	6.25 (4.82-7.92)	7.21 (5.53-9.19)	8.53 (6.34-11.2)	9.54 (6.94-12.7)	10.6 (7.46-14.5)	11.7 (7.86-16.4)	13.2 (8.58-19.1)	14.5 (9.18-21.2)	
10-min	3.10	3.61	4.43	5.11	6.04	6.76	7.49	8.28	9.39	10.3	
	(2.41-3.92)	(2.79-4.57)	(3.41-5.62)	(3.92-6.51)	(4.49-7.95)	(4.91-9.02)	(5.29-10.3)	(5.57-11.6)	(6.08-13.5)	(6.50-15.0)	
15-min	2.43	2.83	3.47	4.01	4.74	5.30	5.87	6.50	7.36	8.06	
	(1.89-3.08)	(2.19-3.58)	(2.68-4.41)	(3.07-5.11)	(3.52-6.24)	(3.86-7.08)	(4.15-8.07)	(4.37-9.10)	(4.77-10.6)	(5.10-11.8)	
30-min	1.71	1.98	2.43	2.80	3.32	3.71	4.11	4.52	5.08	5.51	
	(1.32-2.16)	(1.54-2.51)	(1.88-3.08)	(2.15-3.57)	(2.46-4.36)	(2.69-4.94)	(2.89-5.61)	(3.04-6.33)	(3.29-7.31)	(3.49-8.07)	
60-min	1.10	1.28	1.56	1.80	2.13	2.38	2.64	2.90	3.24	3.50	
	(0.853-1.39)	(0.988-1.62)	(1.21-1.99)	(1.38-2.30)	(1.58-2.80)	(1.73-3.17)	(1.85-3.60)	(1.95-4.06)	(2.10-4.66)	(2.21-5.12)	
2-hr	0.726	0.838	1.02	1.18	1.39	1.55	1.71	1.88	2.11	2.29	
	(0.566-0.912)	(0.653-1.05)	(0.794-1.29)	(0.907-1.49)	(1.03-1.81)	(1.13-2.05)	(1.21-2.32)	(1.27-2.62)	(1.38-3.02)	(1.46-3.33)	
3-hr	0.559	0.647	0.791	0.910	1.08	1.20	1.33	1.47	1.66	1.81	
	(0.438-0.701)	(0.506-0.812)	(0.617-0.994)	(0.706-1.15)	(0.806-1.40)	(0.880-1.59)	(0.944-1.80)	(0.993-2.03)	(1.08-2.36)	(1.15-2.61)	
6-hr	0.351	0.411	0.508	0.589	0.700	0.784	0.871	0.968	1.11	1.22	
	(0.277-0.437)	(0.323-0.512)	(0.398-0.634)	(0.459-0.738)	(0.528-0.907)	(0.579-1.03)	(0.624-1.18)	(0.658-1.33)	(0.724-1.57)	(0.778-1.75)	
12-hr	0.211	0.252	0.317	0.372	0.447	0.503	0.563	0.631	0.730	0.812	
	(0.168-0.261)	(0.199-0.311)	(0.250-0.393)	(0.292-0.463)	(0.339-0.576)	(0.374-0.660)	(0.407-0.761)	(0.430-0.864)	(0.478-1.03)	(0.520-1.16)	
24-hr	0.123	0.149	0.192	0.227	0.275	0.312	0.350	0.396	0.463	0.520	
	(0.098-0.151)	(0.119-0.183)	(0.152-0.236)	(0.179-0.281)	(0.211-0.354)	(0.234-0.407)	(0.255-0.473)	(0.271-0.538)	(0.305-0.648)	(0.334-0.739)	
2-day	0.069	0.085	0.110	0.132	0.161	0.182	0.205	0.234	0.276	0.313	
	(0.056-0.085)	(0.068-0.104)	(0.088-0.135)	(0.105-0.162)	(0.124-0.205)	(0.137-0.237)	(0.151-0.277)	(0.160-0.316)	(0.182-0.383)	(0.201-0.440)	
3-day	0.050	0.061	0.080	0.095	0.116	0.132	0.149	0.169	0.200	0.227	
	(0.040-0.061)	(0.049-0.075)	(0.064-0.097)	(0.076-0.116)	(0.090-0.148)	(0.100-0.171)	(0.110-0.200)	(0.116-0.228)	(0.132-0.277)	(0.146-0.318)	
4-day	0.040	0.049	0.064	0.076	0.092	0.105	0.118	0.134	0.159	0.179	
	(0.033-0.049)	(0.040-0.060)	(0.051-0.077)	(0.061-0.092)	(0.072-0.117)	(0.079-0.135)	(0.087-0.158)	(0.092-0.180)	(0.105-0.219)	(0.116-0.251)	
7-day	0.027	0.033	0.042	0.050	0.060	0.068	0.076	0.086	0.100	0.113	
	(0.022-0.033)	(0.027-0.040)	(0.034-0.051)	(0.040-0.060)	(0.047-0.075)	(0.051-0.087)	(0.056-0.101)	(0.059-0.114)	(0.067-0.138)	(0.073-0.157)	
10-day	0.022	0.026	0.033	0.039	0.046	0.052	0.058	0.065	0.075	0.084	
	(0.018-0.027)	(0.021-0.032)	(0.027-0.040)	(0.031-0.047)	(0.036-0.058)	(0.040-0.066)	(0.043-0.076)	(0.045-0.086)	(0.050-0.103)	(0.055-0.117)	
20-day	0.016	0.018	0.022	0.025	0.029	0.032	0.036	0.039	0.044	0.048	
	(0.013-0.019)	(0.015-0.021)	(0.018-0.026)	(0.020-0.030)	(0.023-0.036)	(0.025-0.041)	(0.026-0.046)	(0.027-0.052)	(0.030-0.060)	(0.031-0.066)	
30-day	0.013	0.015	0.017	0.020	0.023	0.025	0.027	0.030	0.033	0.035	
	(0.011-0.015)	(0.012-0.017)	(0.014-0.021)	(0.016-0.023)	(0.018-0.028)	(0.019-0.031)	(0.020-0.035)	(0.021-0.039)	(0.022-0.045)	(0.023-0.049)	
45-day	0.011	0.012	0.014	0.016	0.018	0.020	0.021	0.023	0.025	0.027	
	(0.009-0.013)	(0.010-0.014)	(0.011-0.017)	(0.013-0.019)	(0.014-0.022)	(0.015-0.024)	(0.016-0.027)	(0.016-0.030)	(0.017-0.034)	(0.017-0.036)	
60-day	0.009	0.010	0.012	0.013	0.015	0.017	0.018	0.019	0.021	0.022	
	(0.008-0.011)	(0.009-0.012)	(0.010-0.014)	(0.011-0.016)	(0.012-0.018)	(0.013-0.020)	(0.013-0.023)	(0.014-0.025)	(0.014-0.028)	(0.014-0.030)	


¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).


Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.


Please refer to NOAA Atlas 14 document for more information.

Back to Top

PF graphical








NOAA Atlas 14, Volume 10, Version 3

Created (GMT): Tue Jan 5 15:37:42 2021

Back to Top

Maps & aerials

Small scale terrain



Large scale terrain






Large scale aerial



Back to Top

US Department of Commerce National Oceanic and Atmospheric Administration National Weather Service National Water Center 1325 East West Highway Silver Spring, MD 20910 Questions?: <u>HDSC.Questions@noaa.gov</u>

Disclaimer





POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

PF_tabular | PF_graphical | Maps_&_aerials

PF tabular

PDS-	based po	int precipi	itation free	quency es	timates w	/ith 90% (confiden	ce interva	als (in ind	ches) ¹				
Duration	Average recurrence interval (years)													
Duration	1	2	5	10	25	50	100	200	500	1000				
5-min	0.365 (0.283-0.462)	0.424 (0.328-0.537)	0.521 (0.402-0.660)	0.601 (0.461-0.766)	0.711 (0.528-0.936)	0.795 (0.578-1.06)	0.881 (0.622-1.21)	0.974 (0.655-1.36)	1.10 (0.715-1.59)	1.21 (0.765-1.77)				
10-min	0.517 (0.401-0.654)	0.601 (0.465-0.761)	0.738 (0.569-0.936)	0.851 (0.653-1.09)	1.01 (0.749-1.33)	1.13 (0.819-1.50)	1.25 (0.881-1.71)	1.38 (0.929-1.93)	1.57 (1.01-2.25)	1.71 (1.08-2.51)				
15-min	0.608 (0.472-0.770)	0.707 (0.547-0.895)	0.868 (0.670-1.10)	1.00 (0.768-1.28)	1.19 (0.881-1.56)	1.32 (0.964-1.77)	1.47 (1.04-2.02)	1.62 (1.09-2.27)	1.84 (1.19-2.65)	2.01 (1.27-2.95)				
30-min	0.854 (0.662-1.08)	0.991 (0.768-1.25)	1.22 (0.938-1.54)	1.40 (1.08-1.79)	1.66 (1.23-2.18)	1.85 (1.35-2.47)	2.05 (1.44-2.81)	2.26 (1.52-3.16)	2.54 (1.65-3.66)	2.76 (1.74-4.03)				
60-min	1.10 (0.853-1.39)	1.28 (0.988-1.62)	1.56 (1.21-1.99)	1.80 (1.38-2.30)	2.13 (1.58-2.80)	2.38 (1.73-3.17)	2.64 (1.85-3.60)	2.90 (1.95-4.06)	3.24 (2.10-4.66)	3.50 (2.21-5.12)				
2-hr	1.45 (1.13-1.82)	1.68 (1.31-2.11)	2.04 (1.59-2.58)	2.35 (1.81-2.98)	2.77 (2.07-3.62)	3.09 (2.26-4.10)	3.42 (2.42-4.64)	3.76 (2.54-5.23)	4.22 (2.75-6.04)	4.59 (2.91-6.67)				
3-hr	1.68 (1.32-2.10)	1.94 (1.52-2.44)	2.38 (1.85-2.99)	2.73 (2.12-3.45)	3.23 (2.42-4.20)	3.60 (2.64-4.76)	3.99 (2.83-5.41)	4.40 (2.98-6.10)	4.97 (3.24-7.08)	5.42 (3.45-7.85)				
6-hr	2.10 (1.66-2.62)	2.46 (1.94-3.06)	3.04 (2.39-3.80)	3.53 (2.75-4.42)	4.19 (3.16-5.43)	4.69 (3.47-6.18)	5.22 (3.74-7.07)	5.80 (3.94-7.99)	6.63 (4.33-9.38)	7.30 (4.66-10.5)				
12-hr	2.55 (2.02-3.15)	3.03 (2.40-3.75)	3.82 (3.02-4.74)	4.48 (3.51-5.58)	5.39 (4.09-6.95)	6.06 (4.51-7.95)	6.78 (4.90-9.17)	7.60 (5.19-10.4)	8.79 (5.77-12.4)	9.78 (6.26-14.0)				
24-hr	2.96 (2.36-3.63)	3.58 (2.85-4.40)	4.60 (3.65-5.67)	5.45 (4.30-6.73)	6.61 (5.06-8.49)	7.48 (5.60-9.77)	8.41 (6.13-11.3)	9.50 (6.50-12.9)	11.1 (7.31-15.5)	12.5 (8.02-17.7)				
2-day	3.33 (2.67-4.06)	4.08 (3.27-4.97)	5.30 (4.24-6.48)	6.31 (5.02-7.76)	7.71 (5.94-9.85)	8.74 (6.60-11.4)	9.86 (7.25-13.3)	11.2 (7.70-15.2)	13.3 (8.74-18.4)	15.0 (9.66-21.1)				
3-day	3.61 (2.91-4.38)	4.42 (3.56-5.37)	5.75 (4.61-7.00)	6.85 (5.46-8.38)	8.37 (6.46-10.6)	9.49 (7.19-12.3)	10.7 (7.89-14.4)	12.2 (8.38-16.4)	14.4 (9.52-19.9)	16.3 (10.5-22.9)				
4-day	3.87 (3.13-4.69)	4.72 (3.82-5.72)	6.12 (4.92-7.44)	7.28 (5.82-8.88)	8.87 (6.87-11.3)	10.1 (7.63-13.0)	11.3 (8.37-15.2)	12.9 (8.88-17.3)	15.2 (10.1-21.0)	17.2 (11.1-24.1)				
7-day	4.60 (3.74-5.54)	5.54 (4.49-6.67)	7.06 (5.71-8.53)	8.32 (6.69-10.1)	10.1 (7.83-12.7)	11.4 (8.65-14.6)	12.8 (9.42-16.9)	14.4 (9.97-19.2)	16.9 (11.2-23.1)	19.0 (12.3-26.4)				
10-day	5.32 (4.34-6.38)	6.31 (5.14-7.57)	7.92 (6.42-9.53)	9.25 (7.46-11.2)	11.1 (8.64-13.9)	12.5 (9.49-15.9)	13.9 (10.3-18.3)	15.6 (10.8-20.8)	18.1 (12.0-24.7)	20.2 (13.1-28.0)				
20-day	7.50 (6.16-8.94)	8.61 (7.06-10.3)	10.4 (8.50-12.4)	11.9 (9.67-14.3)	14.0 (10.9-17.3)	15.5 (11.9-19.5)	17.2 (12.6-22.1)	18.9 (13.2-24.9)	21.3 (14.2-28.8)	23.2 (15.1-31.9)				
30-day	9.32 (7.68-11.1)	10.5 (8.66-12.5)	12.5 (10.2-14.9)	14.1 (11.5-16.9)	16.3 (12.8-20.1)	18.0 (13.8-22.5)	19.8 (14.5-25.3)	21.5 (15.1-28.2)	23.8 (16.0-32.1)	25.6 (16.7-35.1)				
45-day	11.6 (9.59-13.7)	12.9 (10.7-15.3)	15.0 (12.4-17.8)	16.8 (13.7-20.0)	19.3 (15.1-23.5)	21.2 (16.2-26.2)	23.0 (16.9-29.2)	24.8 (17.4-32.4)	27.1 (18.2-36.4)	28.7 (18.8-39.3)				
60-day	13.5 (11.2-15.9)	14.9 (12.3-17.6)	17.2 (14.2-20.3)	19.1 (15.7-22.7)	21.7 (17.1-26.4)	23.8 (18.2-29.3)	25.8 (18.9-32.5)	27.6 (19.5-36.0)	29.9 (20.2-40.1)	31.5 (20.6-43.0)				


¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).


Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.

Please refer to NOAA Atlas 14 document for more information.

Back to Top

PF graphical





Duration 5-min 2-day 10-min 3-day 4-day 15-min 30-min 7-day 60-min 10-day 20-day 2-hr 3-hr 30-day 6-hr 45-day 12-hr 60-day 24-hr

NOAA Atlas 14, Volume 10, Version 3


Created (GMT): Tue Jan 5 15:37:19 2021

Back to Top

Maps & aerials

Small scale terrain

Precipitation Frequency Data Server



Large scale terrain





Large scale aerial

Precipitation Frequency Data Server



Back to Top

US Department of Commerce National Oceanic and Atmospheric Administration National Weather Service National Water Center 1325 East West Highway Silver Spring, MD 20910 Questions?: <u>HDSC.Questions@noaa.gov</u>

Disclaimer

HYDROGRAPH SUMMARY REPORTS – EXISTING AND PROPOSED CONDITIONS 1-YR., 10-YR. & 100-YR.

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	8.397	2	728	32,242				EX-DA1
3	SCS Runoff	7.966	2	728	31,000				PR-DA1
4	SCS Runoff	3.947	2	728	16,751				Roof
6	Reservoir	1.712	2	744	16,748	4	367.38	3,343	Roof Basin
8	Combine	9.386	2	728	47,747	3, 6,			Proposed
2021-01 Armonk, NY Hydro.gpw				Return I	Period: 1 Ye	ear	Monday, 0	7 / 12 / 2021	

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 1

Hydrograph type	= SCS Runoff	Peak discharge	= 8.397 cfs
Storm frequency	= 1 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 32,242 cuft
Drainage area	= 5.540 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 2.96 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(2.020 x 61) + (3.520 x 98)] / 5.540




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 3

PR-DA1

Hydrograph type	= SCS Runoff	Peak discharge	= 7.966 cfs
Storm frequency	= 1 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 31,000 cuft
Drainage area	= 3.900 ac	Curve number	= 92*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 2.96 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(2.630 x 98) + (1.270 x 80)] / 3.900




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 4

SCS Runoff	Peak discharge	= 3.947 cfs
1 yrs	Time to peak	= 728 min
2 min	Hyd. volume	= 16,751 cuft
1.640 ac	Curve number	= 98*
0.0 %	Hydraulic length	= 0 ft
User	Time of conc. (Tc)	= 10.00 min
2.96 in	Distribution	= Type III
24 hrs	Shape factor	= 484
	l yrs 2 min 1.640 ac 0.0 % Jser 2.96 in	I yrsTime to peak2 minHyd. volume1.640 acCurve number0.0 %Hydraulic lengthJserTime of conc. (Tc)2.96 inDistribution

* Composite (Area/CN) = [(1.640 x 98)] / 1.640




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 6

Roof Basin

Hydrograph type	= Reservoir	Peak discharge	= 1.712 cfs
Storm frequency	= 1 yrs	Time to peak	= 744 min
Time interval	= 2 min	Hyd. volume	= 16,748 cuft
Inflow hyd. No.	= 4 - Roof	Max. Elevation	= 367.38 ft
Reservoir name	= UDET-1	Max. Storage	= 3,343 cuft

Storage Indication method used.



Pond Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Pond No. 1 - UDET-1

Pond Data

UG Chambers -Invert elev. = 365.90 ft, Rise x Span = 5.00 x 5.00 ft, Barrel Len = 160.00 ft, No. Barrels = 5, Slope = 0.30%, Headers = Yes


Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	365.90	n/a	0	0
0.55	366.45	n/a	473	473
1.10	367.00	n/a	1,491	1,964
1.64	367.54	n/a	1,978	3,942
2.19	368.09	n/a	2,243	6,184
2.74	368.64	n/a	2,360	8,545
3.29	369.19	n/a	2,361	10,906
3.84	369.74	n/a	2,241	13,147
4.38	370.28	n/a	1,978	15,125
4.93	370.83	n/a	1,489	16,614
5.48	371.38	n/a	472	17,086

Culvert / Orifice Structures

	[A]	[B]	[C]	[PrfRsr]		[A]	[B]	[C]	[D]
Rise (in)	= 18.00	2.25	8.00	0.00	Crest Len (ft)	= 2.75	0.00	0.00	0.00
Span (in)	= 18.00	2.25	8.00	0.00	Crest El. (ft)	= 367.55	0.00	0.00	0.00
No. Barrels	= 1	1	1	0	Weir Coeff.	= 3.33	3.33	3.33	3.33
Invert El. (ft)	= 365.90	365.90	365.80	0.00	Weir Type	= Rect			
Length (ft)	= 116.00	0.50	0.50	0.00	Multi-Stage	= Yes	No	No	No
Slope (%)	= 0.70	0.00	0.00	n/a					
N-Value	= .013	.013	.013	n/a					
Orifice Coeff.	= 0.60	0.60	0.60	0.60	Exfil.(in/hr)	= 0.000 (by	Wet area)		
Multi-Stage	= n/a	Yes	Yes	No	TW Elev. (ft)	= 0.00			

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).




Weir Structures

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 8

Proposed

Hydrograph type	= Combine	Peak discharge	= 9.386 cfs
Storm frequency	= 1 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 47,747 cuft
Inflow hyds.	= 3, 6	Contrib. drain. area	= 3.900 ac



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	11.29	2	728	43,265				EX-DA1
3	SCS Runoff	10.08	2	728	39,614				PR-DA1
4	SCS Runoff	4.797	2	728	20,543				Roof
6	Reservoir	2.094	2	744	20,540	4	367.63	4,296	Roof Basin
8	Combine	11.64	2	728	60,154	3, 6,			Proposed
2021-01 Armonk, NY Hydro.gpw				Return	Period: 2 Ye	 ear	Monday, 0	7 / 12 / 2021	

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 1

Hydrograph type	= SCS Runoff	Peak discharge	= 11.29 cfs
Storm frequency	= 2 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 43,265 cuft
Drainage area	= 5.540 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 3.58 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(2.020 x 61) + (3.520 x 98)] / 5.540




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 3

PR-DA1

Hydrograph type	= SCS Runoff	Peak discharge	= 10.08 cfs
Storm frequency	= 2 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 39,614 cuft
Drainage area	= 3.900 ac	Curve number	= 92*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 3.58 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(2.630 x 98) + (1.270 x 80)] / 3.900




10

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 4

Hydrograph type	= SCS Runoff	Peak discharge	= 4.797 cfs
Storm frequency	= 2 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 20,543 cuft
Drainage area	= 1.640 ac	Curve number	= 98*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 3.58 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(1.640 x 98)] / 1.640




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 6

Roof Basin

Hydrograph type	= Reservoir	Peak discharge	= 2.094 cfs
Storm frequency	= 2 yrs	Time to peak	= 744 min
Time interval	= 2 min	Hyd. volume	= 20,540 cuft
Inflow hyd. No.	= 4 - Roof	Max. Elevation	= 367.63 ft
Reservoir name	= UDET-1	Max. Storage	= 4,296 cuft

Storage Indication method used.




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 8

Proposed

Hydrograph type	= Combine	Peak discharge	= 11.64 cfs
Storm frequency	= 2 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 60,154 cuft
Inflow hyds.	= 3, 6	Contrib. drain. area	= 3.900 ac



13

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	20.27	2	728	78,521				EX-DA1
3	SCS Runoff	16.38	2	728	66,129				PR-DA1
4	SCS Runoff	7.348	2	728	32,001				Roof
6	Reservoir	4.896	2	738	31,998	4	368.03	5,930	Roof Basin
8	Combine	19.36	2	730	98,127	3, 6,			Proposed
202	21-01 Armoni	<, NY Hyd	ro.gpw		Return F	Period: 10 Y	/ /ear	Monday, 07	/ 12 / 2021

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 1

Hydrograph type	= SCS Runoff	Peak discharge	= 20.27 cfs
Storm frequency	= 10 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 78,521 cuft
Drainage area	= 5.540 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 5.45 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(2.020 x 61) + (3.520 x 98)] / 5.540




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 3

PR-DA1

Hydrograph type	= SCS Runoff	Peak discharge	= 16.38 cfs
Storm frequency	= 10 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 66,129 cuft
Drainage area	= 3.900 ac	Curve number	= 92*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 5.45 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(2.630 x 98) + (1.270 x 80)] / 3.900




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 4

Hydrograph type	= SCS Runoff	Peak discharge	= 7.348 cfs
Storm frequency	= 10 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 32,001 cuft
Drainage area	= 1.640 ac	Curve number	= 98*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 5.45 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(1.640 x 98)] / 1.640




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 6

Roof Basin

Hydrograph type = Rese	ervoir Peak discharge	e = 4.896 cfs
Storm frequency = 10 yr	rs Time to peak	= 738 min
Time interval = 2 mir	n Hyd. volume	= 31,998 cuft
Inflow hyd. No. = 4 - R	Roof Max. Elevation	= 368.03 ft
Reservoir name = UDE	T-1 Max. Storage	= 5,930 cuft

Storage Indication method used.




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 8

Proposed

Hydrograph type	= Combine	Peak discharge	= 19.36 cfs
Storm frequency	= 10 yrs	Time to peak	= 730 min
Time interval	= 2 min	Hyd. volume	= 98,127 cuft
Inflow hyds.	= 3, 6	Contrib. drain. area	= 3.900 ac
innow nyus.	- 3, 0		- 3.900 ac



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	25.88	2	728	101,216				EX-DA1
3	SCS Runoff	20.25	2	728	82,779				PR-DA1
4	SCS Runoff	8.926	2	728	39,115				Roof
6	Reservoir	6.638	2	736	39,112	4	368.21	6,680	Roof Basin
8	Combine	25.21	2	730	121,891	3, 6,			Proposed
202	21-01 Armoni	k, NY Hyd	lro.gpw		Return F	Period: 25 \	⁄ear	Monday, 0	7 / 12 / 2021

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 1

Hydrograph type	= SCS Runoff	Peak discharge	= 25.88 cfs
Storm frequency	= 25 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 101,216 cuft
Drainage area	= 5.540 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 6.61 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(2.020 x 61) + (3.520 x 98)] / 5.540




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 3

Hydrograph type	= SCS Runoff	Peak discharge	= 20.25 cfs
Storm frequency	= 25 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 82,779 cuft
Drainage area	= 3.900 ac	Curve number	= 92*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 6.61 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(2.630 x 98) + (1.270 x 80)] / 3.900




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 4

Hydrograph type	= SCS Runoff	Peak discharge	= 8.926 cfs
Storm frequency	= 25 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 39,115 cuft
Drainage area	= 1.640 ac	Curve number	= 98*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 6.61 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(1.640 x 98)] / 1.640




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 6

Roof Basin

Hydrograph type	= Reservoir	Peak discharge	= 6.638 cfs
Storm frequency	= 25 yrs	Time to peak	= 736 min
Time interval	= 2 min	Hyd. volume	= 39,112 cuft
Inflow hyd. No.	= 4 - Roof	Max. Elevation	= 368.21 ft
Reservoir name	= UDET-1	Max. Storage	= 6,680 cuft


Storage Indication method used.



Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 8

Proposed



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	34.56	2	728	137,070				EX-DA1
3	SCS Runoff	26.21	2	728	108,759				PR-DA1
4	SCS Runoff	11.37	2	728	50,157				Roof
6	Reservoir	8.674	2	736	50,154	4	368.48	7,868	Roof Basin
8	Combine	33.56	2	730	158,914	3, 6,			Proposed
2021-01 Armonk, NY Hydro.gpw			Return F	Return Period: 100 Year Monday, 07 / 12 / 202		/ 12 / 2021			

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 1

Hydrograph type	= SCS Runoff	Peak discharge	= 34.56 cfs
Storm frequency	= 100 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 137,070 cuft
Drainage area	= 5.540 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 8.41 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(2.020 x 61) + (3.520 x 98)] / 5.540




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 3

PR-DA1

Hydrograph type	= SCS Runoff	Peak discharge	= 26.21 cfs
Storm frequency	= 100 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 108,759 cuft
Drainage area	= 3.900 ac	Curve number	= 92*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 8.41 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(2.630 x 98) + (1.270 x 80)] / 3.900




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 4

Hydrograph type	= SCS Runoff	Peak discharge	= 11.37 cfs
Storm frequency	= 100 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 50,157 cuft
Drainage area	= 1.640 ac	Curve number	= 98*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.00 min
Total precip.	= 8.41 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484

* Composite (Area/CN) = [(1.640 x 98)] / 1.640




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No. 6

Roof Basin

Hydrograph type	= Reservoir	Peak discharge	= 8.674 cfs
Storm frequency	= 100 yrs	Time to peak	= 736 min
Time interval	= 2 min	Hyd. volume	= 50,154 cuft
Inflow hyd. No.	= 4 - Roof	Max. Elevation	= 368.48 ft
Reservoir name	= UDET-1	Max. Storage	= 7,868 cuft

Storage Indication method used.




Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020


Hyd. No. 8


Proposed

Hydrograph type	= Combine	Peak discharge	= 33.56 cfs
Storm frequency	= 100 yrs	Time to peak	= 730 min
Time interval	= 2 min	Hyd. volume	= 158,914 cuft
Inflow hyds.	= 3, 6	Contrib. drain. area	= 3.900 ac
-			



WATER QUALITY VOLUME CALCULATIONS





ADS WATER QUALITY UNIT (WQU 4220B) – PRODUCT SPECIFICATION

Water Quality Units





WATER QUALITY UNITS

Standards for storm water quality will vary by location and land use. The most targeted sources of runoff pollution are paved areas in urban and industrial sites. These are generally area with high traffic loads, such as parking lots and gas stations, that generate significant concentrations of contaminant particles and hydrocarbons.

Because of land constraints, ADS underground Water Quality Units have become an increasingly efficient solution for treating storm water. These durable, lightweight structures have been specifically designed for fast installation and easy maintenance.

BENEFITS

- Independent testing shows the following:
 - 80% TSS removal
 - 80% oil & grease removal
 - Greater than 40% TP removal
 - 74% heavy metals removal
- Removes floatable debris such as oils and greases.
- Available in 36" (900 mm) through 60" (1500 mm) diameters.
- Lightweight High Density Polyethylene (HDPE) unit installs easily with a minimum of manpower. Heavy cranes are not necessary to install the unit.
- Each unit is fitted with access risers for easy inspection and maintenance of the sediment and oil chambers.
- The unit is inexpensive because the design is simple and there are no moving parts.
- The bypass system prevents re-suspension of captured solids by diverting water flows greater than the first flush.
- HDPE resists abrasion and chemicals found in storm water and in the surrounding soil.







STANDARD MODELS


Product Number	Diameter in (mm)	Length ft (m)	Inlet Size in (mm)	Outlet Size in (mm)	Treated Flow cfs (L/S)	Sediment Vol. ft³ (m³)	Oil Volume ft ³ (m ³)	Sieve Size
3612WQA	36 (900)	12 (3.7)	10 (250)	10 (250)	0.86 (24)	37 (1.0)	17 (0.5)	140
3612WQB	36 (900)	12 (3.7)	10 (250)	10 (250)	0.43 (12)	37 (1.0)	17 (0.5)	200
3620WQA	36 (900)	20 (6)	10 (250)	10 (250)	1.5 (42)	65 (1.8)	30 (0.8)	140
3640WQA	36 (900)	40 (12)	10 (250)	10 (250)	2.38 (67)	137 (3.9)	63 (1.8)	140
3620WQB	36 (900)	20 (6)	10 (250)	10 (250)	0.7 (20)	65 (1.8)	30 (0.8)	200
3640WQB	36 (900)	40 (12)	10 (250)	10 (250)	1.6 (45)	137 (3.9)	63 (1.8)	200
4220WQA	42 (1050)	20 (6)	12 (300)	12 (300)	1.75 (49)	83 (2.3)	38 (1.1)	140
4240WQA	42 (1050)	40 (12)	12 (300)	12 (300)	3.66 (104)	175 (5.0)	81 (2.3)	140
4220WQB	42 (1050)	20 (6)	12 (300)	12 (300)	0.86 (24)	83 (2.3)	38 (1.1)	200
4240WQB	42 (1050)	40 (12)	12 (300)	12 (300)	1.83 (52)	175 (5.0)	81 (2.3)	200
4820WQA	48 (1200)	20 (6)	12 (300)	12 (300)	2.26 (64)	116 (3.3)	55 (1.6)	140
4840WQA	48 (1200)	40 (12)	12 (300)	12 (300)	3.94 (112)	245 (6.9)	115 (3.3)	140
4820WQB	48 (1200)	20 (6)	12 (300)	12 (300)	1.13 (32)	116 (3.3)	55 (1.6)	200
4840WQB	48 (1200)	40 (12)	12 (300)	12 (300)	2.39 (68)	245 (6.9)	115 (3.3)	200
6020WQA	60 (1500)	20 (6)	15 (375)	15 (375)	2.95 (84)	183 (5.2)	87 (2.5)	140
6040WQA	60 (1500)	40 (12)	15 (375)	15 (375)	6.23 (176)	385 (10.9)	184 (5.2)	140
6020WQB	60 (1500)	20 (6)	15 (375)	15 (375)	1.47 (42)	183 (5.2)	87 (2.5)	200
6040WQB	60 (1500)	40 (12)	15 (375)	15 (375)	3.12 (88)	385 (10.9)	184 (5.2)	200

140 sieve is equal to a particle size of 0.0042" (0.106 mm). 200 sieve is equal to a particle size of 0.0030" (0.075 mm).

DESIGN VARIATIONS

The standard models listed above will provide efficient removal of pollutant particles and hydrocarbons for the majority of site conditions. For unusual conditions, ADS can recommend a system combining a variety of sizes and configurations.

ADS Storm Water Quality Unit



Unit configuration & availability subject to change without notice. Product detail may differ slightly from actual product appearance.

PEAK FLOW RATE

The bypass pipe of the ADS WQU is designed to convey the peak storm water flow of the storm line.

For example, at a 1% slope, peak flow rates for the bypass line are as follows:

	CFS	L/S
12"	3.8419	103.9
15"	6.971	188.0
18"	11.343	307.0
24"	24.451	661.0
30"	44.37	1,240.0
36"	72.19	1,950.0
42"	108.95	2,950.0
48"	1556.1	4,210.0
60"	282.36	7,630.0



DESIGN AND INSTALLATION

Available in 36" (900 mm) through 60" (1500 mm) diameters, ADS Water Quality Units are modified sections of N-12[®] pipe with weir plates at specific locations and heights to remove high percentages of sediment and oils from the first flush of a storm event. They can be installed at any point in the subsurface drainage system and are ideally suited to treat "hot spots" in existing storm water lines.

The unit is designed using the fundamental principles of Stoke's Law and a standard orifice outlet control. The settling velocity of a particle is calculated based on the smallest particle to be removed. Standard units offer a choice of 140 or 200 sieve size removal (106 μ m and 75 μ m particle sizes, respectively).

The outlet orifice is sized to release a typical first flush discharge and to redirect any excess flow to a bypass piping system installed with the unit. All ADS Water Quality Units are designed and manufactured to meet ASTM F2737 - Standard Specification for Corrugated High Density Polyethylene (HDPE) Water Quality Units.

Installation of Water Quality Units follows the same accepted practices as for the installation of large diameter flexible pipe. Specific installation instructions, along with details on specifying the proper size of a Water Quality Unit, are available in Technical Note 1.03 and Installation Guide 2.01. You can also find more information on our website at www.ads-pipe.com. TOP: Setting the Water Quality Unit and the inlet tee fitting

MIDDLE: Bedding and backfilling the unit in 300 mm (12") lifts

BOTTOM: Backfill over the Water Quality Unit and installation of bypass line complete









THE HEART OF THE TREATMENT TRAIN

For many drainage sites, the Water Quality Unit by itself can provide the required degree of pollutant removal. However, certain sites with higher concentrations of hydrocarbons or sediment runoff will need further treatment upstream and/or downstream of the unit. This multi-tiered approach to storm water quality is known as the *treatment train*.

Upstream measures include sediment prevention (vegetated swales, etc.) and inlet protection devices such as screens, filters and silt fences. These techniques are designed to prevent a large percentage of pollutants from ever entering the storm drain system. For impervious surfaces such as paved parking areas, catch basin insert filters are most commonly used for early stage treatment.


RETENTION/DETENTION

Treatment downstream from the Water Quality Unit generally involves some form of retention or detention system. Retention allows accumulated storm water to gradually percolate into the surrounding soil, while detention meters the water through an outlet to a ditch, stream or other receiving area.

Inlet designs to such underground storage vessels can also enhance pollutant removal. The "eccentric header system" consists of a large diameter manifold pipe with an invert positioned lower than those of the smaller inlet pipes to the storage vessels. The large header pipe thus acts as a sump into which suspended particles may settle. Manholes and/or risers may be installed to facilitate inspection and cleaning.

Designers can choose between two methods of constructing the retention or detention system. The first is the use of ADS N-12 large diameter corrugated high density polyethylene pipe, known for its economy and ease of installation. The second option is StormTech[®], specially engineered to meet the demands of subsurface storm water management applications.

ADS supplies a complete line of pipe, fittings and fabricated manifolds, along with detailed sizing, design and installation instructions on our website at www.ads-pipe.com.





The "eccentric header" is installed with its invert lower than the inlet pipes, thus acting as a sump to collect suspended sediment.



ADS STORM WATER QUALITY UNIT PRODUCT SPECIFICATION

SCOPE

This specification describes 36- through 60-inch (900 to 1500 mm) Storm Water Quality Units for use in on-site point source storm water treatment applications.

REQUIREMENTS

Storm Water Quality Units shall have a smooth interior and annular exterior corrugations meeting the requirements of ASTM F2737. The unit shall have at least three containment zones, each zone separated from the next by use of a weir or baffle plate Weir and baffle plates shall be welded at all interfaces between the plate and water quality unit. First weir plate shall incorporate a saw tooth design and shall be reinforced with stiffeners positioned horizontally on the downstream side of the plate to be retained. Storm Water Quality Units shall provide adequate clean-out and inspection access.

JOINT PERFORMACE

Connections for the bypass line and the unit shall utilize the same joint quality as specified for the main storm sewer pipe. Couplers for the bypass line may be either split couplers, in-line bell couplers, bell-bell couplers, or welded bell couplers.

SCOPE MATERIAL PROPERTIES

Virgin material for pipe & fittings used to produce Storm Water Quality Units shall be high density polyethylene conforming with the minimum requirements of cell classification 424420C for 4- through 10-inch (100 to 250) diameters, and 435400C for 12- through 60-inch (300 to 1500 mm) diameters as defined and described in the latest version of ASTM D3350. The virgin pipe material shall be evaluated using the notched constant ligament-stress (NCLS) test as specified in Section 9.5 and 5.1 of AASHTO M294 and ASTM F2306, respectively. All smooth baffle and weir plates shall be high density polyethylene.

INSTALLATION

Installation shall be in accordance with the ADS installation guidelines, utilizing a class I (ASTM D2321) structural backfill material or flowable fill (CLSM – Controlled Low Strength Material). Contact your local ADS representative or visit www.ads-pipe.com for the latest installation instructions.


PERFORMANCE

Water Quality Units shall remove a minimum of 80% of the first flush total suspended solids (TSS) based on flow rates and corresponding sieve sizes shown in Table 1. Water Quality units shall be installed "offline" to prevent re-suspension of solids in high flow situations. Offline installation shall be constructed utilizing an ADS bypass structure. Flow through the unit shall be controlled by an orifice fabricated on the outlet end of the structure.

ADS "Terms and Conditions of Sale" are available on the ADS website, www.ads-pipecanada.com Advanced Drainage Systems, and the Green Stripe are registered trademarks of Advanced Drainage Systems, Inc. Nyloplast[®] is a registered trademark of Nyloplast, Inc. StormTech[®] is a registered trademark of StormTech, LLC. © 2019 Advanced Drainage Systems, Inc. #10505 03/19 MH Advanced Drainage Systems, Inc. 3135 Boomer Line Heidelberg, Ontario NOB 1YO

519-699-0222

www.ads-pipecanada.com









POLLUTION PREVENTION PLAN CERTIFICATION

POLLUTION PREVENTION PLAN CERTIFICATION

"I have read or been advised of the permit conditions and believe that I understand them. I also understand that, under the terms of the permit, there may be reporting requirements. I also certify under penalty of law that this document and all corresponding attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person(s) who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further understand that coverage under the general permit will be identified in the acknowledgement that I will receive as a result of submitting this NOI. I also understand that, by submitting this NOI, I am acknowledging that the SWPPP has been developed and will be implemented as the first element of construction and agree to comply with all the terms and conditions of the general permit for which this NOI is being submitted."

Signed:

_____Date: _____

(Owner/Operator)

(Printed Name & Title)

(Company Name, Address & Telephone Number)

CERTIFICATION BY CONTRACTORS

Certification by Contractors

I. Prime Contractor Certification

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the *qualified inspector* during a site inspection. I also understand that the *owner or operator* must comply with the terms and conditions of the most current version of the New York State Pollutant Discharge Elimination System ("SPDES") general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

Prime Contractor:

(Signature)

(Company) (Name)

(Street Address)

(Title)

(Date)

(City, State, Zip Code)

(Phone Number)

II. Sub-Contractor Certification

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the *qualified inspector* during a site inspection. I also understand that the *owner or operator* must comply with the terms and conditions of the most current version of the New York State Pollutant Discharge Elimination System ("SPDES") general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

Sub-Contractor:

(Signature)	(Company) (Name)
	(Street Address)
(Title)	(City, State, Zip Code)
(Date)	(Phone Number)

STORMWATER CONSTRUCTION SITE INSPECTION REPORT

Construction Duration Inspection

Directions:

Inspection Forms will be filled out during the entire construction phase of the project. Required Elements:

- 1. On a site map, indicate the extent of all disturbed site areas and drainage pathways. Indicate site areas that are expected to undergo initial disturbance or significant site work within the next 14-day period.
- 2. Indicate on a site map all areas of the site that have undergone temporary or permanent stabilization.
- 3. Indicate all disturbed site areas that have not undergone active site work during the previous 14-day period.
- 4. Inspect all sediment control practices and record the approximate degree of sediment accumulation as a percentage of sediment storage volume (for example, 10 percent, 20 percent, and 50 percent).
- 5. Inspect all erosion and sediment control practices and record all maintenance requirements such as verifying the integrity of barrier or diversion systems (earthen berms or silt fencing) and containment systems (sediment basins and sediment traps). Identify any evidence of rill or gully erosion occurring on slopes and any loss of stabilizing vegetation or seeding/mulching. Document any excessive deposition of sediment or ponding water along barrier or diversion systems. Record the depth of sediment within containment structures, any erosion near outlet and overflow structures, and verify the ability of rock filters around perforated riser pipes to pass water; and
- 6. Immediately report to the Operator any deficiencies that are identified with the implementation of the SWPPP.

Inspector (Print Name)

Date of Inspection

Qualified Professional (Print Name)

Qualified Professional (Signature)

The above signed acknowledges that, to the best of his/her knowledge, all information provided on the forms is accurate and complete.

Maintaining Water Quality

Yes No N/A

- [] [] [] Is there an increase in turbidity causing a substantial visible contrast to natural conditions?
- [][][] Is there residue from oil and floating substances, visible oil film, or globules or grease?
- [][] All disturbances are within the limits of the approved plans.
- [] [] [] Have receiving lake/bay, stream, and/or wetland been impacted by silt from project?

Housekeeping

1. General Site Conditions

Yes No N/A

- [][][] Is construction site litter and debris appropriately managed?
- [][][] Are facilities and equipment necessary for implementation of erosion and sediment control in working order and/or properly maintained?
- [] [] [] Is construction impacting the adjacent property?
- [][] [] Is dust adequately controlled?

2. Temporary Stream Crossing

Yes No N/A

- [][][] Maximum diameter pipes necessary to span creek without dredging are installed.
- [][][] Installed non-woven geotextile fabric beneath approaches.
- [][][] Is fill composed of aggregate (no earth or soil)?
- [][][] Rock on approaches is clean enough to remove mud from vehicles & prevent sediment from entering stream during high flow.

Runoff Control Practices

1. Excavation Dewatering

Yes No N/A

- [][][] Upstream and downstream berms (sandbags, inflatable dams, etc.) are installed per plan.
- [][][] Clean water from upstream pool is being pumped to the downstream pool.
- [][] Sediment laden water from work area is being discharged to a silt-trapping device.
- [][][] Constructed upstream berm with one-foot minimum freeboard.

2. Level Spreader

Yes No N/A

- [][] Installed per plan.
- [][][Constructed on undisturbed soil, not on fill, receiving only clear, non-sediment laden flow.
- [][] Flow sheets out of level spreader without erosion on downstream edge.

3. Interceptor Dikes and Swales

Yes No N/A

- [][][] Installed per plan with minimum side slopes 2H : IV or flatter.
- [][][] Stabilized by geotextile fabric, seed, or mulch with no erosion occurring.
- [][][] Sediment-laden runoff directed to sediment trapping structure

4. Stone Check Dam

Yes No N/A

- [][] Is channel stable? (Flow is not eroding soil underneath or around the structure).
- [][][] Check is in good condition (rocks in place and no permanent pools behind the structure).
- [][][] Has accumulated sediment been removed?

5. Rock Outlet Protection

Yes No N/A

- [][] Installed per plan?
- [][][] Installed concurrently with pipe installation.

Soil Stabilization

1. Topsoil and Spoil Stockpiles

Yes No N/A

- [][][] Stockpiles are stabilized with vegetation and/or mulch.
- [][][] Sediment control is installed at the toe of the slope.

2. Re-vegetation

Yes No N/A

- [][][] Temporary seeding and mulch have been applied to idle areas.
- [][][] 4 inches minimum of topsoil has been applied under permanent seeding?

Sediment Control

1. Stabilized Construction Entrance

Yes No N/A

- [][][] Stone is clean enough to effectively remove mud from vehicles.
- [][][] Installed per standards and specifications?
- [][] Does all traffic use the stabilized entrance to enter and leave site?
- [][][] Is adequate drainage provided to prevent ponding at entrance?

2. Silt Fence

Yes No N/A

- [][] Installed on Contour, 10 feet from toe of slope (not across conveyance channels).
- [][][Joints constructed by wrapping the two ends together for continuous support.
- [][] Fabric buried 6 inches minimum.
- [][] Posts are stable, fabric is tight and without rips or frayed areas.

Sediment accumulation is ___% of design capacity.

- Storm Drain Inlet Protection (Use for Stone & Block; Filter Fabric; Curb; or, Excavated practices)
 Yes No N/A
 - [][] Installed concrete blocks lengthwise so open ends face outward, not upward.
 - [][] Placed wire screen between No. 3 crushed stone and concrete blocks.
 - [][] Drainage area is 1 acre or less.
 - [][] Excavated area is 900 cubic feet.
 - [][] Excavated side slopes should be 2:1.
 - [][][] 2" x 4" frame is constructed and structurally sound.
 - [][][] Posts 3-foot maximum spacing between posts.
 - [][][] Fabric is embedded 1 to 1.5 feet below ground and secured to frame/posts with staples at max 8-inch spacing.
 - [][] Posts are stable, fabric is tight and without rips or frayed areas.

Sediment accumulation ____% of design capacity.

4. Temporary Sediment Trap

Yes No N/A

[][][] Outlet structure is constructed per the approved plan or drawing.

[][][] Geotextile fabric has been placed beneath rock fill.

Sediment accumulation is ___% of design capacity

5. Temporary Sediment Basin

Yes No N/A

- [][][] Basin and outlet structure constructed per the approved plan.
- [][][] Basin side slopes are stabilized with seed/mulch.
- [][][] Drainage structure flushed and basin surface restored upon removal of sediment basin facility.

Sediment accumulation is ____% of design capacity.

Note: Not all erosion and sediment control practices are included in this listing. Add additional pages to this list as required by site specific design.

Construction inspection checklists for post-development stormwater management practices can be found in Appendix F of the New York Stormwater Management Design Manual.

CORRECTIVE ACTION LOG

Corrective Action Log

Project Name: SWPP Contact:

Inspection Date	Inspector Name(s)	Description of BMP Deficiency	Corrective Action Needed (including planned date/responsible person)	Date Action Taken/ Responsible Person

AMENDMENT LOG

SWPP Amendment Log

Project Name: SWPP Contact:

Amendment No.	Description of the Amendment	Date of Amendment	Amendment Prepared by [Name(s) and Title]
1			
2			
3			
4			
5			
6			
7			
8			
9			

GRADING ACTIVITIES LOG

GRADING AND STABILIZATION ACTIVITIES LOG

Project Name: SWPP Contact:

Date Grading Activity Initiated	Description of Grading Activity	Date Grading Activity Ceased (Indicate Temporary or Permanent)	Date When Stabilization Measures are Initiated	Description of Stabilization Measure and Location

TRAINING LOG

Stormwater Pollution Prevention Training Log

Project Name:			
Project Location:			
Instructor's Name(s):			
Instructor's Title(s):			
Course Location:		Date:	
Course Length (hours):			
Stormwater Training Topic: (che	ck as appropriate)		
Erosion Control BMPs	Emergency Procedures		
□ Sediment Control BMPs	Good Housekeeping BMPs		
□Non-Stormwater BMPs			
Specific Training Objective:			

Attendee Roster: (attach additional pages as necessary)

No.	Name of Attendee	Company
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		

POST CONSTRUCTION STORMWATER MANAGEMENT FACILITIES MAINTENANCE CHECKLISTS

MAINTENANCE WORK ORDER AND CHECKLIST FOR STORMWATER MANAGEMENT FACILITIES

NAME OF FACILITY:	
LOCATION:	DATE:
WEATHER:	WORK STARTED:
MAINTENANCE PERFORMED BY:	WORK COMPLETED:

A. PREVENTATIVE MAINTENANCE				
WORK ITEMS	ITEMS REQUIRED	ITEMS DONE	COMMENTS AND SPECIAL INSTRUCTIONS	
1. GRASS CUTTING				
A. BOTTOMS				
B. EMBANKMENTS AND SIDE SLOPES				
C. PERIMETER AREAS				
D. ACCESS AREAS AND ROADS				
E. OTHERS				
2. GRASS MAINTENANCE				
A. FERTILIZING				
B. RE-SEEDING				
C. DE-THATCHING				
D. PEST CONTROL				
E. OTHERS				
3. VEGETATIVE COVER				
A. FERTILIZING				
B. PRUNING				
C. PEST CONTROL				
D. POISONOUS PLANTS				
E. OTHERS				
4. TRASH AND DEBRIS REMOVAL				
A. BOTTOMS				
B. EMBANKMENTS AND SIDE SLOPES				
C. PERIMETER AREAS				
D. ACCESS AREAS AND ROADS				
E. INLETS				
F. OUTLETS AND TRASH RACKS				
G. OTHERS				
5. SEDIMENT REMOVAL				
A. INLETS				
B. OUTLETS AND TRASH RACKS				
C. LOW FLOW CHANNELS				
D. BOTTOMS				
E. OTHERS				
6. PEST CONTROL				
A. GEESE				
B. MOSQUITO BREEDING				
C. RODENTS / RODENT HOLES				
D. OTHERS				
7. STRUCTURAL REPAIRS				
A. VALVES				
B. SLUICE GATES				
C. PUMPS				
D. FENCE GATES				
E. LOCKS				
F. ACCESS HATCHES	1			
G. OTHER:	1			
8. POND MAINTENANCE	·			
A. AERATION EQUIPMENT				
B. DEBRIS AND TRASH REMOVAL				
C. WEED REMOVAL				
D. OTHER:				
9. OTHER PREVENTIVE MAINTENANCE				
A. PARKING LOT SWEEPING				
B. EMPTYING TRASH RECEPTACLES	1			
C. PUMPS AND VALVES	1			
D. ELECTRICAL PANEL AND WIRING	1			
E. DEWATERING				
F. GRAFFITI REMOVAL				
1. SIVILITII KENIO (AL	1		1	

E. OTHER:		

B. CORRECTIVE MAINTENANCE				
WORK ITEMS	ITEMS REOUIRED	ITEMS DONE	COMMENTS AND SPECIAL INSTRUCTIONS	
1. REMOVAL OF DEBRIS AND SEDIMENT				
2. STRUCTURAL REPAIRS				
3. EMBANKMENTS AND SIDE SLOPES				
4. DEWATERING				
5. BASIN MAINTENANCE				
6. CONTROL OF MOSQUITOES				
7. EROSION REPAIR				
8. FENCE REPAIR				
9. SNOW AND ICE REMOVAL				
10. SAND LAYER REPLACEMENT				
11. OTHER				

C. AESTHETIC MAINTENANCE			
WORK ITEMS	ITEMS REQUIRED	ITEMS DONE	COMMENTS AND SPECIAL INSTRUCTIONS
1. GRAFFITI REMOVAL			
I. UKAFITII KEMOVAL			I
2. GRASS TRIMMING			
3. WEEDING			
4. OTHERS			

GENERAL NOTES AND REMARKS:

WORK ORDER PREPARED BY:

WORK COMPLETED BY:

DRAINAGE AREA MAPS

