

Section I- PROJECT

TOWN OF NORTH CASTLE

WESTCHESTER COUNTY 17 Bedford Road Armonk, New York 10504-1898

RESIDENTIAL PROJECT REVIEW COMMITTEE Adam R. Kaufman AICP, Chair Telephone: (914) 273-3000 x 43 Fax: (914) 273-3554 www.nortcastleny.com

RESIDENTIAL PROJECT REVIEW COMMITTEE (RPRC) APPLICATION

ADDRESS: 7 HEMLOCK HO	DLLOW PLACE, ARMO	NK, NY 10504
Section III- DESCRIPTION OF	WORK:	
PC	OL HOUSE	
Coation III CONTACT INFOR	MATION.	
Section III- CONTACT INFOR	MATION:	
APPLICANT: EVAN MITTMAN		
ADDRESS: 643 BEDFORD ROA	ND, ARMONK, NEW YO	DRK 10504
PHONE: <u>914-273-5700</u> MC	BILE:	EMAIL: tomdio@djdmgmt.com
PROPERTY OWNER: SAME AS A	B∩VF	
ADDRESS:		
		EMAIL:
PROFESSIONAL:: RALPH ALFO	NZETŢI, P.E.	
ADDRESS: 14 SMITH AVENUE, I	MOUNT KISCO, NY 10	549
PHONE: 914.666.9800	MOBILE:	
EMAIL: RALPHA@ALFONZE		
Section IV- PROPERTY INFO		
Zone: R-2A	Tax ID (lot designation)	ON 04-2-20 3



Town of North Castle Residential Project Review Committee

17 Bedford Road Armonk, New York 10504 (914) 273-3542 (914) 273-3554 (fax)

RPRC COMPLETENESS REVIEW FORM

This form represents the standard requirements for a completeness review for all Residential Project Review Committee submissions. Failure to provide all of the information requested will result in a determination that the application is incomplete.

Project Name on Plan: PROPOSED POOL HOUSE					
☐Initial Submittal ■Revised Preliminary					
Street Location: 7 HEMLOCK HOLLOW PLACE					
Zoning District: R-2A Property Acreage: 4.5 Tax Map Parcel ID:					
Date:					
DEPARTMENTAL USE ONLY					
Date Filed: Staff Name:					
Preliminary Plan Completeness Review Checklist Items marked with a are complete, items left blank are incomplete and must be completed, "NA" means not applicable.					
1. Plan prepared by a registered architect or professional engineer					
2. Aerial photo (Google Earth) showing the applicant's entire property and adjacent properties and streets					
3. Map showing the applicant's entire property and adjacent properties and streets					
1. A locator map at a convenient scale					
The proposed location, use and design of all buildings and structures					
3. Existing topography and proposed grade elevations					
7. Location of drives					
B. Location of all existing and proposed site improvements, including drains, culverts, retaining walls and fences					

RPRC COMPLETENESS REVIEW FORM

Page 2

). De	escription of method of water supply and sewage disposal and location of such facilities
	he name and address of the applicant, property owner(s) if other than the applicant and f the planner, engineer, architect, surveyor and/or other professionals engaged to work
	ubmission of a Zoning Conformance Table depicting the plan's compliance with the inimum requirements of the Zoning District
gr. dis	a tree removal permit is being sought, submission of a plan depicting the location and raphical removal status of all Town-regulated trees within the proposed area of sturbance. In addition, the tree plan shall be accompanied by a tree inventory includes unique ID number, the species, size, health condition and removal status of each tree.
	a wetlands permit is being sought, identification of the wetland and the 100-foot wetland uffer.
Planning	formation about the items required herein can be obtained from the North Castle g Department. A copy of the Town Code can be obtained from Town Clerk or on the astle homepage: http://www.northcastleny.com/townhall.html
	On this date, all items necessary for a technical review of the proposed site plan have been submitted and constitute a COMPLETE APPLICATION.



TOWN OF NORTH CASTLE

WESTCHESTER COUNTY 17 Bedford Road Armonk, New York 10504-1898

PLANNING DEPARTMENT Adam R. Kaufman, AICP Director of Planning

Telephone: (914) 273-3542 Fax: (914) 273-3554 <u>www.northcastleny.com</u>

GROSS LAND COVERAGE CALCULATIONS WORKSHEET

Applic	ation Name or Identifying Title:	7 HEMLOCK HOLLOW F	PL Date:	<u>03/19/</u> 2024
Tax Ma	ap Designation or Proposed Lot No.:	94.04-2-29.3	<u></u>	
Gross 1	Lot Coverage			
1.	Total lot Area (Net Lot Area for Lo	ots Created After 12/13/06):		<u>184,017 S.F.</u>
2.	Maximum permitted gross land co	overage (per Section 355-26.C(1)(b)):		20,537 S.F.
3.	BONUS maximum gross land cov	er (per Section 355-26.C(1)(b)):		
0	Distance principal home is beyond x 10 = 0	minimum front yard setback		0
4.	TOTAL Maximum Permitted gr	ross land coverage = Sum of lines 2 and	d 3	20,537 S.F.
5.	Amount of lot area covered by pri existing + 3,437	ncipal building: proposed =		3,437 S.F.
6.	Amount of lot area covered by accompact existing + 472	ressory buildings: proposed =		472 S.F.
7.	Amount of lot area covered by dec output existing + 0	cks: proposed =		0 S.F.
8.	Amount of lot area covered by por O existing + 1,286			1,286 S.F.
9.	Amount of lot area covered by dri output existing + 11,768	veway, parking areas and walkways: _ proposed =		11,768 S.F.
10.	Amount of lot area covered by term 0 existing + 2,358			2,358 S.F.
11.	Amount of lot area covered by ten O existing + 947	nis court, pool and mechanical equip: _ proposed =		947 S.F.
12.	Amount of lot area covered by all existing + 0	other structures: _ proposed =		0 S.F.
13. Pro	posed gross land coverage: T	otal of Lines $5 - 12 =$		20,268 S.F.
does no	13 is less than or eq ual to Line 4, you ject may proceed to the Residential Fot comply with the Town's regulation are and Seal of Professional Propagation	* AN ALL ON ALL		nd coverage regulations and r than Line 4 your proposal



TOWN OF NORTH CASTLE


WESTCHESTER COUNTY 17 Bedford Road Armonk, New York 10504-1898

PLANNING DEPARTMENT Adam R. Kaufman, AICP Director of Planning

Telephone: (914) 273-3542 Fax: (914) 273-3554 www.northcastleny.com

FLOOR AREA CALCULATIONS WORKSHEET


Applicat	ion Name or Identifying Title:	Schwartz Residence	_ Date:	7/18/23
Tax Map	Designation or Proposed Lot No.:	94.04-2-29.3		
Floor Ar	<u>rea</u>			
1.	Total Lot Area (Net Lot Area for L	ots Created After 12/13/06):		184,017 S.F.
2.	Maximum permitted floor area (pe	er Section 355-26.B(4)):		13,900 S.F.
3.	Amount of floor area contained wit 2,464 existing + 0			2,464 S.F.
4.	Amount of floor area contained wit 3,158 existing + 0			3,158 S.F.
5.	Amount of floor area contained wit 969 existing + 0			969 S.F.
6.	Amount of floor area contained wit 932 existing + 388	thin porches capable of being enclosed: _ proposed =		1,320 S.F.
7.	Amount of floor area contained wit output existing + 0	chin basement (if applicable – see definition): _ proposed =		0
8.	Amount of floor area contained wit output existing + 0	chin attic (if applicable – see definition): _ proposed =		0
9.	Amount of floor area contained wit 203 existing + 448	thin all accessory buildings: _ proposed =		651 S.F.
10.	Proposed floor area: Total of Line	s 3 – 9 =		8,562 S.F.
and the p	10 is less than or egaal to Vine 2, your project may proceed to the Residential posal loss/not comply with the To	our proposal complies with the Town's maxing Project Review Committee for review. If Linguistry, and the Town's regulations.	mum floo ne 10 is g	or area regulation reater than Line 2
Signatur	e and Scale Professional Prepaying	y Worksheet	2/29/2 Date	4
Signatul	OF NEW Y	5 WOLKSHOOL	Date	




ALFONZETTI ENGINEERING, P.C. 14 SMITH AVE, MT. KISCO, N.Y. 10549 914-666-9800 INFO@ALFONZETTIENG.COM

7 HEMLOCK HOLLOW ROAD TOWN OF NORTH CASTLE, WESTCHESTER COUNTY, NEW YORK

AERIAL VIEW MARCH 19, 2024








ALFONZETTI ENGINEERING, P.C. 14 SMITH AVE, MT. KISCO, N.Y. 10549 914-666-9800 INFO@ALFONZETTIENG.COM

SCHWARTZ RESIDENCE TOWN OF NORTH CASTLE, WESTCHESTER COUNTY, NEW YORK

GROSS LAND COVERAGE
MARCH 19, 2024







2020 Residential Code Of New York State

	Climatic & Geographic Design Criteria Table R301.2(1)												
Ground					Seismic	Subject	To Dama	ge From	Winter	Ice Shield	Flood	Air Freezing	Mean Annual
Snow Load	Speed (mph)	Topographic Effects	Special Wind Region	Wind-Borne Debris Zone	Design Category	Meathering	Frost Line Depth	Termite	Design Temp.	Underlayment Required	Hazards	Index	Temperature
30 lb/ft	115 mph	No	Yes	Zone I	В	Severe	42"	Very Heavy	Ю°F	Yes	Yes	1500 or Less	50 F

Manual J Design Criteria							
Elevation	Latitude	Minter Heating	Summer Cooling	Altitude Correction Factor	Indoor Design Temperature	Design Temperature Cooling	Heating Temperature Difference
292	41°8' 11"	12	87	None	72	15	60
Cooling Temperature Difference	Mind Velocity Heating	Mind Velocity Cooling	Coincident Wet Bulb	Dally Range	Minter Humidity	Summer Humidity	
12	-	-	72	М	-	-	

General Notes:


7. CAULKING

- I. ALL WORK AND MATERIALS SHALL CONFORM TO ALL LOCAL, COUNTY AND STATE CODES.
- 2. CONTRACTOR SHALL PROVIDE ALL LABOR, MATERIALS AND EQUIPMENT REQUIRED TO FULLY COMPLETE THE JOB. EXCEPT WHERE SPECIFICALLY AGREED ON BY OWNER, JOB SHALL BE READY FOR OCCUPANCY IN A GOOD WORKMANSHIP MANNER WITH ALL WORK DONE AS SHOWN OR REASONABLY INTENDED ON DRAWINGS, IT SHALL INCLUDE BUT NOT BE LIMITED TO THE FOLLOWING:


8. GUTTERS & LEADERS I. BUILDING PERMIT 9. INSULATION 2. INSURANCE IO. GYPSUM BOARD & TAPING 3. EXCAVATION II. STONE & TILE WORK 4. CONCRETE WORK 12. PAINTING & FINISHING


5. CARPENTRY 13. ELECTRICAL 6. ROOFING & FLASHING 14. PLUMBING

See Specification on last page for more information





Residential Structure. See Section 1265.5 For Further Notes On Sign Location. See Title 19 NYCRR Part 1265 For Other Specs

























Excavation:

FOUNDATION: Excavate all earth, boulders, loose and soft rock to the lines and depths indicated on the drawings. All footings to bear on solid, undisturbed earth. Excavate for all utilities as required.

FOOTINGS: To bear 12" below line of solid undisturbed earth. Design of footings are based on 2,000 psi soil. If soil bearing conditions are questionable, contractor shall consult engineer for footing design. Sloped footings shall be 1:2 max. slope. Provide (2) #4 bars continuous (refer to wall section). All footings bearing from rock to soil shall be reinforced with (4) #5 bars (6' min. on both sides of joint). Dowel and pin all footings bearing on rock with a slope greater than 7:12 (30 degrees) w/ #4 dowels @ 24" o/c

FINISH GRADING: Finish grading shall be established to provide surface drainage in all directions away from the pool house and excavated areas.

Concrete & Masonry:

Weathering Condition: Severe

CONCRETE: Shall be a min. F'c = 3,000 psi compressive strenath for footings & foundation walls and F'c = 3500 psi compressive strength for terrace & floors. Concrete shall be "Air Entrained", total air content shall not be less than 5 % or more than 7 %. All concrete work shall conform to the latest American Concrete Institute (ACI) quidelines.

CONCRETE FLOORS: Shall have a smooth, dense steel trowel finish, suitable to receive flooring. Concrete floors in living areas shall have 6 mil. poly vapor barrier and 2" x 24" (min.) rigid polystyrene foam insulation around the perimeter of the slab, where slab is within 2'-0" of grade. Pitch all terrace floors for drainage. (1/8"/ft. min.)

POURED CONCRETE FOUNDATION: Shall comply with the latest edition of American Concrete Institute Specification and shall be plumb, straight, level and true. Forms to be properly constructed to hold concrete. Provide (2) #4 bars located at top and bottom of wall. All reinforcing bars for concrete work shall conform to A.S.T.M. A615 grade 60.

MASONRY: Concrete block shall be load bearing laid level, plumb and straight in a full bed of cement mortar (TYPE "S") with galvanized metal truss-type ties @ 24" horizontal and vertical. All joints to be well tooled. All masonry work shall conform to ACI 530 code and all reinforcement work shall conform to ACI 318-71. Fill top two courses solid with cement mortar.

DAMPROOFING: In areas of high water table or severe soil-water conditions are known to exist, provide 2-ply hot mopped felts, 55 pound roll roofing from top of footing to finished grade. All joints are to be lapped and sealed with adhesive.

Miscellaneous Metals:

STEEL: Shall conform to ASTM specification A-36 for structural steel.

ANCHOR BOLTS: Provide I/2" dia. X I2" with hooked end. Bolts to be placed 6-0" o.c. max., 12" min. from corner and 2 bolts min. per sill. Consult Architect for anchoring in other seismic zone.

Carpentry:

Decay Design Condition: Slight - Moderate Termite Design Condition: Moderate - Heavy. Design Loads;

First Floor Loads	Live Load Dead Load	40 #/sf 12 #/sf
Second Floor Loads	Live Load Dead Load	30 #/sf 12 #/sf
Attic Load (< 4'-6" Headroom)	Live Load Dead Load	20 #/sf 12 #/sf
(> 4'-6" Headroom)	Live Load Dead Load	30 #/sf 12 #/sf
Ground Snow Load	Live Load Dead load	45 #/sf 7 #/sf

Wind Speed Design load: 100 mph

LUMBER: All framing lumber to be stress grade Douglas Fir Larch No. 2 or better.

FRAMING: Framing of the entire house shall be erected plumb, level and true, securely nailed. Joists, studs and rafters shall be doubled above all openings. All flush headers shall be connected with metal joist hangers. Double frame under all partitions parallel to framing. Sizes of joists, sheathing and rafters are shown on plans. Provide solid blocking under all posts. Contractor to provide all fire blocking at all stud wall over 10'-0" high or all horizontal furred spaces at 10'-0" intervals max.

TERMITE SHIELD: Shall be bent Copper with sealed lapped joints (refer to wall section for other information).

SILL PLATES: All wood sill plates that rest on concrete or masonry exterior walls shall be pressure preservatively treated in accordance with AMPA standards or shall be of decay-resistant heartwood of redwood, black locust, or cedars. All sill plates to be set on fiberglass sill sealer or

GLULAM BEAM: Shall be No. 1 Douglas Dir (min. Fb-2200 PSI).

LAMINATED VENEER BEAM: Shall be "Microlam I.9E" by Trus Joist MacMillan or equal, min. fb. 2600. Install as per manufacturer's specifications. Install as per manufacturer's specifications.

SHEATHING: Shall be 1/2" at walls \$ 5/8" at roof exterior grade plywood nailed to each framing member.

WINDOWS & PATIO DOORS TO BE "ANDERSEN" SEE PLANS FOR TYPE, COMPLETE WITH HIGH PERFORMANCE GLASS AND SCREENS. Units to match existing house

EXTERIOR DOORS TO BE "Anderson" OR EQUAL

FIBER-CEMENT SIDING: Shall be Fiber-cement Plank Siding by HARDIPLANK or Equal. Install according to manufacturer's guidelines and details. Provide 3/8" \times 1 1/2" wood starter strip set to true level 1/4" up from bottom edge of siding. Lap siding on 1 1/4" minimum over course below, placing all end joints over stud bearing. Use only galvanized or corrosion resistant fasteners.

INTERIOR DOORS: as per owners specifications

EXTERIOR TRIM: AZEK or equal

INTERIOR TRIM: as per owners specifications

FLOORS: as per owners specifications

ROOFING: All chimneys shall be properly flashed. Provide self-sealing rubberized waterproof membrane (36" wide min.) at all eaves, openings, hips, valleys, and ridges by W.R. Grace and Company or equal (ice and matershield). All roofing shall be installed by qualified roofing contractors, in strict accordance with manufactourer's specifications.

ASPHALT SHINGLE ROOF: Shall be 25 Yr. Asphalt Shingles To Match Existing House laid on 15 lb. roofing felt.

ROOF VENTILATION: Ventilate all attic and rafter spaces with proper sized screened ridge and soffit vents or louvers (see plans).

GYPSUM BOARD: 1/2" nailed with rosin nails according to manufacturer's specifications. All joints to be taped and receive three (3) coats of joint compound. Finish to be smooth and even, ready for painting. Provide 5/8" type "X" aupsum board at both sides at storage room. Water resistant Gupsum Board At Walls and Optional at Ceiling

GUTTERS AND LEADERS: Provide baked aluminum gutters leaders and hardware as required. All leaders and gutters are to be properly supported at all joint areas. Profile to match existing house

INSULATION: Shall be fiberglass batts with vapor barrier. Provide insulation as per Energy Conservation Code


Ceilings adjoining roof: R-30 Exterior Stud Walls: R-21


U <u>ب</u> 2 K15CO, O MOUNT 4 AVENUE, SMITH 0 95 (414) \mathcal{O} m|ock #0||on Plan For Cabana Revision Date Date Feb. 29, 2024 Job No 224-009 Drawing

4

Computer Polyline Entities

Note: Lines Shown are





ALFONZETTI ENGINEERING, P.C.

14 Smith Avenue, Mt. Kisco, NY 10549

(914) 666-9800

Info@AlfonzettiEng.com

Stormwater Pollution Prevention Plan

for

7 Hemlock Hollow Place Town of North Castle

September 18, 2023 Revised: March 19, 2024

ALFONZETTI ENGINEERING, P.C.

14 Smith Avenue, Mt. Kisco, NY 10549

(914) 666-9800

Info@AlfonzettiEng.com

PROJECT: 7 Hemlock Hollow Place

Town of North Castle, NY

SCOPE: Stormwater Pollution Prevention Plan

DATE: September 18, 2023

Revised: March 19, 2024

Introduction:

The subject site is located at 7 Hemlock Hollow Place, in the Town of North Castle, New York. The site consists of vegetation in the form of woods. The applicant is proposing a single-family residence with a pool, patio and pool house. The change in surface cover and addition of impervious surface warrants this drainage assessment.

The subject property's tax map identification is Section 94.04, Block 2, Lot 29.3 and the total lot area is 4.5 acres.

Discussion:

The site is located in an area tributary to the Inland Long Island Sound Basin. Site disturbance is approximately 81,119 S.F. or 1.86 acres.

The proposed improvements to this site, with approximately 1.86 acres of disturbance, require a Stormwater Pollution Prevention Plan as per New York State Department of Environmental Conservation. This stormwater pollution prevention plan complies with New York State Department of Environmental Conservation SPDES General Permit for Stormwater Discharges from Construction Activity—GP-0-20-01, as such this stormwater pollution prevention plan only includes erosion and sediment controls, as the disturbance is greater than 1 acre but is not located in a watershed identified in appendix D of the SPDES Stormwater Permit.

Stormwater Quantity:

Deep test holes and percolation tests were performed on site to determine the suitability of the soil for subsurface detention. The results are shown in the appendix of this report. In addition, the soils in the area of disturbance are classified as Charlton-Chatfield complex, 0 to 15 percent slopes, very rocky and Charlton-Chatfield complex, 15 to 35 percent slopes, very rocky. A hydrologic soil group of 'B' is used.

Revised: March 19, 2024

Page 2

In the existing condition Drainage Study Area 1 consists of the existing wooded area contained in the outline of the proposed impervious driveway.

In the existing condition Drainage Study Area 2 consists of the existing wooded area contained in the outline of the proposed impervious dwelling, patio, pool and pool house.

In the proposed condition Drainage Study Area 1 consists of the proposed impervious driveway.

In the existing condition Drainage Study Area 2 consists of the proposed impervious dwelling, patio, pool and future pool house.

Curve number calculations for the drainage study area are shown in the appendix of this report. The results are shown below:

Drainage Study area	Tributary Area	Area (sf)	Existing Curve Number	Proposed Curve Number
1	Driveway	11,039	55	98
2	Dwelling, Patio, Pool & Pool House	8,520	55	98

Using the curve number, and a 100-year design storm event of 9.2", the existing and proposed conditions were entered using a HydroCad model. To be conservative, existing impervious area on the site was not accounted for in the HydroCad model.

To ensure no off-site flooding occurs as a result of the proposed construction, a subsurface infiltration system is proposed to capture the required storage volume for both drainage studies.

The infiltration system for drainage area 1 is located in the lawn area. The infiltration system consists of thirty (30) 'Cultec' stormwater chambers, model '330XLHD', or approved equal, surrounded by crushed stone and filter fabric.

The infiltration system for drainage area 2 is located in the lawn area. The infiltration system consists of twenty-eight (28) 'Cultec' stormwater chambers, model '330XLHD', or approved equal, surrounded by crushed stone and filter fabric.

Using the dimensions of the chambers, a stone void ratio of 33%, and a design percolation rate of 10 min./inch for drainage study 1 and 20 min./inch for drainage study 2, the peak flow comparison is shown below.

Peak Flow Comparison:

Design Point	Storm Event	Existing Peak Runoff (cfs)	Proposed Peak Runoff (cfs)	Net Change (cfs)
1	100 Year	0.98	0.64	-0.34
2	100 Year	0.76	0.61	-0.15

Calculations and additional information are shown in the appendix of this report. Details are shown on the site plan.

Temporary Erosion Control Measures:

The following is an inventory and description of the temporary erosion control devices proposed on this site.

Revised: March 19, 2024

Page 4

Silt Fence – Silt Fencing consists of a fabric barrier between supporting stakes or posts usually made of wood. The fabric is proposed to capture suspended sediments from construction runoff and also decreases the velocity of the runoff to protect off-site areas. The proposed location of the silt fence is shown on the plans along with details for installing the silt fence.

Anti-Tracking Pad – An Anti-Tracking Pad shall be installed at the construction entrance. The purpose of the Anti-Tracking Pad shall be to dislodge mud, dirt, and debris from construction vehicles prior to these vehicles leaving the construction site. This will ensure the existing roadways are kept clear of sediment. Locations and details of the Anti-Tracking Pad are shown on the plans.

Construction Sequence:

The proposed development is proposed to be constructed in 1 phase. The construction will be in a sequence that will minimize the potential for erosion. Construction is scheduled to begin in the spring of 2023. The general sequence of construction is as follows:

Stakeout, Erosion Control Measures, Clearing

The initial fieldwork shall consist of surveying and staking for disturbance limits and erosion control installation. All trees to be preserved shall be marked and protected prior to the start of clearing operations. Erosion controls shall be installed as shown on the erosion control plan and as per the respective erosion control details. The tree clearing, if any, shall begin prior to the completion of the entire silt fence. Silt fence should not be installed in areas where tree clearing operations will damage silt fence. The silt fence installation will closely follow the tree clearing operations and will be complete prior to tree stump removal. Tree stump removal shall only begin following the installation of the anti-tracking pad at the construction entrance.

Earthwork

After trees/brush/stumps and other vegetation has been removed, the grading operations shall begin and the footing installation will begin. Initial earthwork operations involve the installation of some structural erosion control measures such as soil stockpiles. Any disturbed soil that will not be worked for a period greater than 14 days must be stabilized.

Revised: March 19, 2024

Page 5

Grading/Drainage/Utility Installation

The drainage construction shall begin once the footings have cured, been striped, and backfilled. As the drainage system is installed it shall be protected to ensure sediment does not enter the system. Once land disturbing operations are completed, final grading, seeding, sodding, and other soil stabilizing landscaping may be installed. The infiltration systems shall not be put into service until the contributing area is stabilized.

• Removal of Erosion Control Devices

As areas are stabilized, sediment shall be removed and erosion control devices shall be discarded in an appropriate and lawful manor.

Maintenance:

A maintenance chart is below showing typical maintenance schedule of temporary erosion control devices during construction. The maintenance of the erosion control devices is the responsibility of the contractor.

Revised: March 19, 2024

Page 6

Temporary Erosion Control device maintenance schedule is as follows:

Device			Bi-		Prior to	After
Device	Weekly	Monthly	annually	Annually	Significant	Significant
			alillually		Rainfall	Rainfall
Silt fence		Inspect		Inspect	Inspect	Inspect/clean
Anti-tracking pad	Inspect		Restore			Inspect

Conclusion:

The proposed infiltration systems consisting of a total of fifty-eight (58) 'Cultec' model '330XLHD' stormwater chambers, will mitigate the small increase in stormwater runoff, therefore there should be no adverse impacts due to stormwater as a result of the proposed improvements.

Ralph Alfonzetti, P.E. ALFONZETTI ENGINEERING, P.C.



Schwartz Residence/7 Hemlock Hollow Place Appendix: Stormwater Pollution Prevention Plan

Deep Test Hole Information: (designations are shown on the plan)

Deep Test Hole (DT1)

0-12"	Topsoil
12" – 24"	Brown Sandy Loam
24" – 90"	Fine Gray Sand with Rocks

Revised: March 19, 2024

Page 1

No Ledge / No Water

Percolation Test 1 (PT1) Results: (designations are shown on the plan)
Percolation Test 1 (PT1): 1.7 min./inch*

Deep Test Hole (DT2)

0 – 14"	Topsoil
14" – 24"	Brown Sandy Loam
24" – 84"	Tan Sand with Stones

No Ledge / No Water

Percolation Test (PT) Results: (designations are shown on the plan)
Percolation Test (PT): 17 min./inch*

Note: Percolation tests were conducted as per New York State Design Manual.

^{*} A design percolation of 10 min./inch (6 inch/hour) was used.


^{*} A design percolation of 20 min./inch (3 inch/hour) was used.

Hydrologic Soil Group Map (from USDA):



Revised: March 19, 2024

Page 2



Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
CrC	Charlton-Chatfield complex, 0 to 15 percent slopes, very rocky	В	6.5	57.1%
CsD	Chatfield-Charlton complex, 15 to 35 percent slopes, very rocky	В	1.6	14.3%
CtC	Chatfield-Hollis-Rock outcrop complex, 0 to 15 percent slopes	D	0.1	1.0%
CuD	Chatfield-Hollis-Rock outcrop complex, 15 to 35 percent slopes	D	1.5	13.1%
LcB	Leicester loam, 3 to 8 percent slopes, stony	A/D	1.6	13.7%
Sm	Sun loam, extremely stony	C/D	0.1	0.9%
Totals for Area of Inter	rest	3.	11.4	100.0%

Hydrologic Soil Group-Westchester County, New York

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.


If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition Component Percent Cutoff: None Specified

Tie-break Rule: Higher

HydroCad Report:



Revised: March 19, 2024

Page 6

Revised: March 19, 2024 Page 7

SCHWARTZ 7 HEMLOCK HOLLOW PLACE

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC Printed 3/19/2024

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
19,559	55	Woods, Good, HSG B (EXDSA1, EXDSA2)
11,039	98	Paved Parking, HSG B (PRDSA 1)
4,365	98	Proposed Dwelling (PRDSA2)
2,316	98	Proposed Patio (PRDSA2)
1,008	98	Proposed Pool (PRDSA2)
831	98	Proposed Pool House (PRDSA2)
39,118		TOTAL AREA

Schwartz Residence/7 Hemlock Hollow Place Appendix: Stormwater Pollution Prevention Plan

SCHWARTZ 7 HEMLOCK HOLLOW PLACE

Type III 24-hr 100 YEAR Rainfall=9.20"

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC Printed 3/19/2024

Revised: March 19, 2024

Page 8

Time span=0.00-72.00 hrs, dt=0.01 hrs, 7201 points
Runoff by SCS TR-20 method, UH=SCS
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EXDSA1: EXDSA 1 Runoff Area=11,039 sf 0.00% Impervious Runoff Depth=3.63"

Tc=8.0 min CN=55 Runoff=0.98 cfs 3,342 cf

Subcatchment EXDSA2: EXDSA 2 Runoff Area=8,520 sf 0.00% Impervious Runoff Depth=3.63"

Tc=8.0 min CN=55 Runoff=0.76 cfs 2,580 cf

Subcatchment PRDSA 1: PRDSA 1 Runoff Area=11,039 sf 100.00% Impervious Runoff Depth=8.96"

Tc=6.0 min CN=98 Runoff=2.29 cfs 8,242 cf

Subcatchment PRDSA2: PRDSA 2 Runoff Area=8,520 sf 100.00% Impervious Runoff Depth=8.96"

Tc=6.0 min CN=98 Runoff=1.77 cfs 6,361 cf

Pond SMS1: SMS1-330XLHD Peak Elev=607.71' Storage=2,339 cf Inflow=2.29 cfs 8,242 cf

Discarded=0.16 cfs 7,203 cf Primary=0.64 cfs 1,039 cf Outflow=0.80 cfs 8,242 cf

Pond SMS2: SMS2-330XLHD Peak Elev=607.75' Storage=2,100 cf Inflow=1.77 cfs 6,361 cf

Discarded=0.07 cfs 5,063 cf Primary=0.61 cfs 1,298 cf Secondary=0.00 cfs 0 cf Outflow=0.67 cfs 6,361 cf

Link EXDP1: EXDP1 Inflow=0.98 cfs 3,342 cf

Primary=0.98 cfs 3,342 cf

Link EXDP2: EXDP2 Inflow=0.76 cfs 2,580 cf

Primary=0.76 cfs 2,580 cf

Link PRDP1: PRDP1 Inflow=0.64 cfs 1,039 cf

Primary=0.64 cfs 1,039 cf

Link PRDP2: PRDP2 Inflow=0.61 cfs 1,298 cf

Primary=0.61 cfs 1,298 cf

Total Runoff Area = 39,118 sf Runoff Volume = 20,525 cf Average Runoff Depth = 6.30" 50.00% Pervious = 19,559 sf 50.00% Impervious = 19,559 sf

Revised: March 19, 2024 Page 9

SCHWARTZ 7 HEMLOCK HOLLOW PLACE

Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Summary for Subcatchment EXDSA1: EXDSA 1


Runoff = 0.98 cfs @ 12.12 hrs, Volume= 3,34

3,342 cf, Depth= 3.63"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100 YEAR Rainfall=9.20"

A	rea (sf)	CN E	Description			
	11,039	55 V	Voods, Goo	d, HSG B		
	11,039	1	.00.00% Per	vious Area	i	
Tc (min)	Length (feet)	Slope (ft/ft)	7-02000	Capacity (cfs)	Description	
8.0					Direct Entry, Direct Entry	

Subcatchment EXDSA1: EXDSA 1



SCHWARTZ 7 HEMLOCK HOLLOW PLACE

Type III 24-hr 100 YEAR Rainfall=9.20"

Printed 3/19/2024

Revised: March 19, 2024

Page 10

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC


Summary for Subcatchment EXDSA2: EXDSA 2

Runoff = 0.76 cfs @ 12.12 hrs, Volume= 2,580 cf, Depth= 3.63"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100 YEAR Rainfall=9.20"

A	rea (sf)	CN [Description			
2	8,520	55 \	Woods, Goo	d, HSG B		0
	8,520	1	100.00% Per	vious Area	ı	
Tc (min)	Length (feet)	Slope (ft/ft)	7-02000	Capacity (cfs)	Description	8
8.0		-			Direct Entry, Direct Entry	

Subcatchment EXDSA2: EXDSA 2



SCHWARTZ 7 HEMLOCK HOLLOW PLACE

Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Revised: March 19, 2024

Page 11

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Summary for Subcatchment PRDSA 1: PRDSA 1


Runoff = 2.29 cfs @ 12.08 hrs, Volume=

8,242 cf, Depth= 8.96"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100 YEAR Rainfall=9.20"

	Area (sf)	CN	Description				
•	11,039	98	Paved Parking, HSG B				
	11,039		100.00% lm	pervious Ar	rea		
(mir	c Length) (feet)	Slop (ft/fr		Capacity (cfs)	Description		
6	0				Direct Entry, Direct Entry		

Subcatchment PRDSA 1: PRDSA 1



Revised: March 19, 2024 Page 12

SCHWARTZ 7 HEMLOCK HOLLOW PLACE

Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC


Summary for Subcatchment PRDSA2: PRDSA 2

Runoff = 1.77 cfs @ 12.08 hrs, Volume= 6,361 cf, Depth= 8.96"

Runoff by SCS TR-20 method, UH=SCS, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs Type III 24-hr 100 YEAR Rainfall=9.20"

	Area (sf)	CI	I D	Description				
	4,365	9	3 P	roposed Dy	welling			
•	2,316	9	3 P	roposed Pa	tio			
	1,008	9	3 P	roposed Po	ool			
*	831	9	3 P	Proposed Pool House				
	8,520	9	3 W	Weighted Average				
	8,520		1	00.00% lm	pervious Ar	rea		
	Tc Lengt		lope	7-02010	Capacity	Description		
_(m	in) (feet) (t/ft)	(ft/sec)	(cfs)			
	6.0					Direct Entry, Direct Entry		

Subcatchment PRDSA2: PRDSA 2



Schwartz Residence/7 Hemlock Hollow Place Appendix: Stormwater Pollution Prevention Plan

SCHWARTZ 7 HEMLOCK HOLLOW PLACE

Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Revised: March 19, 2024

Page 13

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Summary for Pond SMS1: SMS1-330XLHD

Inflow Area	a =	11,039 s	f,100.00% Imperviou	s, Inflow Depth =	8.96"	for 100 YEAR event
Inflow	=	2.29 cfs @	12.08 hrs, Volume=	8,242 cf		
Outflow	=	0.80 cfs @	12.34 hrs, Volume=	8,242 cf,	Atten:	= 65%, Lag= 15.6 min
Discarded	=	0.16 cfs @	10.88 hrs, Volume=	7,203 cf		
Primary	=	0.64 cfs @	12.34 hrs, Volume=	1,039 cf		

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs / 2 Peak Elev= 607.71' @ 12.34 hrs Surf.Area= 1,129 sf Storage= 2,339 cf

Plug-Flow detention time= 81.6 min calculated for 8,242 cf (100% of inflow) Center-of-Mass det. time= 81.6 min (821.2 - 739.6)

Volume	Invert	Avail.Storage	Storage Description
#1A	604.25'	804 cf	25.67'W x 44.00'L x 3.54'H Field A
			4,000 cf Overall - 1,565 cf Embedded = 2,435 cf x 33.0% Voids
#2A	604.75	1,565 cf	Cultec R-330XL x 30 Inside #1
			Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf
			Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap
		2,368 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	604.25'	6.000 in/hr Exfiltration over Surface area
#2	Primary	607.00	6.0" Vert. Orifice/Grate C= 0.600

Discarded OutFlow Max=0.16 cfs @ 10.88 hrs HW=604.29' (Free Discharge) 1=Exfiltration (Exfiltration Controls 0.16 cfs)

Primary OutFlow Max=0.64 cfs @ 12.34 hrs HW=607.71' (Free Discharge) 2=Orifice/Grate (Orifice Controls 0.64 cfs @ 3.28 fps)

Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Revised: March 19, 2024

Page 14

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Pond SMS1: SMS1-330XLHD - Chamber Wizard Field A

Chamber Model = Cultec R-330XL

Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap

52.0" Wide + 6.0" Spacing = 58.0" C-C


6 Chambers/Row x 7.00' Long = 42.00' + 12.0" End Stone x 2 = 44.00' Base Length 5 Rows x 52.0" Wide + 6.0" Spacing x 4 + 12.0" Side Stone x 2 = 25.67' Base Width 6.0" Base + 30.5" Chamber Height + 6.0" Cover = 3.54' Field Height

30 Chambers x 52.2 cf = 1,564.7 cf Chamber Storage

3,999.7 cf Field - 1,564.7 cf Chambers = 2,435.0 cf Stone x 33.0% Voids = 803.6 cf Stone Storage

Stone + Chamber Storage = 2,368.3 cf = 0.054 af

30 Chambers 148.1 cy Field 90.2 cy Stone






Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Pond SMS1: SMS1-330XLHD



Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Revised: March 19, 2024

Page 16

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Summary for Pond SMS2: SMS2-330XLHD

Inflow Area	=	8,520 s	f,100.00% I	mpervious,	Inflow Depth =	8.96"	for 100 YEAR event
Inflow =		1.77 cfs @	12.08 hrs,	Volume=	6,361 cf		
Outflow =	=	0.67 cfs @	12.31 hrs,	Volume=	6,361 cf,	Atten=	62%, Lag= 13.7 min
Discarded =	=	0.07 cfs @	9.22 hrs,	Volume=	5,063 cf		
Primary =		0.61 cfs @	12.31 hrs,	Volume=	1,298 cf		
Secondary =		0.00 cfs @	0.00 hrs,	Volume=	0 cf		

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs / 2 Peak Elev= 607.75' @ 12.31 hrs Surf.Area= 986 sf Storage= 2,100 cf

Plug-Flow detention time= 179.3 min calculated for 6,360 cf (100% of inflow) Center-of-Mass det. time= 179.3 min (918.8 - 739.6)

Volume	Invert	Avail.Storage	Storage Description
#1A	604.30'	670 cf	19.33'W x 51.00'L x 3.54'H Field A
			3,492 cf Overall - 1,460 cf Embedded = 2,032 cf x 33.0% Voids
#2A	604.80	1,460 cf	Cultec R-330XL x 28 Inside #1
			Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf
			Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap
		2,131 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	604.30	3.000 in/hr Exfiltration over Horizontal area
#2	Primary	607.00'	6.0" Round Culvert L= 19.3' CPP, square edge headwall, Ke= 0.500 Outlet Invert= 606.80' S= 0.0104 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior
#3	Secondary	607.75	24.0" x 24.0" Horiz, Orifice/Grate C= 0.600 Limited to weir flow at low heads

Discarded OutFlow Max=0.07 cfs @ 9.22 hrs HW=604.34' (Free Discharge)
1=Exfiltration (Exfiltration Controls 0.07 cfs)

Primary OutFlow Max=0.61 cfs @ 12.31 hrs HW=607.75' (Free Discharge)
2=Culvert (Barrel Controls 0.61 cfs @ 3.08 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=604.30' (Free Discharge)

-3=Orifice/Grate (Controls 0.00 cfs)

Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Revised: March 19, 2024

Page 17

Prepared by Alfonzetti Engineering, P.C.
HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Pond SMS2: SMS2-330XLHD - Chamber Wizard Field A

Chamber Model = Cultec R-330XL

Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap

52.0" Wide + 0.0" Spacing = 52.0" C-C


7 Chambers/Row x 7.00' Long = 49.00' + 12.0" End Stone x 2 = 51.00' Base Length 4 Rows x 52.0" Wide + 12.0" Side Stone x 2 = 19.33' Base Width 6.0" Base + 30.5" Chamber Height + 6.0" Cover = 3.54' Field Height

28 Chambers x 52.2 cf = 1,460.4 cf Chamber Storage

3,492.1 cf Field - 1,460.4 cf Chambers = 2,031.7 cf Stone x 33.0% Voids = 670.5 cf Stone Storage

Stone + Chamber Storage = 2,130.9 cf = 0.049 af

28 Chambers 129.3 cy Field 75.2 cy Stone






Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Pond SMS2: SMS2-330XLHD



Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Revised: March 19, 2024

Page 19

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Summary for Link EXDP1: EXDP1


Inflow Area = 11,039 sf, 0.00% Impervious, Inflow Depth = 3.63" for 100 YEAR event

Inflow = 0.98 cfs @ 12.12 hrs, Volume= 3,342 cf

Primary = 0.98 cfs @ 12.12 hrs, Volume= 3,342 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link EXDP1: EXDP1



SCHWARTZ 7 HEMLOCK HOLLOW PLACE

Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Summary for Link EXDP2: EXDP2


Inflow Area = 8,520 sf, 0.00% Impervious, Inflow Depth = 3.63" for 100 YEAR event

Inflow = 0.76 cfs @ 12.12 hrs, Volume= 2,580 cf

Primary = 0.76 cfs @ 12.12 hrs, Volume= 2,580 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link EXDP2: EXDP2



SCHWARTZ 7 HEMLOCK HOLLOW PLACE

Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Prepared by Alfonzetti Engineering, P.C. HydroCAD® 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Summary for Link PRDP1: PRDP1


Inflow Area = 11,039 sf,100.00% Impervious, Inflow Depth = 1.13" for 100 YEAR event

Inflow = 0.64 cfs @ 12.34 hrs, Volume= 1,039 cf

Primary = 0.64 cfs @ 12.34 hrs, Volume= 1,039 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link PRDP1: PRDP1



Type III 24-hr 100 YEAR Rainfall=9.20" Printed 3/19/2024

Revised: March 19, 2024

Page 22

Prepared by Alfonzetti Engineering, P.C.
HydroCAD* 9.00 s/n 02177 © 2009 HydroCAD Software Solutions LLC

Summary for Link PRDP2: PRDP2


Inflow Area = 8,520 sf,100.00% Impervious, Inflow Depth = 1.83" for 100 YEAR event

Inflow = 0.61 cfs @ 12.31 hrs, Volume= 1,298 cf

Primary = 0.61 cfs @ 12.31 hrs, Volume= 1,298 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link PRDP2: PRDP2



9/29/23, 9:00 AM

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

NOI for coverage under Stormwater General Permit for Construction Activity

version 1.37

(Submission #: HPW-YHJ9-CYD3D, version 1)

Details

Originally Started By Ralph Alfonzetti

Alternate Identifier Schwartz Residence
Submission ID HPW-YHJ9-CYD3D

Submission Reason New Status Draft

Form Input

Owner/Operator Information

Owner/Operator Name (Company/Private Owner/Municipality/Agency/Institution, etc.)

Scott Schwartz

Owner/Operator Contact Person Last Name (NOT CONSULTANT)

Schwartz

Owner/Operator Contact Person First Name

Scott

Owner/Operator Mailing Address

44 Bedford Road

City

Armonk

State

New York

9/29/23, 9:00 AM

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

Zip 10504

Phone

9142735700

Email

tomdio@djdmgmt.com

Federal Tax ID

n/a

If the owner/operator is an organization, provide the Federal Tax ID number, or Employer Identification Number (EIN), in the format xx-xxxxxxx. If the owner/operator is an individual and not an organization, enter "Not Applicable" or "N/A" and do not provide the individual's social security number.

Project Location

Project/Site Name

Schwartz Residence

Street Address (Not P.O. Box)

7 Hemlock Hollow Place

Side of Street

West

City/Town/Village (THAT ISSUES BUILDING PERMIT)

North Castle

State

NY

Zip

10504

DEC Region

3

The DEC Region must be provided. Please use the NYSDEC Stormwater Interactive Map (https://gisservices.dec.ny.gov/gis/stormwater/) to confirm which DEC Region this site is located in. To view the DEC Regions, click on "Other Useful Reference Layers" on the left side of the map, then click on "DEC Administrative Boundary." Zoom out as needed to see the Region boundaries.

For projects that span multiple Regions, please select a primary Region and then provide the additional Regions as a note in Question 39.

9/29/23, 9:00 AM

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

County

WESTCHESTER

Name of Nearest Cross Street

Hemlock Rise

Distance to Nearest Cross Street (Feet)

815

Project In Relation to Cross Street

West

Tax Map Numbers Section-Block-Parcel

94.04-2-29.3

Tax Map Numbers

NONE PROVIDED

If the project does not have tax map numbers (e.g. linear projects), enter "Not Applicable" or "N/A".

1. Coordinates

Provide the Geographic Coordinates for the project site. The two methods are:

- Navigate to the project location on the map (below) and click to place a marker and obtain the XY coordinates.
- The "Find Me" button will provide the lat/long for the person filling out this form. Then pan the map to the correct location and click the map to place a marker and obtain the XY coordinates.

Navigate to your location and click on the map to get the X,Y coordinates 41.15930793149449,-73.67727995672645

Project Details

2. What is the nature of this project?

New Construction

For the purposes of this eNOI, "New Construction" refers to any project that does not involve the disturbance of existing impervious area (i.e. 0 acres). If existing impervious area will be disturbed on the project site, it is considered redevelopment with either increase in impervious area or no increase in impervious area.

3. Select the predominant land use for both pre and post development conditions.

Pre-Development Existing Landuse

Forest

9/29/23, 9:00 AM

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

Post-Development Future Land Use

Single Family Home

3a. If Single Family Subdivision was selected in question 3, enter the number of subdivision lots.

NONE PROVIDED

4. In accordance with the larger common plan of development or sale, enter the total project site acreage, the acreage to be disturbed and the future impervious area (acreage)within the disturbed area.

*** ROUND TO THE NEAREST TENTH OF AN ACRE. ***

Total Site Area (acres)

4.5

Total Area to be Disturbed (acres)

1 C

Existing Impervious Area to be Disturbed (acres)

0.0

Future Impervious Area Within Disturbed Area (acres)

16026.0

5. Do you plan to disturb more than 5 acres of soil at any one time?

No

6. Indicate the percentage (%) of each Hydrologic Soil Group(HSG) at the site.

A (%)

0

B (%)

94.7

C (%)

0

D (%)

5.3

7. Is this a phased project?

Νo

8. Enter the planned start and end dates of the disturbance activities.

9/29/23, 9:00 AM

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

Start Date

10/01/2023

End Date

10/01/2024

9. Identify the nearest surface waterbody(ies) to which construction site runoff will discharge.

Cobamong Pond

Drainage ditches and storm sewer systems are not considered surface waterbodies. Please identify the surface waterbody that they discharge to. If the nearest surface waterbody is unnamed, provide a description of the waterbody, such as, "Unnamed tributary to Niagara River."

9a. Type of waterbody identified in question 9?

Lake Off Site

Other Waterbody Type Off Site Description

NONE PROVIDED

9b. If "wetland" was selected in 9A, how was the wetland identified? NONE PROVIDED

10. Has the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001?

No

11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001?

No

12. Is the project located in one of the watershed areas associated with AA and AA-S classified waters?

Yes

Please use the DEC Stormwater Interactive Map

(https://gisservices.dec.ny.gov/gis/stormwater/) to confirm if this site is located in one of the watersheds of an AA or AA-S classified water. To view the watershed areas, click on "Permit Related Layers" on the left side of the map, then click on "Class AA AAS Watersheds."

If No, skip question 13.

13. Does this construction activity disturb land with no existing impervious cover and where the Soil Slope Phase is identified as D (provided the map unit name is inclusive of slopes greater than 25%), E or F on the USDA Soil Survey? Yes

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

If Yes, what is the acreage to be disturbed?

0.2

14. Will the project disturb soils within a State regulated wetland or the protected 100 foot adjacent area?

No

15. Does the site runoff enter a separate storm sewer system (including roadside drains, swales, ditches, culverts, etc)?

No

16. What is the name of the municipality/entity that owns the separate storm sewer system?

N/A

- 17. Does any runoff from the site enter a sewer classified as a Combined Sewer?
- 18. Will future use of this site be an agricultural property as defined by the NYS Agriculture and Markets Law?

No

19. Is this property owned by a state authority, state agency, federal government or local government?

No

20. Is this a remediation project being done under a Department approved work plan? (i.e. CERCLA, RCRA, Voluntary Cleanup Agreement, etc.)

Required SWPPP Components

- 21. Has the required Erosion and Sediment Control component of the SWPPP been developed in conformance with the current NYS Standards and Specifications for Erosion and Sediment Control (aka Blue Book)?
 Yes
- 22. Does this construction activity require the development of a SWPPP that includes the post-construction stormwater management practice component (i.e. Runoff Reduction, Water Quality and Quantity Control practices/techniques)?

If you answered No in question 22, skip question 23 and the Post-construction Criteria and Post-construction SMP Identification sections.

23. Has the post-construction stormwater management practice component of the SWPPP been developed in conformance with the current NYS Stormwater Management Design Manual?

NONE PROVIDED

9/29/23, 9:00 AM

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

24. The Stormwater Pollution Prevention Plan (SWPPP) was prepared by:

Professional Engineer (P.E.)

SWPPP Preparer

Ralph Alfonzetti P.E.

Contact Name (Last, First)

Alfonzetti Ralph

Mailing Address

14 Smith Avenue

City

Mount Kisco

State

New York

Zip

10549

Phone

9146669800

Email

Info@AlfonzettiEng.com

Download SWPPP Preparer Certification Form

Please take the following steps to prepare and upload your preparer certification form:

- 1) Click on the link below to download a blank certification form
- 2) The certified SWPPP preparer should sign this form
- 3) Scan the signed form
- 4) Upload the scanned document

Download SWPPP Preparer Certification Form

Please upload the SWPPP Preparer Certification

SCHWARTZ - 7 HEMLOCK HOLLOW - SWPPP PREPARER CERTIFICATION FORM PRINTED 2023-09-29.pdf - 09/29/2023 09:00 AM

Comment

NONE PROVIDED

Erosion & Sediment Control Criteria

25. Has a construction sequence schedule for the planned management practices been prepared?

Yes

Revised: March 19, 2024

Page 30

9/29/23, 9:00 AM

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

26. Select all of the erosion and sediment control practices that will be employed on the project site:

Temporary Structural

Silt Fence
Stabilized Construction Entrance

Biotechnical

None

Vegetative Measures

Seeding Sodding Protecting Vegetation Dune Stabilization

Permanent Structural

Rock Outlet Protection

Other

NONE PROVIDED

Post-Construction Criteria

* IMPORTANT: Completion of Questions 27-39 is not required if response to Question 22 is No.

27. Identify all site planning practices that were used to prepare the final site plan/layout for the project.

NONE PROVIDED

27a. Indicate which of the following soil restoration criteria was used to address the requirements in Section 5.1.6("Soil Restoration") of the Design Manual (2010 version).

NONE PROVIDED

28. Provide the total Water Quality Volume (WQv) required for this project (based on final site plan/layout). (Acre-feet)

NONE PROVIDED

29. Post-construction SMP Identification

Use the Post-construction SMP Identification section to identify the RR techniques (Area Reduction), RR techniques(Volume Reduction) and Standard SMPs with RRv Capacity that were used to reduce the Total WQv Required (#28).

Identify the SMPs to be used by providing the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

Note: Redevelopment projects shall use the Post-Construction SMP Identification section to identify the SMPs used to treat and/or reduce the WQv required. If runoff reduction techniques will not be used to reduce the required WQv, skip to question 33a after identifying the SMPs.

- 30. Indicate the Total RRv provided by the RR techniques (Area/Volume Reduction) and Standard SMPs with RRv capacity identified in question 29. (acre-feet) NONE PROVIDED
- 31. Is the Total RRv provided (#30) greater than or equal to the total WQv required (#28)?

NONE PROVIDED

If Yes, go to question 36. If No, go to question 32.

32. Provide the Minimum RRv required based on HSG. [Minimum RRv Required = (P) (0.95) (Ai) / 12, Ai=(s) (Aic)] (acre-feet)
NONE PROVIDED

32a. Is the Total RRv provided (#30) greater than or equal to the Minimum RRv Required (#32)?

NONE PROVIDED

If Yes, go to question 33.

Note: Use the space provided in question #39 to summarize the specific site limitations and justification for not reducing 100% of WQv required (#28). A detailed evaluation of the specific site limitations and justification for not reducing 100% of the WQv required (#28) must also be included in the SWPPP.

If No, sizing criteria has not been met; therefore, NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.

33. SMPs

Use the Post-construction SMP Identification section to identify the Standard SMPs and, if applicable, the Alternative SMPs to be used to treat the remaining total WQv (=Total WQv Required in #28 - Total RRv Provided in #30).

Also, provide the total impervious area that contributes runoff to each practice selected.

NOTE: Use the Post-construction SMP Identification section to identify the SMPs used on Redevelopment projects.

33a. Indicate the Total WQv provided (i.e. WQv treated) by the SMPs identified in question #33 and Standard SMPs with RRv Capacity identified in question #29. (acre-feet)

NONE PROVIDED

Note: For the standard SMPs with RRv capacity, the WQv provided by each practice = the WQv calculated using the contributing drainage area to the practice - provided by the practice. (See Table 3.5 in Design Manual)

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

- 34. Provide the sum of the Total RRv provided (#30) and the WQv provided (#33a). NONE PROVIDED
- 35. Is the sum of the RRv provided (#30) and the WQv provided (#33a) greater than or equal to the total WQv required (#28)?
 NONE PROVIDED

If Yes, go to question 36.

If No, sizing criteria has not been met; therefore, NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.

36. Provide the total Channel Protection Storage Volume (CPv required and provided or select waiver (#36a), if applicable.

CPv Required (acre-feet)

NONE PROVIDED

CPv Provided (acre-feet)

NONE PROVIDED

36a. The need to provide channel protection has been waived because:

NONE PROVIDED

37. Provide the Overbank Flood (Qp) and Extreme Flood (Qf) control criteria or select waiver (#37a), if applicable.

Overbank Flood Control Criteria (Qp)

Pre-Development (CFS)

NONE PROVIDED

Post-Development (CFS)

NONE PROVIDED

Total Extreme Flood Control Criteria (Qf)

Pre-Development (CFS)

NONE PROVIDED

Post-Development (CFS)

NONE PROVIDED

37a. The need to meet the Qp and Qf criteria has been waived because:

NONE PROVIDED

38. Has a long term Operation and Maintenance Plan for the post-construction stormwater management practice(s) been developed?

NONE PROVIDED

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

If Yes, Identify the entity responsible for the long term Operation and Maintenance NONE PROVIDED

39. Use this space to summarize the specific site limitations and justification for not reducing 100% of WQv required (#28). (See question #32a) This space can also be used for other pertinent project information.

NONE PROVIDED

Post-Construction SMP Identification

Runoff Reduction (RR) Techniques, Standard Stormwater Management Practices (SMPs) and Alternative SMPs

Identify the Post-construction SMPs to be used by providing the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

RR Techniques (Area Reduction)

Round to the nearest tenth

Total Contributing Acres for Conservation of Natural Area (RR-1) NONE PROVIDED

Total Contributing Impervious Acres for Conservation of Natural Area (RR-1) NONE PROVIDED

Total Contributing Acres for Sheetflow to Riparian Buffers/Filter Strips (RR-2) NONE PROVIDED

Total Contributing Impervious Acres for Sheetflow to Riparian Buffers/Filter Strips (RR-2)

NONÉ PROVIDED

Total Contributing Acres for Tree Planting/Tree Pit (RR-3)

NONE PROVIDED

Total Contributing Impervious Acres for Tree Planting/Tree Pit (RR-3) NONE PROVIDED

Total Contributing Acres for Disconnection of Rooftop Runoff (RR-4) NONE PROVIDED

RR Techniques (Volume Reduction)

Total Contributing Impervious Acres for Disconnection of Rooftop Runoff (RR-4) NONE PROVIDED

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

Total Contributing Impervious Acres for Vegetated Swale (RR-5)

NONE PROVIDED

Total Contributing Impervious Acres for Rain Garden (RR-6)

NONE PROVIDED

Total Contributing Impervious Acres for Stormwater Planter (RR-7)

NONE PROVIDED

Total Contributing Impervious Acres for Rain Barrel/Cistern (RR-8)

NONE PROVIDED

Total Contributing Impervious Acres for Porous Pavement (RR-9)

NONE PROVIDED

Total Contributing Impervious Acres for Green Roof (RR-10)

NONE PROVIDED

Standard SMPs with RRv Capacity

Total Contributing Impervious Acres for Infiltration Trench (I-1)

NONE PROVIDED

Total Contributing Impervious Acres for Infiltration Basin (I-2)

NONE PROVIDED

Total Contributing Impervious Acres for Dry Well (I-3)

NONE PROVIDED

Total Contributing Impervious Acres for Underground Infiltration System (I-4)

NONE PROVIDED

Total Contributing Impervious Acres for Bioretention (F-5)

NONE PROVIDED

Total Contributing Impervious Acres for Dry Swale (O-1)

NONE PROVIDED

Standard SMPs

Total Contributing Impervious Acres for Micropool Extended Detention (P-1)

NONE PROVIDED

Total Contributing Impervious Acres for Wet Pond (P-2)

NONE PROVIDED

Total Contributing Impervious Acres for Wet Extended Detention (P-3)

NONE PROVIDED

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

Total Contributing Impervious Acres for Multiple Pond System (P-4)
NONE PROVIDED

Total Contributing Impervious Acres for Pocket Pond (P-5)

NONE PROVIDED

Total Contributing Impervious Acres for Surface Sand Filter (F-1)

NONE PROVIDED

Total Contributing Impervious Acres for Underground Sand Filter (F-2)

NONE PROVIDED

Total Contributing Impervious Acres for Perimeter Sand Filter (F-3)

NONE PROVIDED

Total Contributing Impervious Acres for Organic Filter (F-4)

NONE PROVIDED

Total Contributing Impervious Acres for Shallow Wetland (W-1)

NONE PROVIDED

Total Contributing Impervious Acres for Extended Detention Wetland (W-2)

NONE PROVIDED

Total Contributing Impervious Acres for Pond/Wetland System (W-3)

NONE PROVIDED

Total Contributing Impervious Acres for Pocket Wetland (W-4)

NONE PROVIDED

Total Contributing Impervious Acres for Wet Swale (O-2)

NONE PROVIDED

Alternative SMPs (DO NOT INCLUDE PRACTICES BEING USED FOR

PRETREATMENT ONLY)

Total Contributing Impervious Area for Hydrodynamic

NONE PROVIDED

Total Contributing Impervious Area for Wet Vault

NONE PROVIDED

Total Contributing Impervious Area for Media Filter

NONE PROVIDED

"Other" Alternative SMP?

NONE PROVIDED

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

Total Contributing Impervious Area for "Other" NONE PROVIDED

Provide the name and manufaturer of the alternative SMPs (i.e. proprietary practice(s)) being used for WQv treatment.

Note: Redevelopment projects which do not use RR techniques, shall use questions 28, 29, 33 and 33a to provide SMPs used, total WQv required and total WQv provided for the project.

Manufacturer of Alternative SMP

NONE PROVIDED

Name of Alternative SMP NONE PROVIDED

Other Permits

40. Identify other DEC permits, existing and new, that are required for this project/facility.

None

If SPDES Multi-Sector GP, then give permit ID

NONE PROVIDED

If Other, then identify NONE PROVIDED

41. Does this project require a US Army Corps of Engineers Wetland Permit?

If "Yes," then indicate Size of Impact, in acres, to the nearest tenth NONE PROVIDED

42. If this NOI is being submitted for the purpose of continuing or transferring coverage under a general permit for stormwater runoff from construction activities, please indicate the former SPDES number assigned.

NONE PROVIDED

MS4 SWPPP Acceptance

43. Is this project subject to the requirements of a regulated, traditional land use control MS4?

Yes - Please attach the MS4 Acceptance form below

If No, skip question 44

NYSDEC eBusiness Portal System - NOI for coverage under Stormwater General Permit for Construction Activity. Revision 1

44. Has the "MS4 SWPPP Acceptance" form been signed by the principal executive officer or ranking elected official and submitted along with this NOI? Yes

MS4 SWPPP Acceptance Form Download

Download form from the link below. Complete, sign, and upload. MS4 SWPPP Acceptance Form

MS4 Acceptance Form Upload

SCHWARTZ - 7 HEMLOCK HOLLOW - MS4.pdf - 09/27/2023 01:25 PM Comment NONE PROVIDED

Owner/Operator Certification

Owner/Operator Certification Form Download

Download the certification form by clicking the link below. Complete, sign, scan, and upload the form.

Owner/Operator Certification Form (PDF, 45KB)

Upload Owner/Operator Certification Form

SCHWARTZ - 7 HEMLOCK HOLLOW - OWNER CERTIFICATION FORM SIGNED PRINTED 2023-09-29.pdf - 09/29/2023 08:58 AM

Comment

NONE PROVIDED

Attachments

Date	Attachment Name	Context	User
9/29/2023 9:00 AM	SCHWARTZ - 7 HEMLOCK HOLLOW - SWPPP PREPARER CERTIFICATION FORM PRINTED 2023-09-29.pdf	Attachment	Ralph Alfonzetti
9/29/2023 8:58 AM	SCHWARTZ - 7 HEMLOCK HOLLOW - OWNER CERTIFICATION FORM SIGNED PRINTED 2023-09-29.pdf	Attachment	Ralph Alfonzetti
9/27/2023 1:25 PM	SCHWARTZ - 7 HEMLOCK HOLLOW - MS4.pdf	Attachment	Ralph Alfonzetti